

26

מדינת ישראל

משרד ראש הממשלה

גנזך המדינה

4

27

תיק מס'

הגנזך הממלכתי - תל אביב

Historical Sites

1947 - 1938 - תל אביב

מחלקה גנזך הממלכתי - תל אביב

תיק מס' 1/3/1
מיכל מס'

מדינת ישראל
גנזך המדינה



Historical Sites - אתרים היסטוריים

שם:

מ - 4900/27

112.0/6 - 61

02-108-11-11-07

18/07/2005

מזהה פיזי:

מזהה לוגי:

כתובת:

מ

ארץ ישראל

ממשלת המנדט

Fig. 2

Other files dealing with
same Subject

T/3/1

1440

410

I

HISTORICAL SITES

CITY, 815-35,500-55-1-88-5175

Referred to	Date	Referred to	Date	Referred to	Date
				P. A.	Date

D.O.T. MINUTE PAPER

--	--	--

SUBJECT

--

D.O.T. MINUTE PAPER

--	--	--

SUBJECT

(34) Ref 33 ^{o.o.} Is this so? RP 22.2.47


(35) M.M.
pl. speak. hi 26/2

I am not aware of the ~~whereabouts~~
of KR. Jaisuya mentioned in Dir of
Antiquities letter.

Do H/3.

36 ec
pl. reply Do negatively. This Khirbat
is not known to us. hi 5/3

(38) Ref 37 - 39 11/3/47 (13)



ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

11th March, 1947.

District Commissioner,
Samarra District.

Reference your transmission No. 704 dated 15.2.47 dealing with schedule of Historical sites and Monuments etc., I have the honour to inform you that there is no place in Tulkarm Sub-District called Kh. Farisiya.


2. I was informed by the District Officer, Jenin that there is Kh. Farasin which falls under the jurisdiction of Jenin Sub-District.

(Sgd.) A. SINCLAIR

Assistant District Commissioner
Tulkarm.

RM/AT.

P3/12/13



7
1

6/2/19

GOVERNMENT OF PALESTINE.

37

IN REPLY PLEASE QUOTE

No. 704

31/ DISTRICT COMMISSIONER'S OFFICE,
SAMARIA DISTRICT,
NABLUS.

7 March, 1947

Asst. Dist. Commissioner,
Tulkarm

33
I have the honour to refer
to my transmission note No. 704 of the
18th February, 1947, transmitting a
copy of a letter No. ATQ/44, dated the
8th February, 1947, from the Director
of Antiquities, on the subject of schedule
of Historical Sites and to enquire when
I may expect your reply.

Crossed
10/3

Handwritten signature
DISTRICT COMMISSIONER
SAMARIA DISTRICT

Copy to:- Director of Antiquities,
Jerusalem, ref. his ATQ/44
of 1-3-47.

(Copy)

No. ATQ/144

GOVERNMENT OF PALESTINE

DEPARTMENT OF ANTIQUITIES
JERUSALEM
8th February, 1947

District Commissioner,
Samarra

Subject:- Schedule of Historical Sites
and Monuments (Gaz. Extra.
No. 1375 of 24-11-44, Suppl. No. 2)
Reference: Administrative Divisions
(Amendment) Proclamation, 1947,
in Gaz. No. 1552 of 30-1-47.

From the new schedule of administrative divisions it appears that Kh. FARISIYA (Schedule of Historical Sites and Monuments p. 1255) has been transferred from Tulkarm to Jenin Sub-District.

If you would kindly confirm that this is so, I will have the Schedule of Historical Sites and Monuments amended accordingly.

(sgd)
Director of Antiquities

Copy to:- Mr. S.A.S. Hussaini, Inspector of Antiquities, Jerusalem.

PK.

20 FEB 1947

JERUSALEM

704

15.2.47

ad Tulk

pl

20/2

GOVERNMENT OF PALESTINE.

CONTROLLER OF SALVAGE

4 BEN YEHUDA STREET,

P.O. B. 674,

JERUSALEM.

IN REPLYING TO THIS LETTER
PLEASE QUOTE THE DATE AND
REFERENCE NUMBER.

TELEPHONES:
2138 AND 4630; 4839.

شهادة طلاق السيدة مروة حبيب بنوع

صدرت في المحلة الشرعية بطنس في ١٤٧٠ الموافق ١٠ / ١٠ / ١٩٥٨

GPP. 20064-200 Bks-7-6-44

الذهب

المهنة

محل الإقامة

العمر

الاسم

الزوج

محمد بن عبد الله بن حنين

٧

الطبية

ضاح

الزوجة

عمدة بنت يوسف المبروك

٤٥

صديق محمد بن شحاتة

٤٥

الشهود

يوسف بن عبد القادر محمد

٥١

أنا فاضل طوسم الشري

اصدق ان هذه الشهادة مطابقة لاصلها المسجل بنمرة

١١٨ ٤٨ ١١٩

التاريخ ١٠ / ١٠ / ١٩٥٨

التوقيع



ATQ/9(a)/722.

30th April, 1946.

8 JULY 1946

The Chairman,
Samaris Regional T.P. Commission,
District Commissioner's Offices,
Nablus.

Subject : Building applications affecting historical monuments and sites.

I have the honour to refer to your meeting of 30th March, 1946, of the Committee for Arab Areas which was attended by Salem Eff. Hussein, Inspector of Antiquities, and at which means for controlling development on scheduled historical sites were considered.

I confirm the arrangements proposed and adopted by the Commission to this end, subject to the amendment that any application to build on any historical site not already developed should be referred to me, whether the site is an important site (list A) or not (list B).

Accordingly I propose that the resolutions should be amended to read as follows:

- (1) The Department of Antiquities will provide the Secretary, Regional Town Planning Commission, Samaria District, (Arab Areas) with a list of scheduled historical monument and sites in the Samaria District for distribution to the Chairmen of the Building Permit Sub-Committees of Nablus, Jenin and Tulkarm. The lists shall show:
 - (a) the better preserved or more important historical sites in each sub-district, which sites shall be underlined;
 - (b) the sites which contain fewer surface remains, not underlined.
- (2) The Building Permit Sub-Committees will refer to these lists when considering applications for building permits.
- (3) If it is found that any site under (a) is likely to be affected by the proposed works, the application should be referred to the Director of Antiquities for his consent (under Section 18 of the Antiquities Ordinance, 1929) and the Director of Antiquities will arrange with the promoters for the site to be inspected and any necessary modifications in the plans to be made, informing the Committee accordingly.

If it is found that a site listed under (b) is affected, and if the site is not built up in any way, the application shall similarly be referred to the Director of Antiquities. But if the site is already partly or wholly built up, then it shall be sufficient to state in the building permit that works are to be suspended if any antiquities are discovered in the course of the work, and that the discovery is to be reported immediately (under Section 3 of the Antiquities Ordinance, 1929):


Lists as mentioned under (1) above will be sent shortly.

May I suggest that a similar routine arrangement might be considered in the case of Jewish areas also.

(Sgd.) R.W. HAMILTON

DIRECTOR OF ANTIQUITIES.

[illegible]



31A

(Copy)

ATQ/3/44

DEPARTMENT OF ANTIQUITIES
JERUSALEM
5th February, 1946

The District Commissioner, Jerusalem

-do-	Haifa
-do-	Lydda
-do-	Gelilee
-do-	Samaris
-do-	Gaza

Subject:- Schedule of Historical
Monuments and Sites.

I am sending you herewith photographic extracts from the Schedule of Historical Monuments and Sites arranged to show the sites situated in each sub-district separately. These extracts have been made for convenience of District Officers and others who may be concerned with the distribution of sites by sub-districts.

The extracts are from the English schedule only, and the supply is limited. I should be glad to know how many copies of the list for each sub-district separately would be required for the use of Administrative Officers in your District.

(sgd)
DIRECTOR OF ANTIQUITIES

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

63 February, 1946.

The Director of Antiquities,
J e r u s a l e m.
-----Subject:- Qalansawa. Scheduled Historical Site.
Ref'nce:- Your ATQ/562 dated 30.1.46.

The reprimand was administered.

Further I attach an apology and undertaking
from the Mukhtar and Members of the Village Committee addressed
to you through this Office.
Assistant District Commissioner,
Tulkarm.

JS/AT

K/3/2

GOVERNMENT OF PALESTINE.

ממשלת פלשתינה (א"י)

DEPARTMENT OF LANDS.

מחלקת הקרקעות

* N305062 *

and Registry Office of

Name of Payer

Nature of Transaction

Consideration L.P.

Date

מكتب تسجيل اراضي

משרד מס הכנסות

اسم الدافع

نوع المعاملة

طبيعة الصفقة

القيمة

المعاملة

المعاملة (ب.م.)

التاريخ

الرقم

27407-200 Bks-6.11.34 - O.P.

Remarks ملاحظات הערות	Particulars التفاصيل הפרטים	Fees payable الرسوم المتفق عليها מסוימת		
		L.P. ב.מ. (א"י)	Mills מל סל	
39 188 7935	200 Waga Munis			100
Total				100

The sums shown above have been received by me.

استلمت المبالغ المذكورة أعلاه
المذكورة هنا بمقتضى هذا

الى سعادة مدير الآثار المحترم

بواسطة حمزة مساعد حاكم اللسوا في طولكرم

محسنة واحتراما

نحن الموقعين ادناه مختاروا "عصفا" لبيت قرية قلندوة نطلب اليكم بالادارة عن

القرية التي وقعت منا في عدم طلب الاستدانة لرفع القرية القديمة المسماة بالمزار

كما واننا نأسف لعدم اخبارنا اياكم عن عثرتنا على قبر في حفرة اساسات القرية الجديدة

للقرية واننا لنعلمكم ان هكذا حوادث لا تكرر في المستقبل

وسعدوا بقبول فائق احتراما



مختار قاصص

عضو لجنة خايز مصطفى

محمد بنده براهيم

صبري بنده جويو


عبدالله بنده انجب

حمزة بنده ابراهيم



محمد دجاني مع النذور ١٤/٤/٢٧

Handwritten signature or note in the bottom right corner.



الى سعادة مدير الانار المحترم

بواسطة خيسره مساعد حاكم اللسوا في طولكرم

تحية واحتراما

نحن الموقعين ادناه مختار واعضاء لجنة قرية قلندوة نتقدم اليكم بالاعذار عن

الزلة التي وقعت منا في عدم طلب الاستدانة لرفع القرعة القديمة المسماة بالمزار

كما واننا نأسف لعدم اخبارنا اياكم عن عنواننا على قبور في حفرة اساسات القرعة الجديدة

للمدرسة واننا نعتذر لكم ان هكذا حوادث لا تفكر في المستقبل

وتسعدوا بقبول فائق احترامنا



مختار فارس

عضو لجنة فايز مصطفى

محمد بنديز


عبد الله سليم جوي

جنته عيسى

محمد بنديز

محمد بنديز

١٩٤١/٤/٢٦



الى مختار واعضا* لجنة قرية قلنسوة المحترمين

الموضوع :- مخالفة قانون الآثار القديمة .

وجه الي سعادتكم بدور الآثار القديمة كتاب بين فيه أن في نيته محاكمكم
على هدمكم المزار بدون إذن خاص منه وكذلك عدم اعطاء المعلومات عن منحوركم على قبور
عند حفرة اساسا - الفرقة الجديدة للمدرسة .

بنت لسعادتكم بما استعملت عليه منكم في الموضوع وقد وافق سعادتكم
على الاكتفاء* بانذاركم هذه المرة على أن توفروا اليه اعتذار خطي في الموضوع .
انقل اليكم في حبه ٣ نسخ من سورة اعتذار ارجو توقيعكم عليها
واعادتها الي لا تدمها بدورتي الي سعادتكم .

كما واني ارجو الانتباه الكلي الي لزم عدم مخالفة قانون الآثار في المستقبل .

ودمتم

مساعد حاكم اللموا*
بمطولكم

B.F 15/2



27

GOVERNMENT OF PALESTINE

IN REPLY PLEASE QUOTE

No. ATQ/562

ASSISTANT DISTRICT COMMISSIONER'S OFFICE		DEPARTMENT OF ANTIQUITIES.
JERUSALEM.		
2-58-15		30th January, 1946.
TULKARM		

The Assistant District Commissioner,
Tulkarm.

Subject :- Qalansawa. Scheduled
Historical Site.

Reference :- Your T/3/1-26 of -.1.46.

Thank you for your letter. In view
of your explanation I shall take no further
action, but shall be grateful if you will
administer the reprimand as proposed.

R. Hamilton

Director of Antiquities.

B.F. G/2
✓

28

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

14 January, 1946.

The Director of Antiquities,
Jerusalem.Subject:- Qalansawa. Scheduled Historical
Site VI. 148 188.

Ref'nce:- Your ATQ/562 dated 18.1.1946.

El Mazar was demolished by order of the Mukhtar without reference to this Office or to you. The prime object of demolition however was not to supply stone for the school building, which could easily have been got elsewhere, but to stop what had become a village nuisance in that the room in question had come to be frequented by youths with immoral intentions.

The fact that your permission was not sought is regretted and the Mukhtar and Village Committee have been reprimanded and will be reprimanded again in public at the next Mukhtar's Meeting. The Mukhtar is actually the person responsible.

The matter of failing to report the graves found in excavating the foundations for the two new classrooms is also regretted. The rooms in question were sited by a proper Siting Board in accordance with the conditions for orientation laid down by the Dept. of Education. They fall within the perimeter of the school grounds acquired by the village for that purpose and covering an area of several dunums. As the whole of that section appears to be honey-combed with such graves and as the particular graves concerned do not appear to have been of special importance, I feel that, with the exception of failure in the duty to report such, no serious harm has been done.

In view of the above offences under Secs. 18 and 22 of the Antiquities Ordinance having been committed with absolutely no intention of defraud or abuse, I would recommend that prosecution be withheld and a severe reprimand be considered as sufficient plus a written apology and undertaking by the Mukhtar and Village Committee never to omit to seek the necessary permission in future.

Assistant District Commissioner,
Tulkarm.

JS/AT

GOVERNMENT OF PALESTINE

IN REPLY PLEASE QUOTE

No. ATQ/562

DEPARTMENT OF ANTIQUITIES,
JERUSALEM.

18th January, 1946.

The Assistant District Commissioner,
Tulkarm.

Subject :- Qalansuwa. Scheduled Historical
Site VI. 148 188.

I refer to the domed mausoleum situated to the west of the village, and known as El Mazar, which, as I am informed, has been demolished by the Mukhtar with the purpose of utilising the stone for the construction of additional rooms at the village school.

2. This 'domed mausoleum' was mentioned as such in the Schedule of Historical Monuments and Sites published in the Gazette Extraordinary No.1375 of 24.11.1944, Supplement No.2, p.1296, s.v. Qalansuwa.

Therefore under Section 18 of the Antiquities Ordinance, 1929, my permission should have been sought before the building was demolished.

I am informed also that in the digging of foundations for the new rooms at the school some ancient graves were encountered, and that they were not reported as required by Section 3 of the Antiquities Ordinance, 1929, but were destroyed.

3. As regards the demolition of the Mazar I propose to have the person or persons responsible prosecuted under Section 22(6) of the Antiquities Ordinance. But since the Village Administration Ordinance expressly imposes on a Mukhtar the duty of safeguarding scheduled historical sites, I should be glad of your advice as to who is actually responsible before I request the police to take action. I should also be glad of your observations on the second offence, namely, the failure to report the ancient graves discovered on the site of the school, which is punishable under Section 22(1) of the Ordinance.

4. At the same time I have to thank you for drawing attention to the inscribed slab with the inscription and blazon of Malik an-Nasir, which is built into one of the graves in the modern cemetery. This is also mentioned in the Schedule (under Qalansuwa, reference as above). But if you think it advisable to remove it for safety to this Museum, I should be glad to acquire it in exchange for a new stone and would be grateful if you could arrange this on my behalf.

Mustammil

Director of Antiquities.

Copy to: Mr. Ory, Inspector of Antiquities, P.O.B.1368,
Tel-Aviv, ref. his S.3292 of 7.1.46.

See p. 26

مكتب مساعد حاكم اللوات* بمطولكم

١١٤٦/١/١٤

الرقم - ط/٢/١

الى مختار قرية قنيسوة المحنة

ارجو حذورك الى هذه الدائرة لمواجهتي في يوم

الاثنين الواقع في ١٤/١/١١٤٦ .

وديت



مساعد حاكم اللوات*

بمطولكم

حكومة فلسطين

ממשלת פלשתינה (א"י)

REVENUE TAX RECEIPT

وصل بالضريبة التحصيل

קבלה על מסים

No. D 302454

District	لواء	Intalment	مقسمة
Sub-District	مقاطعة	Register No.	رقم السجل
Village	قرية	Polio No.	رقم الصفحة
Kind of Taxes	نوع الضرائب	Area	مساحة
House and Land Tax	ضريبة المنازل والأراضي	ل.ف. ميل	ل.ف. ميل
Rural Property Tax	ضريبة الأملاك في القرى	ل.ف. ميل	ل.ف. ميل
Urban Property Tax	ضريبة الأملاك في المدن	ل.ف. ميل	ل.ف. ميل
Animal Tax	ضريبة الحيوانات	ل.ف. ميل	ل.ف. ميل
Tithes	اعشار	ل.ف. ميل	ل.ف. ميل
TOTAL	المجموع من كل	ل.ف. ميل	ل.ف. ميل

Received from

the sum of

on a/c of

Date

Sub-District

التاريخ

Signature

الموقع

ووصل من

مبلغ

على حساب

في

التاريخ

الموقع

الموقع

A Dept. of Antiquities
Inspector called yesterday at
12.30 pm. stating that damage
had been reported to a historical
site at Qalansawa.

I took him there. A dome
(no) known as Sheikh Hussein had
been demolished by the lumberer to
get stone for the school. This ~~later~~
apparently should have been ~~done~~ ^{allowed}
only after permission had been sought
from ~~this Dept.~~

The Insp. further pointed out
that before the foundations for the
new classrooms had been dug, per-
mission should also have been
secured.

A list of ~~historical~~ archaeological
sites as requested by the Dept. is attached.
Siting Boards to take note of. H 8/1

URBAN PROPERTY TAX ORDINANCE.

قالون ضريبة الاملاك في المدن
מקורות מס הרכוש העירוני.

NOTICE OF VALUATION.

הרדעה בנדרין שומא
اعلان التخمين

Urban Area of

Co. 10. 10000

No. 288877

22

Take Notice

that the property described hereunder, which you are stated to be the reputed owner, has been assessed in respect of the Property Tax as follows:-

ليكن معلوماً لديك بأن الملك الميتة أوصاه وبنهاضته
أدائه الذي يقال أنك ماله المروف أنه جرى تخفيفه
لاستيفاء ضريبة الألامال منه على الوجه التالي :

להזי ידוע לך
שהרכוש המפורסם לקסון
שאתה נהן מתואר כבעל
הידוע שלו הועד לעודם
הרכוש העירוני כדלקסון:

OTF: 5638-1000 MHz, -15.000-90.00

Name of Street اسم الشارع اسم الشارع	Name and Number of Block اسم القطعة و رقمها اسم القطعة و رقمها	Number of Parcels عدد القطع عدد القطع	Description of Property أوصاف الملك أوصاف الملك	Category for Taxation نوع الملك من حيث القيمة نوع الملك من حيث القيمة	Net Annual Value قيمة الإيجار السنوي التقاضي قيمة الإيجار السنوي التقاضي
STREET NO رقم الشارع	170001 STN 00 رقم القطعة	170001 STN 00 عدد القطع	170001 STN 00 أوصاف الملك	170001 STN 00 نوع الملك من حيث القيمة	170001 STN 00 قيمة الإيجار السنوي التقاضي

Y177

12

2

9

Registered Sites along secondary program roads.

1) Tulkarm-Baga el Gharbiye

PWD. No. 5

(from South to North)
Shuweikeh (registered in Addendum)

Kafr Sib "

Yemma

Zeita

Jett

Baga el Gharbiye

2) Jaba-Kufeir (from West to East)

Nos. 8,13.

Jaba

Kh. Jafa

Kh. Deidabah

Tell el Qaza'i

Tell Kheibar

Sir

el Kufeir

3) Zabadba-Tubas (from North to South)

Kh. Kafr Dukk

Tubas

4) Tubas-es Samiriye (from South to North)

PWD. No. 9

Tubas

Kh. Handus

Tayasir

Marah el Maut

el Mukhabbi

Kh. Qa'un

es Samriyeh

Note: This line follows an old and partly preserved Roman road with numerous extant milestones.

5) Qalqiliye/Tulkarm Road - Fundug. (West to East)

No. 11

Magharet el Haj Khalil

Kh. el Mudahdara

Kur

el Mejdal

د جوان قاضی نظام لکیم

51/11/15

الرقم — ١٣/١٦

المسجد محمود عبد الرازق الصراقي - السطيرة

عمر الحاج عمر

لقد سار حفر ونشر اصحاب مدقونة وحمل بقايا قطع عواميد في ارض خربة

لم التعليق المائدة لكه وهذا مخالف للقوانين دائمة الآثار إذ أن هذه الأراضي

• أنثوية كما جاء بالخارطة رقم ١٣٩١/١/٦

ولذلك فاني اذكركم بعدم السوء لاجراء حفريات ونهب اثار في هذه الارض

مرة اخرى • والعصا

تاسیسات قضا' حوالہ

نسخة لحاضرة مدير دائرة الآثار بالقدس المحترم

بالاشاره لكتابه رقم 1013 ATQ/ تاريخ 24 اكتوبر 1965 .

14/7/0

الرقم - ٤١٠ / ٢٠

ارجو تبليغ الاشخاص المذكورة اسماؤهم ادناه بالحضور

والسلام •

قائم مقام قضاہ طولکس

عمر الحاء - عمر

۱۰۰/۱۱/۱۱

BF 10.11

Signature of Payer
 بوبى اللى
 بوبى اللى

Signature of Registry Clerk
 بوبى اللى
 بوبى اللى

The sums shown above have been received by me.
 بوبى اللى
 بوبى اللى

TOTAL بوبى اللى	 050 050
--------------------	--


51/37

DEPARTMENT OF ANTIQUITIES,
JERUSALEM.

ATQ/1013.

24th October, 1945.

District Officer,
Tulkarm



Sub : Kh. Umm 'Ulleiqā -
Tira village lands.

I enclose a copy of a report by
my Inspector.

I should be glad if you would warn
the landlords Mahmoud Abd er Raziq and
Umar el Haj Umar of Tira village against
further damage to the site.

Rusthamlin

DIRECTOR OF ANTIQUITIES.

see p. 21

Y. Y. Y.

12

No. S4235

J. Ory

Date 3.10.45

Site Kh. Umm 'Ulleiga

Map Ref. VI 139 181

Situation & approaches mainly to E of the Haifa road.

Traces of ~~gi~~ digging for stone were noted over a large area.

Mainly rubble was dug up, but also some dressed stones a few fragments of column shafts and a circular stone basin was damaged.

The land in which the digging took place is owned by Mahmoud Abd er Raziq and Umar el-Haj Umar, from et-Tira village.

Should be warned through the District Officer, Tulkarm.

10
3

17
GOVERNMENT OF PALESTINE.

TELE. : "PRINTER, JERUSALEM".

TEL. NO. 4487. - P. O. BOX 293.

PRINTING & STATIONERY OFFICE,
JERUSALEM.

REF. P/3/23

4/10 *gf*
4 May, 1945.

Assistant District Commissioner,
Tulkarm.

Sub:- Schedule of Historical Sites
and Monuments.

Ref:- Your letter No. T/410/16 dated 18.9.45.

In reply to your above
mentioned letter I have to inform you
that these have now been forwarded to
you reference Issue Voucher No. Pub/3563
dated 2nd May, 1945.

P.18.
P.16
gf
A/GOVERNMENT PRINTER.

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

18th April, 1945.

Govt. Printer,
Jerusalem.

Subject:- Schedule of Historical Monuments and Sites.

Ref'nce:- My No. T/410/15 dated 20.3.1945.

I shall be grateful if you will expedite supply.

Assistant District Commissioner,
Tulkarm.

15

19/4/45

ASSISTANT DISTRICT COMMISSIONER'S OFFICE
TULKARM.

20th March, 1945.

Govt. Printer,
Jerusalem.

Subject:- Schedule of Historical Monuments and Sites.

Ref'nce:- Letter No. ATQ/3/44 of 9th March, 1945 from
Director of Antiquities to all District
Commissioners with copy to you.I should be grateful if I could be supplied with
20 copies at your convenience.Assistant District Commissioner,
Tulkarm.

20/3/45

2 Rem. to H
yes H. J. J.
/7.

A.P.C.

Ref. (13)

9 suggest 8 :-

- 1) District Offices, Tulkarm.
- 2) Police, Tulkarm.
- 3) Police, Seilsith u.
- 4) Police, Khirbat Beit Liel.
- 5) Police, Tel-monal.
- 6) Municipalities, Tulkarm.
- 7) Local Council, Seil.
- 8) " " , Anshita.

SK

19.3.

DEPARTMENT OF ANTIQUITIES,
JERUSALEM.

No. ATQ/3/44

9th March, 1945.

The Inspector General of Police.
All District Commissioners.

Subject:- Schedule of Historical Monuments and Sites.

A revised schedule of historical monuments and sites has been published, as a supplement to the Palestine Gazette No. 1375 of 24.11.44, in accordance with sub-section (1) of section (17) of the Antiquities Ordinance, 1929.

2. In accordance with the Antiquities (Amendment) Ordinance of 1943, dated 10.12.43, copies of the relevant parts of this schedule shall be available for inspection in every District Office and Police Station in the sub-district in which an historical monument or historical site is situated.

3. I shall be grateful if you will kindly give directions for copies of the supplement in the appropriate languages to be available for inspection in all District Offices and Police Stations. Distribution has, I understand, been effected in accordance with the attached list. Will you kindly inform me, as early as possible, whether any further copies are required.

4. The new schedule supersedes the Provisional Schedule of 15.6.1929 and all copies of the latter should be withdrawn.

(Sgd.) 7777777

DIRECTOR OF ANTIQUITIES.

Copy to:- The Government Printer.

IA.

DISTRICT COMMISSIONER'S
OFFICES, SAMARIA, NABLUUS

No. 174 16.3.1945

Transmitted to Ant. Tulkarn

for [signature]

[signature] 16/3

9.9.45
I suggest 8
no follow-up:-
1. picket

How many copies do we need, to carry
out the above (para 3)?

(COPY)

Palestine Gazette No. 1375. Historical Sites.

4/8/45

<u>B.</u>	<u>A.</u>	<u>H.</u>	<u>Department.</u>
2	-	-	A/ District Commissioner, Nablus.
1	6	1	District Officer, Tulkarm.
2	2	-	" " Jenin
1	-	10	" " Natanya
2	6	-	District Commissioner, Nablus.

Dear C.C. Tulkarni

Herewith the list referred to
in para of this office letter No
174 of 16/3/45 re historical sites

Y. T.
to
22/3

410
ATQ/987

12
Department of Antiquities,
Jerusalem.
6th March, 1945.

The Water Commissioner,
P.O.B.189, Jerusalem.

Subject :- Kh. Azzun.

Reference :- Your IR/764/3 of 17.2.45.

I have no objection to the drilling of a well at Kh. Azzun Village provided that any ancient structures which may be encountered are reported to this office and left undamaged pending inspection and record.

(Signed) R. W. HAMILTON

Director of Antiquities.

Copy to: The District Officer, Tulkarm.

J 1/3
EX
6/3
14/1/45

د یوان قائمقام طولکرم

۱۹۴۴/۷/۲۰

الرفم - ۱۰

السید رضوان السنزای المحترم - طولکرم

بالاشارة الى الاستدعاء المستقدم منك بتاريخ ۱۹۴۴/۶/۱۷

بخصوص الآثار المقدسة التي ظهرت في ارضك .

اخبرك أنه بإمكانك ردم محلي الحفر واستعمال الحجارة بشرط أن تحفظ
الناבותين من حجر والموجودين الآن على الأرض في محل أمان والسلام

~~محرر~~
قائم مقام قضاة طولکرم

۱۹۴۴/۷/۲۰

INSPECTOR OF ANTIQUITIES.

P.O.B.1368, Tel-Aviv.

16th July, 1944.

District Officer,
Tulkarm.

Subject:-Birket Umm el-'Idham.

Reference:-Your No.TUL.410/9 of 26.7.44.

The petitioner, Radwan Ghazzawi, may be allowed to fill and level the site. Two sarcophagi on the site may be put in a place of safety and loose stones may be used by him for building.


Inspector of Antiquities.

Copy to:-Director of Antiquities.

Assistant District Commissioner's Office,
Tulkarm,

25th June, 1944.

Inspector of Antiquities,
P. O. Box. 1368,
Tel-Aviv.

Subject:- Antiquity Site-Tulkarm town.

Reference:- My letter No. TUL.410/6 of 28.1.1944.

I enclose for your information a petition received
from Radwan el Ghazawi of Tulkarm.

(Sgd) A. S. KHAYR
District Officer,
Tulkarm.

Vide P. 8.

28/6

RECEIVED
JAN 10 1964
U.S. DEPT. OF JUSTICE

8

9

763
17 JUL 1966

معرفة فائضكم طوبى لكم

R 162

المستعدين
المنفعة
فيما يتعلق
الانذار

بعضه في نظره انما هو انذار مجازي. البرج. آتيا قديم وقد اجبتنا ان نعلم
عنه ذلك وحده ما هو به من دائرة الانذار. ومجتبوا هذه الانذار في
الانذار انما هي صفة وتكون.

فانما ارادوا السالك في محكم ردم من لطيفات والتفرد
بالجاء في طهرت واقبلوا انذاره فيقولون ك ما نرى في

في
فيما يتعلق

Enclose copy
to compare - 1 - %
out 6 for sub. 2. 9 remainder arrived and
application for
Bury.

19/6

Phase see page 6

AT

See P. 9

Assistant District Commissioner's Office,
Tulkarm.

31st January, 1944.

Inspector of Antiquities,
P.O. B. 1368,
TEL-AVIV.
-----Subject :- Illicit Building at Tabeur (Kh. Azzun).Ref'nce :- My TUL.410/4 of 25th January, 1944.

The Mukhtar and elders denied all knowledge of their village built on area to have been declared as antiquity site. They were however warned accordingly.

2. I suggest that the antiquity area be pointed out to the Mukhtar. Probably this may be done on your next visit to the village.

(Sgd.) A. S. KHAYR

District Officer,
Tulkarm.

dik.

r/v
1

Assistant District Commissioner's Office,
Tulkarm.

28th January, 1944.

Inspector of Antiquities,
Tel-Aviv,
P.O.B. 1368

Subject :- Antiquity Site - Tulkarm town.

Ref'nce :- Enclosed petition, dated 28.1.44
from Radwan Gazzawi of Tulkarm
town.

Copy of above petition is forwarded for information
and any action necessary.

2. I presume the site comes under you.

Reluctant

(Sgd.) A. S. KHAYR

District Officer,
Tulkarm.

29/1
17

٩

28 JAN. 1914

عذرة فاعلموا انكم

المستحقين، فوالله اني طوبى لكم سائر عوار البروع

الموضوع، وجود آثار قدسية

بعضها من مذبحية بياض ارض الجارة مدارحما طائفة باغدة

مدارحما طوبى لكم طاهر "سنة" قدسية وقد تسمى مع حاله

فانما تحيطوا عما يروى هذا عطاء قدسية الوفاة

سنة

١٩١٤
١٤٣٥

4
No. FUL. 410/A.

Assistant District Commissioner's Office,
Tulkarm.

25th January, 1944.

Inspector of Antiquities,
P.O.B. 1368,
Tel-Aviv.

P. ③
Subject :- Illicit Building at Tabsur (Kh. Azzun).

Ref'nce :- Your letter of 24th January, 1944.

Action is being taken and you will be informed of
results in due course.

3/12

(Sgd.) A. S. KHAYR

District Officer,
Tulkarm.

Copy to Director of Antiquities,
Jerusalem.

See P. 7

INSPECTOR OF ANTIQUITIES
P.O.B.1368, Tel-Aviv.
24th January, 1944.

District Officer,
Tul-karem.



Subject:-Illicit Building at Tabsur(Kh.Azzun).

It has been observed that unauthorised building was taking place at the Registered Historical site of Tabsur(Kh.Azzun), contrary to Sections 18 and 22(6) of the Antiquities Ordinance. Recently also a mosque was built on the site without the permission of the Director of Antiquities having been previously obtained.

I shall be grateful if you would convey a competent warning to those concerned with the building of the mosque and ensure at the same time that it reaches the individual villagers as well, with a view to prevent further unauthorised building in future.

Applications by those who intend to build had best be submitted in good time through you and passed on to the Director of Antiquities for his conditional approval.

Inspector of Antiquities.

Copy to:-Director of Antiquities.

תד"ר 1250

מדינת ישראל

דואר רשמי



12a1

Supplement No. 2
to the
Palestine Gazette Extraordinary No. 1575 of 24th November, 1944.

SCHEDULE OF HISTORICAL MONUMENTS AND SITES.

Published in accordance with subsection (1) of section 17 of the Antiquities Ordinance, 1929.

Additions to this Schedule will be published from time to time in the Palestine Gazette.

The omission of any historical site from this schedule, or part of such site from the description of it herein, does not exclude it from the provisions of the Antiquities Ordinance.

All antiquities in the immediate neighbourhood of an historical site or monument are deemed to be part of such site or monument.

R. W. HAMILTON
Director of Antiquities.

LIST OF ARCHAEOLOGICAL SITES.

The following abbreviations are used:

A.	— Acre	J.	— Jenin	RA.	— Ramallah
Ba.	— Beersheba	Ja.	— Jaffa	S.	— Safad
Bu.	— Beisan	Jm.	— Jerusalem	T.	— Tiberias
G.	— Gaza	N.	— Nablus	Tk.	— Tulkarm
H.	— Haifa	Nt.	— Nazareth	Kh.	— Khirbat
He.	— Hebron	R.	— er Ramla		

The map references are to the Survey of Palestine 1 : 100,000 series (1942 edition). Roman numerals indicate the sheet; the groups of figures give the coordinates. For details of the system of coordinates, see *Survey of Palestine, Maps and Publications*, 1936, pp. 21-24.

Map references without sheet number are to the 1 : 250,000 Map of Palestine (South Sheet), published by the Survey of Palestine.

Place names are arranged alphabetically, the common prefixes Khirba, Khirab, Khurayib, Maghara, Rujm, Rujum, Tell, Tulul and Wadi being disregarded and printed after the name. The Arabic definite article is printed before the word it qualifies, but is disregarded in the alphabetic arrangement. Thus Tell el Mutasallim appears as el Mutasallim, Tell; Khirbat Abu Huweilan as Abu Huweilan, Kh., etc.

Name of Site	Sub-District	Map Reference	Description
'Abá, Kh.	J.	V. 181 207	Ruined village; rock-cut cistern. To east rock-cut tomb with sarcophagi; to north cave.
Abáls, Tell	S.	III. 207 274	Artificial mound.
'Abasán el Kabir	G.	XI. 088 082	Mosaic pavements, marble columns and bases.
el Abawát, Kh. (el 'Uda, Kh., et Tabla, Kh.)	A.	III. 171 274	Ruins and cistern.
'Abbád, Kh.	A.	III. 180 296	see Ras 'Abbád, Kh.
'Abbád, Kh.	He.	IX. 147 121	Foundations of buildings and walls with streets.
'Abbás, Kh. Wadi	RA.	X. 172 147	Ruined walls, foundations, rock-cut tombs.
'Abbásiya, Kh.	A.	II. 165 275	Ruins, caves, cisterns, press. Rock-cut tomb to south.
'Abd el 'Al, Kh. (el 'Afrata, Kh., el 'Afrít, Kh.)	N.	VII. 176 169	Ruined dry-stone building and towers. Arches and vault. Rock-cut cave.
'Abd en Nabi, Kh.	Re.	IX. 151 153	Heaps of stones, foundations, rock-cut tombs and cisterns.
'Abda	Ba.	120 020	Ruins of town with fortress, churches and bath. Roman camp. Nabatean tombs, temple and high place. Roman block houses on 'Aslôj track.
'Abda, Kh.	A.	II. 163 272	Ruined walls, cisterns. Remains of press.
'Abda, Kh.	He.	XII. 152 097	Ruined walls, cisterns, caves.
'Abdûn	H.	IV. 143 220	Traces of walls, cistern.
el 'Abhar, Kh.	Jm.	IX. 161 125	Foundations, heaps of stones.
el 'Abid, Kh.	He.	IX. 151 125	Ruined buildings, heaps of stones, cisterns, architectural fragments.
Abil, Tell (el Mudeira)	S.	I. 204 296	Artificial mound.
Abil el Qamh	S.	I. 204 296	Artificial mound, rock tombs, flints, cairns of stones between Abil and Tell el Qâdi.
'Abirjân, Kh.	RA.	IX. 159 145	Foundations, lintels, rock-cut cisterns.
Abraga, Kh.	He.	XII. 143 104	Ruins.
el 'Abtah	G.	VIII. 112 126	Artificial mound, surface pottery, floor made of potsherds stuck in plaster.
Abu 'Adas, Kh.	Jm.	IX. 160 127	Ruins.
Abu el 'Alaiq, Tulul	Jm.	X. 191 140	Two artificial mounds, remains of buildings, walls and bridge, conduit and pool below northern mound.
Abu 'Ali, Kh.	J.	VII. 178 192	Vaulted rooms, cisterns, caves.
Abu 'Amir, Kh.	J.	V. 170 209	Ruined buildings, cisterns. Rock-cut tombs.
Abu 'Arqûb, Kh.	G.	VIII. 121 136	see el 'Arqubiya, Kh.
Abu 'Arrâm, Kh.	G.	XII. 131 116	Ruins, cave, tesserae.
Abu 'Ataba	A.	II. 159 290	Moslem shrine. Surface pottery.
Abu Bala, Kh. (Iskandar, Kh.)	TK.	VI. 160 185	Ruin, cistern.
Abu ed Diba', Wadi	Jm.	X. 185 138	Ruined aqueduct or dam.
Abu Dubbah, Kh.	He.	XII. 160 107	Traces of ruins.
Abu Duheila, Kh.	Ba.	XII. 130 105	Ruins, cisterns.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Abu Falâh, Kh.	RA.	X. 179 157	Cisterns and caves in village. Built and rock-cut pool to north-east.
Abu Faraj, Tell	Bn.	V. 199 203	Artificial mound, masonry near spring.
Abu Fatûn, Kh. (Sabil esh Sheikh Kabakba)	G.	XI. 113 119	Fragments of columns, surface pottery. Maqâm and Sabil of esh Sheikh Mohd. el Kabakba.
Abu Fursij, Kh.	Re.	IX. 152 146	Rock-cut cisterns, scattered dressed stones.
Abu Ghalyûn, Kh.	Ba.	XIV. 112 075	see el Khashif, Kh.
Abu Gharîb, Kh.	N.	VII. 183 189	see Kafr Gharîb, Kh.
Abu Ghosh	Jm.	IX. 160 135	see Qaryat el 'Inab.
Abu Hadâid, Kh.	G.	XI. 109 107	Rubble foundations, cisterns, rock-cut tomb.
Abu Hajjâj, Kh.	Ba.	XI. 094 089	Rubble foundations, cistern, rubbish mounds, surface pottery.
Abu Hamâd, Kh. (Bablun, Kh.)	H.	IV. 149 212	Artificial mound with surface pottery and press.
Abu el Hamam, Kh.	He.	XII. 163 098	see Zif, Kh.
Abu Hamid, Kh.	Re.	IX. 145 157	Rock-cut tombs, plastered cistern.
Abu el Hawa, Tell (Tell el Hawa, Tell er Riyâh)	G.	XI. 098 105	Small artificial mound, mosaic pavement, surface pottery and marble fragments.
Abu Hindi, Tell	Jm.	X. 192 141	Artificial mound.
Abu Hureira, Tell	Ba.	XI. 113 088	Artificial mound, mud brick wall, stone glacis, potsheerds.
Abu Huweilan, Kh.	Jm.	X. 178 131	Heaps of stones.
Abu Imgheis	Ba.	XII. 120 107	see Abu Mugheis.
Abu Irqaiyiq	Ba.	XV. 121 077	see Abu Ruqaiyiq.
Abu Irteimat	Ba.	130 030	see Abu Ruteimat.
Abu el Jamal, Tell	Bn.	V. 203 223	see ez Zanbaqiya esh Sharqi, Tell.
Abu Jarâima, Magharat	A.	III. 172 270	Cave.
Abu el Jarra, Kh.	Ba.	XI. 113 089	Ruined cisterns.
Abu Juwei'id	G.	VIII. 121 121	Rubble vaulted cisterns, tombs, remains of mosaic floor.
Abu Kabir	T.	V. 209 232	Megalithic foundation, flint flakes.
Abu Khaff, Kh.	Ba.	XII. 135 087	see Beikat Abu Hadba.
Abu Khumeish, Kh.	TK.	VI. 158 191	Foundations, heaps of stones, rock-cut tombs.
Abu Lahm, Kh.	Jm.	IX. 159 128	Ruins.
Abu Lahm, Kh.	Jm.	X. 191 144	Foundations of rectangular buildings. Maqâm of Imam 'Ali.
Abu Lauza, Kh.	RA.	IX. 167 148	Ruined walls, terraces.
Abu Malul, Kh.	RA.	X. 180 158	Remains of buildings, cisterns, tombs, caves.
Abu Maqiri, Kh.	Jm.	X. 175 127	see Abu Mugheiri, Kh.
Abu Mu'ammâr, Kh. (el 'Uneizya, Kh.)	Jm.	IX. 164 140	Remains of buildings, caves, rock-cut cistern.
Abu Mugheiri, Kh. (Abu Maqiri, Kh.)	Jm.	X. 175 127	Foundations, rock-cut cisterns and caves, wine-press.
Abu Mugheis, Kh. (Abu Imgheis, Kh.)	Ba.	XII. 120 107	Small ruin, fragments of pottery.
Abu Muhammad, Kh.	Jm.	IX. 159 136	see Bâtin el 'Ursh.
Abu Mulassam, Kh.	He.	XII. 142 097	Remains of buildings and tower.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Abu Musarra, Kh.	Jm.	X. 177 137	Ruined walls.
Abu en Naml	T.	V. 208 232	Small artificial mound, rubble walls, traces of ancient road east to west.
Abu Qudeis, Tell	J.	V. 171 218	Artificial mound, masonry wells.
Abu el Quháf, Kh.	Re.	IX. 134 128	Rubble foundations, cisterns, surface pottery.
Abu Quleiba, Kh.	Jm.	XII. 161 120	Ruined walls, wells.
Abu Qutáf	G.	XI. 106 118	Well and reservoir, surface pottery.
(Dureibát Abu Qutáf, Dhahr Abu Qutáf)			
Abu er Rafi'	Ba.	XII. 123 107	see esh Shuqaf, Tell.
Abu Rajliya	Ba.	XI. 089 089	Traces of rubble constructions, potsherds.
Abu Rashid, Kh.	RA.	X. 182 148	Traces of settlement.
Abu er Rawázin, Kh.	He.	XII. 145 113	see er Rawázin, Kh.
Abu Rish, Kh.	He.	XII. 163 108	Walls of a church with two pillar shafts and a base; door post, vaulted cistern.
Abu Rizq, Kh.	Ba.	XII. 130 093	Traces of settlement, rock-cut cisterns.
Abu Rukheim, Kh.	He.	XII. 144 112	Foundations, caves, cisterns.
Abu Rumb, Tell	N.	VII. 193 179	Artificial mound.
Abu Ruqaiyiq, Kh.	Ba.	XV. 121 077	Rubble cisterns, scattered stones, artificial mounds with surface pottery.
(Irqayiq)			
Abu Rûs, Kh.	Jm.	X. 177 140	Heaps of stones.
Abu Ruteimat	Ba.	130 030	Blockhouse.
(Irteimat)			
Abu Sa'd, Kh.	Jm.	X. 177 130	Heaps of stones.
Abu Samâha, Magharat	TK.	VI. 138 194	see Dhahr Umm el Haiya.
Abu Samâra, Kh.	Ba.	XI. 119 085	Traces of extensive settlement. Surface pottery, caves, rock-cut cisterns, fragment of column.
Abu Sarhân, Kh.	Ba.	XIV. 108 077	Artificial mound, traces of brick work, basalt hand mill.
Abu Shabbân, Kh.	He.	XIII. 165 094	Foundations.
Abu Sharab, Kh.	Ba.	XII. 124 089	see Bir Abu Mansur.
Abu esh Shauk, Kh.	He.	XII. 153 116	Foundations, cisterns, wine press, remains of an old road.
Abu esh Shiba, Kh.	A.	III. 189 259	Ruined buildings, foundations, cisterns, vaulted cave, rock-cut graves.
(esh Shiba, Kh.)			
Abu Shûsha	H.	IV. 163 224	Artificial mound. Vaulted room, mosaic floor. Architectural fragments in village. Rock-cut tombs, traces of buildings in the valley.
Abu Shûsha	Re.	IX. 142 140	Artificial mound, partly excavated.
(Jazar, Tell)			
Abu Shûsha, Kh.	T.	III. 198 251	Ruined mills.
Abu Shûsha, Kh.	H.	IV. 150 214	Foundations. Surface pottery.
Abu Sidra, Tell	N.	VII. 203 178	Artificial mound. Rubble foundations.
Abu Silâsil, Kh.	He.	XII. 149 114	Cisterns, foundations, heaps of stones.
Abu Sinân	A.	II. 167 262	Cisterns, presses, tombs and rock-cuttings.
Granite mill stone.			
Abu Sûd, Kh.	Jm.	IX. 165 123	Foundations, press, rock-cut tombs (½ km. to west) and cisterns.
Abu Suheibân, Kh.	Ba.	XIV. 117 073	Foundations, cisterns.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Abu Suhweila, Kh.	He.	XII. 142 096	Foundations, press, caves, cisterns.
Abu Sultân, Tell	Re.	VIII. 126 147	<i>see</i> es Sultân, Tell.
Abu Suqeir, Kh.	RA.	IX. 156 145	<i>see</i> Mannâ', Kh.
Abu Sûs, Tell	N.	VII. 203 198	Artificial mound, foundations.
Abu Suwwâna, Kh.	Jm.	X. 179 130	Remains of two buildings, cisterns.
Abu Tareifi, Wadi	Ba.	XV. 156 052	Ruins of tower, cisterns, walls, cave, cairns.
Abu Tulûl, Kh.	Ba.	XV. 145 065	Foundations of building, artificial mounds; three cisterns, terrace walls, caves (to north). (<i>see also</i> el Madhbah, Kh.)
Abu Ufeish, Wadi	He.	IX. 152 123	Roman road, milestones.
Abu Usba', Magharat	H.	IV. 148 235	Cave with prehistoric remains.
Abu Zalaf, Tell	Jm.	X. 192 141	Artificial mound, partly excavated. Squared stones on surface.
Abu Zalafa, Kh.	S.	III. 202 261	Heaps of stones, ruined enclosure.
Abu Za'rûr, Kh.	Jm.	IX. 163 139	Ruins.
Abu Zeitûn, Tell	Ja.	VI. 134 167	Artificial mound.
Abu Zu'eiza, Kh.	Ba.	XII. 123 095	<i>see</i> 'Amûdiya, Kh.
Abu Zurei'i, Kh. (Hazzâra, Kh.)	Ba.	XII. 124 107	Traces of ruins, scattered stones, broken pottery.
Abu Zureiq, Tell	H.	IV. 162 227	Artificial mound, caves and tombs. Decorated stone in cemetery.
'Abûd	RA.	IX. 157 158	Reused lintels in village, mosaic pavement. Ruined churches in vicinity: Mar Theodros, Deir Nastâsiya, Mar 'Abadi, Burbâra.
el Abyad, Tell	N.	VII. 196 167	Artificial mound, foundations.
Acre	A.	II. 157 258	City walls and citadel. Crypt of St. John. Medieval vaults and foundations. Sûqs. Khans. Remains of moles, el Manâra. Remains of medieval town to north and east of city. Aqueduct.
el 'Adâra, Kh.	G.	XI. 096 094	Cisterns, foundations, piles of broken pottery.
el 'Adara, Kh.	He.	XII. 142 107	Foundations, caves.
el 'Adas, Kh. (Umm el 'Adas)	He.	IX. 145 120	Ruined walls, columns, cisterns, press, heaps of stones.
el 'Adas, Kh.	Jm.	IX. 165 139	Traces of ruins.
el 'Adas, Kh.	G.	XIV. 051 075	Surfaces pottery over extensive site.
'Adasa, Kh.	Jm.	X. 173 137	Ruined walls, tank, rock-cut cisterns.
Adathîr	S.	III. 195 971	<i>see</i> el Manâra, Kh.
'Addâsa, Kh.	Jm.	X. 170 139	Ruined building. Bath (1). Caves, cisterns, reservoir, presses.
el 'Adini, Kh.	Ba.	XI. 095 088	Domed building, surface pottery, column fragments.
'Adlân	H.	IV. 144 224	Circle of upright stones.
'Afâna, Rujm	Jm.	IX. 167 129	Cairn.
el 'Affûla	Nt.	V. 177 224	Artificial mounds partly excavated, mosaic pavements, building partly constructed of sarcophagi.

Name of Site	Sub-District	Map Reference	Description
el 'Afrata, Kh.	N.	VII. 176 169	<i>see</i> 'Abd el 'Al. <i>see</i> el Ifshâr, Tell. Traces of settlement, cisterns. Ruined mosque on site of older building. Granite column. Ruins of small settlement with khan, well, ancient road. Artificial mound. <i>see</i> 'Ein... Small artificial mound, rock cuttings, rock-cut tombs. Traces of settlement. Ruin with heaps of squared stones, cisterns, oil press and Maqâm. Pool cut in the rock. Village on ancient site. Foundations, cisterns, rock-cut tombs with sarcophagi. <i>see</i> 'Ijjis er Ras, Kh. Traces of ruins in the village, rock-cut tombs, architectural fragments in mosque. <i>see</i> el 'Ujâl, Tell. Ancient foundations in village. Foundations, architectural fragments, rock-cut tomb. Artificial mound. Traces of foundations. Two small mounds, with surface pottery. <i>see</i> Umm el Kadish, Kh. Ruined walls, cisterns, olive press, tombs. A double sarcophagus cut in rock near 'Ein Sâlih. <i>see</i> esh Sheik Zirâq, Tell. <i>see</i> Murra, Tell. Foundations, rock-cuttings, cistern cut in the rock. Remains of buildings in squared masonry, foundations, cisterns, oil presses, rock-cut tombs. Ruined walls, foundations, presses, cisterns; rock-cut tombs, pools to south. Ancient hermitage, caves. Traces of settlement, walls of square building, rock-cut cisterns and caves. Scattered stones, cisterns, caves. <i>see</i> el 'Alyâ, Kh. Foundations, remains of building with columns and bases, rock-cut tombs and caves, press, mosaic pavement.
el 'Afrât, Kh.	N.	VII. 177 168	
el Afshâr, Tell	TK.	VI. 141 198	
Ahmad el Qarqafâwi	G.	VIII. 124 122	
Ahmadiya, Kh.	Jm.	XII. 164 119	<i>see</i> 'Ein... Small artificial mound, rock cuttings, rock-cut tombs. Traces of settlement. Ruin with heaps of squared stones, cisterns, oil press and Maqâm. Pool cut in the rock. Village on ancient site. Foundations, cisterns, rock-cut tombs with sarcophagi. <i>see</i> 'Ijjis er Ras, Kh. Traces of ruins in the village, rock-cut tombs, architectural fragments in mosque. <i>see</i> el 'Ujâl, Tell. Ancient foundations in village. Foundations, architectural fragments, rock-cut tomb. Artificial mound. Traces of foundations. Two small mounds, with surface pottery. <i>see</i> Umm el Kadish, Kh. Ruined walls, cisterns, olive press, tombs. A double sarcophagus cut in rock near 'Ein Sâlih. <i>see</i> esh Sheik Zirâq, Tell. <i>see</i> Murra, Tell. Foundations, rock-cuttings, cistern cut in the rock. Remains of buildings in squared masonry, foundations, cisterns, oil presses, rock-cut tombs. Ruined walls, foundations, presses, cisterns; rock-cut tombs, pools to south. Ancient hermitage, caves. Traces of settlement, walls of square building, rock-cut cisterns and caves. Scattered stones, cisterns, caves. <i>see</i> el 'Alyâ, Kh. Foundations, remains of building with columns and bases, rock-cut tombs and caves, press, mosaic pavement.
(Humeidiya, Kh.)	Jm.	XII. 164 119	
el Ahmar, Tell	G.	XI. 081 086	
'Ain . . .	G.	XI. 081 086	
el 'Aiyadiya, Kh.	A.	II. 165 258	<i>see</i> 'Ein... Small artificial mound, rock cuttings, rock-cut tombs. Traces of settlement. Ruin with heaps of squared stones, cisterns, oil press and Maqâm. Pool cut in the rock. Village on ancient site. Foundations, cisterns, rock-cut tombs with sarcophagi. <i>see</i> 'Ijjis er Ras, Kh. Traces of ruins in the village, rock-cut tombs, architectural fragments in mosque. <i>see</i> el 'Ujâl, Tell. Ancient foundations in village. Foundations, architectural fragments, rock-cut tomb. Artificial mound. Traces of foundations. Two small mounds, with surface pottery. <i>see</i> Umm el Kadish, Kh. Ruined walls, cisterns, olive press, tombs. A double sarcophagus cut in rock near 'Ein Sâlih. <i>see</i> esh Sheik Zirâq, Tell. <i>see</i> Murra, Tell. Foundations, rock-cuttings, cistern cut in the rock. Remains of buildings in squared masonry, foundations, cisterns, oil presses, rock-cut tombs. Ruined walls, foundations, presses, cisterns; rock-cut tombs, pools to south. Ancient hermitage, caves. Traces of settlement, walls of square building, rock-cut cisterns and caves. Scattered stones, cisterns, caves. <i>see</i> el 'Alyâ, Kh. Foundations, remains of building with columns and bases, rock-cut tombs and caves, press, mosaic pavement.
el 'Ajalân, Kh.	Ba.	XII. 134 110	
(Fuheidi, Kh.)	Ba.	XII. 134 110	
el 'Ajami, Kh.	H.	IV. 149 215	
'Ajja	J.	VI. 168 196	<i>see</i> 'Ein... Small artificial mound, rock cuttings, rock-cut tombs. Traces of settlement. Ruin with heaps of squared stones, cisterns, oil press and Maqâm. Pool cut in the rock. Village on ancient site. Foundations, cisterns, rock-cut tombs with sarcophagi. <i>see</i> 'Ijjis er Ras, Kh. Traces of ruins in the village, rock-cut tombs, architectural fragments in mosque. <i>see</i> el 'Ujâl, Tell. Ancient foundations in village. Foundations, architectural fragments, rock-cut tomb. Artificial mound. Traces of foundations. Two small mounds, with surface pottery. <i>see</i> Umm el Kadish, Kh. Ruined walls, cisterns, olive press, tombs. A double sarcophagus cut in rock near 'Ein Sâlih. <i>see</i> esh Sheik Zirâq, Tell. <i>see</i> Murra, Tell. Foundations, rock-cuttings, cistern cut in the rock. Remains of buildings in squared masonry, foundations, cisterns, oil presses, rock-cut tombs. Ruined walls, foundations, presses, cisterns; rock-cut tombs, pools to south. Ancient hermitage, caves. Traces of settlement, walls of square building, rock-cut cisterns and caves. Scattered stones, cisterns, caves. <i>see</i> el 'Alyâ, Kh. Foundations, remains of building with columns and bases, rock-cut tombs and caves, press, mosaic pavement.
'Ajjas er Ras, Kh.	G.	XI. 118 118	
'Ajjâl	RA.	IX. 167 159	
el 'Ajjâl Tell	Nt.	V. 185 226	
el 'Ajjâl, Tell	G.	XI. 093 098	<i>see</i> 'Ein... Small artificial mound, rock cuttings, rock-cut tombs. Traces of settlement. Ruin with heaps of squared stones, cisterns, oil press and Maqâm. Pool cut in the rock. Village on ancient site. Foundations, cisterns, rock-cut tombs with sarcophagi. <i>see</i> 'Ijjis er Ras, Kh. Traces of ruins in the village, rock-cut tombs, architectural fragments in mosque. <i>see</i> el 'Ujâl, Tell. Ancient foundations in village. Foundations, architectural fragments, rock-cut tomb. Artificial mound. Traces of foundations. Two small mounds, with surface pottery. <i>see</i> Umm el Kadish, Kh. Ruined walls, cisterns, olive press, tombs. A double sarcophagus cut in rock near 'Ein Sâlih. <i>see</i> esh Sheik Zirâq, Tell. <i>see</i> Murra, Tell. Foundations, rock-cuttings, cistern cut in the rock. Remains of buildings in squared masonry, foundations, cisterns, oil presses, rock-cut tombs. Ruined walls, foundations, presses, cisterns; rock-cut tombs, pools to south. Ancient hermitage, caves. Traces of settlement, walls of square building, rock-cut cisterns and caves. Scattered stones, cisterns, caves. <i>see</i> el 'Alyâ, Kh. Foundations, remains of building with columns and bases, rock-cut tombs and caves, press, mosaic pavement.
'Ajjôr	He.	IX. 143 122	
el 'Ajjûri, Kh.	Re.	VIII. 128 143	
(ed Duheisha, Kh.)	Re.	VIII. 128 143	
'Ajlân, Kh.	Ba.	XII. 124 108	<i>see</i> 'Ein... Small artificial mound, rock cuttings, rock-cut tombs. Traces of settlement. Ruin with heaps of squared stones, cisterns, oil press and Maqâm. Pool cut in the rock. Village on ancient site. Foundations, cisterns, rock-cut tombs with sarcophagi. <i>see</i> 'Ijjis er Ras, Kh. Traces of ruins in the village, rock-cut tombs, architectural fragments in mosque. <i>see</i> el 'Ujâl, Tell. Ancient foundations in village. Foundations, architectural fragments, rock-cut tomb. Artificial mound. Traces of foundations. Two small mounds, with surface pottery. <i>see</i> Umm el Kadish, Kh. Ruined walls, cisterns, olive press, tombs. A double sarcophagus cut in rock near 'Ein Sâlih. <i>see</i> esh Sheik Zirâq, Tell. <i>see</i> Murra, Tell. Foundations, rock-cuttings, cistern cut in the rock. Remains of buildings in squared masonry, foundations, cisterns, oil presses, rock-cut tombs. Ruined walls, foundations, presses, cisterns; rock-cut tombs, pools to south. Ancient hermitage, caves. Traces of settlement, walls of square building, rock-cut cisterns and caves. Scattered stones, cisterns, caves. <i>see</i> el 'Alyâ, Kh. Foundations, remains of building with columns and bases, rock-cut tombs and caves, press, mosaic pavement.
el 'Ajwa, Tell	G.	XI. 088 094	
el Akâdish, Kh.	H.	IV. 154 216	
'Akbara	S.	III. 197 261	
el Akhdar, Tell	H.	IV. 138 204	<i>see</i> 'Ein... Small artificial mound, rock cuttings, rock-cut tombs. Traces of settlement. Ruin with heaps of squared stones, cisterns, oil press and Maqâm. Pool cut in the rock. Village on ancient site. Foundations, cisterns, rock-cut tombs with sarcophagi. <i>see</i> 'Ijjis er Ras, Kh. Traces of ruins in the village, rock-cut tombs, architectural fragments in mosque. <i>see</i> el 'Ujâl, Tell. Ancient foundations in village. Foundations, architectural fragments, rock-cut tomb. Artificial mound. Traces of foundations. Two small mounds, with surface pottery. <i>see</i> Umm el Kadish, Kh. Ruined walls, cisterns, olive press, tombs. A double sarcophagus cut in rock near 'Ein Sâlih. <i>see</i> esh Sheik Zirâq, Tell. <i>see</i> Murra, Tell. Foundations, rock-cuttings, cistern cut in the rock. Remains of buildings in squared masonry, foundations, cisterns, oil presses, rock-cut tombs. Ruined walls, foundations, presses, cisterns; rock-cut tombs, pools to south. Ancient hermitage, caves. Traces of settlement, walls of square building, rock-cut cisterns and caves. Scattered stones, cisterns, caves. <i>see</i> el 'Alyâ, Kh. Foundations, remains of building with columns and bases, rock-cut tombs and caves, press, mosaic pavement.
el Akheidir, Tell	G.	VIII. 118 137	
Akhfât edh Dhahara	Ba.	XII. 130 109	
'Akrûsh, Kh.	A.	II. 160 264	
'Alâ ed Din, Kh.	H.	IV. 158 233	<i>see</i> 'Ein... Small artificial mound, rock cuttings, rock-cut tombs. Traces of settlement. Ruin with heaps of squared stones, cisterns, oil press and Maqâm. Pool cut in the rock. Village on ancient site. Foundations, cisterns, rock-cut tombs with sarcophagi. <i>see</i> 'Ijjis er Ras, Kh. Traces of ruins in the village, rock-cut tombs, architectural fragments in mosque. <i>see</i> el 'Ujâl, Tell. Ancient foundations in village. Foundations, architectural fragments, rock-cut tomb. Artificial mound. Traces of foundations. Two small mounds, with surface pottery. <i>see</i> Umm el Kadish, Kh. Ruined walls, cisterns, olive press, tombs. A double sarcophagus cut in rock near 'Ein Sâlih. <i>see</i> esh Sheik Zirâq, Tell. <i>see</i> Murra, Tell. Foundations, rock-cuttings, cistern cut in the rock. Remains of buildings in squared masonry, foundations, cisterns, oil presses, rock-cut tombs. Ruined walls, foundations, presses, cisterns; rock-cut tombs, pools to south. Ancient hermitage, caves. Traces of settlement, walls of square building, rock-cut cisterns and caves. Scattered stones, cisterns, caves. <i>see</i> el 'Alyâ, Kh. Foundations, remains of building with columns and bases, rock-cut tombs and caves, press, mosaic pavement.
'Alâli el Banât	Jm.	IX. 154 130	
el 'Alawina, Kh.	Jm.	IX. 168 125	
el 'Alawiya, Kh.	S.	III. 193 271	
'Alî, Kh.	He.	IX. 149 125	<i>see</i> 'Ein... Small artificial mound, rock cuttings, rock-cut tombs. Traces of settlement. Ruin with heaps of squared stones, cisterns, oil press and Maqâm. Pool cut in the rock. Village on ancient site. Foundations, cisterns, rock-cut tombs with sarcophagi. <i>see</i> 'Ijjis er Ras, Kh. Traces of ruins in the village, rock-cut tombs, architectural fragments in mosque. <i>see</i> el 'Ujâl, Tell. Ancient foundations in village. Foundations, architectural fragments, rock-cut tomb. Artificial mound. Traces of foundations. Two small mounds, with surface pottery. <i>see</i> Umm el Kadish, Kh. Ruined walls, cisterns, olive press, tombs. A double sarcophagus cut in rock near 'Ein Sâlih. <i>see</i> esh Sheik Zirâq, Tell. <i>see</i> Murra, Tell. Foundations, rock-cuttings, cistern cut in the rock. Remains of buildings in squared masonry, foundations, cisterns, oil presses, rock-cut tombs. Ruined walls, foundations, presses, cisterns; rock-cut tombs, pools to south. Ancient hermitage, caves. Traces of settlement, walls of square building, rock-cut cisterns and caves. Scattered stones, cisterns, caves. <i>see</i> el 'Alyâ, Kh. Foundations, remains of building with columns and bases, rock-cut tombs and caves, press, mosaic pavement.
'Alî, Kh. ('Alla, Kh.)	Re.	VI. 153 161	

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
'Ali Mālikina, Kh (esh Sheikh 'Ali)	Re.	IX. 146 156	Foundations, door posts, presses, rock-cut reservoirs, cisterns, ruined mosque, rock-cut tombs.
'Ali Qauqa, Kh.	J.	IV. 161 210	Foundations, remains of ancient cultivation.
'Alīn, Kh.	He.	XII. 153 119	see 'Illn, Kh.
'Alīn, Wādī, Kh.	Jm.	IX. 150 128	Ruined walls, rock-cut cisterns, watch-tower, ancient road, tombs.
'Alla, Kh.	Re.	VI. 153 161	see 'Ali, Kh.
'Allar es Suffa	Jm.	IX. 155 125	Ruined building, rock-cut tombs, ruined tanks.
'Almā	S.	III. 197 273	Ruins of synagogue, architectural fragments and inscription in the village. To the east ruined watch-towers, three dolmens, sarcophagus.
'Almit, Kh.	Jm.	X. 176 137	Ruined walls, rock-cut cisterns.
'Alyā, Kh.	A.	III. 175 269	Cisterns, foundations, mill-stones, ashlar building with transverse arches.
el 'Alyā, Kh.	S.	III. 205 261	Basalt heaps, circular heap in centre.
el 'Alyā, Kh. (Kh. 'Ali)	He.	IX. 149 125	Ruined walls, foundations, rock-cut cisterns and caves. Cup marks in rock, ancient road to Zanā' and Deir 'Asfūr.
'Alyā, Kh.	Jm.	IX. 165 121	Ruins of building with mosaic pavements, niches and sumps. Rock-cut cisterns, tombs.
el 'Alyā, Kh.	RA.	X. 176 149	Ruined walls, rock-cut cisterns.
'Alyātā, Kh.	RA.	X. 173 159	Foundations, heaps of stones, column shaft, tombs.
'Āmīr, Kh.	N.	VI. 154 170	Ruined walls, watch-towers.
el Amīra, Kh.	He.	XII. 161 084	Caves.
el Amīra, Magharat	T.	III. 199 252	Cave with prehistoric remains.
'Ammar, Kh.	Re.	IX. 147 160	Foundations, cisterns, surface pottery.
'Ammūqa	S.	III. 199 268	Masonry tomb. Caves.
'Ammūriya, Kh.	He.	IX. 141 128	Remains of tower and vaults. Rock-cuttings, tombs.
'Ammūriya, Kh.	RA.	X. 177 159	Remains of square building, rock-cut cisterns, rock-cuttings, tombs.
'Amqā	A.	II. 166 265	Village on ancient site. Architectural material reused. Cisterns, tombs.
'Amr, Kh.	Jm.	IX. 143 126	Heaps of stones, foundations, caves, cisterns.
'Amr, Kh.	He.	XII. 141 119	Ruins of village, press cut in the rock.
el 'Amr, Tell	H.	IV. 159 237	Artificial mound.
'Amran, Kh.	Jm.	IX. 155 128	see 'Umrān, Kh.
el 'Amūd, Kh.	A.	II. 163 271	Foundations, press stones.
'Amūda, Kh.	RA.	IX. 169 149	Foundations, cave, ancient building material reused.
'Amūda, Kh.	G.	XI. 113 113	Artificial mound, column shaft, cisterns.
'Amūdiya, Kh. (Abu Zu'eiza, Kh.)	Ba.	XII. 123 095	Foundations, column fragments, cisterns. Well (in wadi to east). Surface flints.

Name of Site	Sub-District	Map Reference	Description
'Anâb el Kabîra, Kh.	He.	XII. 143 089	Ruins of town, church, walls, tower converted to mosque, now disused. Vaulted building (Qasr el 'Anab). Foundations, cisterns, presses.
'Anâb es Saghîra, Kh.	He.	XII. 146 091	Caves, cisterns, heaps of stones, foundations.
'Anabîâ	TK.	VI. 161 190	Rock-cut tombs, cisterns, reservoir.
'Anâhum, Kh.	J.	V. 190 201	Ruins of settlement, stone heaps.
el 'Anâqîr, Kh.	A.	III. 185 260	see er Rama.
'Anâta	Jm.	X. 175 136	Ancient site, foundations, building materials reused and mosaic <i>in situ</i> , fragments of columns, cisterns.
'Anîn	J.	IV. 166 212	Rock-cut passage, rock-cut tombs.
'Anîn, Kh.	J.	IV. 168 209	see Umm Zeid, Tell.
'Annîr, Kh.	RA.	IX. 166 151	Ruined walls of buildings, rock-cut tombs, olive press, rock-cut chamber with arched doorway, column shafts.
el 'Aqaba, Kh.	N.	VII. 160 193	Ruined enclosures, cistern cut in the rock.
'Aqada ('Aqqada)	J.	IV. 166 216	Ruined buildings.
'Aqbara, Kh.	A.	III. 186 274	Ruined settlement, foundations, presses, cisterns, tombs, sarcophagus. Cave at the spring.
el Aqbiya, Tell	J.	IV. 165 223	see Nagnhaghîya.
el 'Aqd, Kh.	Re.	IX. 151 138	Foundations, caves, presses.
'Aqd el 'Azîrîya	H.	IV. 146 204	Surface pottery, scattered rubble, mosaic fragments.
el 'Aqda, Kh.	N.	VII. 161 185	Remains of buildings. Architectural fragments.
el 'Aqîl, Kh.	N.	VI. 168 187	Remains of rubble walls.
Aqîr	Re.	IX. 133 141	Sarcophagi, Arabic inscription. Ancient well, surface pottery.
Aqlîdia, Kh.	He.	IX. 146 123	see Quleidiya, Kh.
'Aqqada	J.	IV. 166 216	see 'Aqada.
'Aqqara, Kh.	H.	IV. 163 239	Fallen masonry.
el Aqra', Kh.	N.	VI. 164 173	Ruined walls, heaps of stones.
el Aqra', Kh.	Ba.	XI. 118 104	Two circular rough masonry cisterns, scattered stones.
el Aqra', Tell	He.	XII. 138 101	Traces of ruins.
'Aqraba (el Husn)	N.	VII. 183 170	Remains of fort (el Husn), cistern. Pool. Foundations of buildings. Architectural and inscribed fragments in the village.
'Ara, Kh.	H.	IV. 158 212	Traces of settlement.
el 'Arab, Kh.	He.	IX. 143 123	Foundations of buildings and tower, caves, surface pottery.
el 'Arab, Kh.	He.	XII. 141 110	Heaps of stones. Remains of chapel with three apses. Also two small ruins in Wadi el 'Arab.
'Arabîya, Kh.	He.	XIII. 168 104	Foundations, heaps of stones, cisterns.
'Arâd, Tell	He.	XV. 162 077	see 'Urâd, Tell.
'Arâka, Kh.	N.	X. 195 159	see Dash-sha, Kh.
'Ar'ara, Kh.	N.	VI. 155 165	Ruined walls.
'Ar'ara, Kh.	Ba.	XV. 148 062	Extensive settlement razed to the ground.

Name of Site	Sub-District	Map Reference	Description
'Ar'ara, Tell	Ba.	XV. 148 062	Artificial mound, remains of city wall and foundations. Dam across wadi to south-west.
'Arbita, Kh.	T.	V. 189 237	<i>see</i> 'Irbada, Kh.
'Ard el Mihjar	G.	XI. 103 114	Surface pottery and marble fragments on the sand dunes.
el 'Arcini, Tell	G.	XII. 130 113	<i>see</i> esh Sheikh Ahmad el 'Arcini, Tell.
'Arnaba, Kh.	He.	XII. 156 111	Foundations, walls, rock-cut cisterns, mosaic pavement.
Arnūtiya	RA.	X. 171 151	Walls, foundations of large stones, cisterns, presses.
'Arqūb ed Darajāt	He.	XII. 158 080	Traces of ancient road with steps.
'Arqūb Ibn Basma	He.	XII. 161 084	Ruined watch-tower.
el 'Arqūbiya, Kh.	G.	VIII. 121 136	Foundations, reservoir, loose masonry, surface pottery.
'Arrāba	A.	III. 182 251	Ancient remains and Maqām in village. Column shafts, tombs, cisterns.
'Arrabuna	J.	V. 185 213	Foundations.
'Arrāna	J.	V. 181 211	Remains of ancient settlement, loose masonry, rock-cut tombs and cisterns, press, on north Maqām.
el 'Arrāb, Kh.	He.	XII. 164 114	Caves cut in the rock. Reservoir. Aqueduct from 'Ein 'Arrūb.
Arsūf	Ja.	VI. 132 178	Remain of Crusaders' castle and town, ancient harbour to west.
Artabba, Kh.	RA.	IX. 157 155	Foundations and walls. To south remains of press. To east and south caves.
Artās	Jm.	IX. 168 122	Aqueduct.
'Artūf	Jm.	IX. 150 131	Foundations, tombs, caves, presses; rock-cuttings and cupmarks; to north-west and east stone heaps.
'Arūra	RA.	VI. 166 161	Ruined walls and foundations. Fragments of columns. Rock-cut tomb, Maqām el Khadr, Maqām el 'Aruri, Maqām esh Sheikh Ridwān, el Qubba.
Aryāq, Kh.	S.	I. 204 298	Foundations, walls, column shafts, door jambs, font, sarcophagus, caves.
el Asad, Kh.	Jm.	IX. 153 126	Ruined walls. Foundations, rock-cut caves and cistern with steps, rock-cut press.
'Asāfa, Kh.	Nt.	VI. 164 180	Ruined walls, foundations, rock-cut cisterns.
'Asafira, Kh.	Re.	IX. 135 143	Ancient well.
'Asafna, Kh.	H.	IV. 155 237	Foundations, olive-press, rock-cut tombs, quarries.
'Asaila, Kh.	He.	XII. 143 085	<i>see</i> 'Useila, Kh.
el 'Asaliya, Kh.	S.	III. 202 261	Heaps of stones, ruined houses.
el Asāwir, Tell	H.	IV. 152 210	Artificial mound.
Ascalon	G.	XI. 107 119	Medieval walls enclosing ancient site and artificial mound. Remains of buildings. Architectural and sculptural fragments. Tombs, Maqām (el Khadra).

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
el Asfar, Kh.	He.	XII. 159 085	Foundations, heaps of masonry, Roman road, cistern, cave.
'Asfûra, Kh. (Umm el 'Ausaj)	Re.	IX. 142 136	Foundations, rock-cut cisterns, caves, mill-stone, surface pottery.
'Ashîr, Tell	TK.	VI. 135 186	Prehistoric site. Surface pottery, flints.
el Ashqar, Kh.	N.	VI. 152 172	Remains of walls.
Ashraf, Kh.	G.	XI. 106 114	<i>see</i> esh Sharaf, Kh.
'Asida, Kh.	He.	XII. 160 114	Foundations of church. Mosaic pavement, cisterns, tanks, caves, presses.
'Asira esh Shamaliya	N.	VII. 175 184	Traces of settlement on village site. To north, rock-cut cisterns and tombs, caves. Mosaics.
'Askar	N.	VII. 179 180	Tombs, rock-cut tunnel at spring, reservoir.
'Askar, Kh.	N.	VI. 163 177	<i>see</i> 'Uskur, Kh.
'Askariya, Kh.	RA.	IX. 167 149	Ruined fort and settlement. Walls, cisterns, vaults.
Asqalân	G.	XI. 107 119	<i>see</i> Ascalon.
'Asqalân, Kh.	RA.	IX. 163 144	Foundations, broken columns, rock-cut tombs.
'Asqalûn, Kh.	He.	IX. 144 121	Foundations, remains of buildings, rock-cut cisterns.
'Asur, Tell	RA.	X. 177 154	Rock-cut cisterns, foundations.
el 'Atar, Kh.	He.	XII. 139 114	Cisterns, foundations, quarried rock, terraces.
'Atâra, Kh.	Jm.	X. 171 143	Reservoir, ruins of walls and vault. Rock-cut press with tessellated floor, tombs.
'Atariya, Kh.	He.	XII. 141 117	Heaps of stones.
'Atarud, Kh.	N.	VII. 173 171	Artificial mound, square building, surface pottery, heaps of stones, foundations, caves, terraces, cisterns, rock-cuttings, presses.
el 'Atâwîna, Rujm	Ba.	XI. 108 093	Ruined rubble cisterns, surface sherds, two small rubbish mounds.
'Athlit (including Dustri, Kh.)	H.	IV. 145 233	Crusaders' castle and walled town. Artificial mound. Bath house. Crusader and Phœnician cemeteries. Including Kh. Dustri, and the whole area, containing roads, dykes, walls and rock-cuttings, bounded on the west by the sea; on the north by Wadi Dustri; on the east by Haifa—'Athlit track; on the south by a line drawn east and west and passing 50 m. south of the rock-cutting known as Bab el Hawa on the road to 'Athlit Station, and including the rock-cutting known as el Maqati'.
'Attiya, Rujm	Jm.	IX. 167 128	Cairn.
'Atraba, Kh.	He.	IX. 140 123	Foundations of village, mosaic floor. To north caves.
'Attainsi, Kh.	H.	II. 150 243	Foundations, terrace walls, rock-cuttings, surface pottery.

Name of Site	Sub-District	Map Reference	Description
'Attîl	TK.	VI. 157 197	Domed building in village. Column shafts, mosaic fragment, well, rock-cut cisterns and caves.
'Attîr, Kh.	He.	XII. 152 085	Ruined buildings, foundations, caves, tomb, cisterns, press, column shafts, capitals, Maqâm.
'Attûra, Kh.	Jm.	X. 177 138	<i>see</i> el Kharâba, Kh.
'Attûs, Kh.	He.	XII. 148 114	Ruined buildings, foundations, mill-stones, cisterns, caves.
'Attûsha, Kh.	T.	V. 196 237	Ruined houses, cisterns.
'Atuf, Kh.	N.	VII. 191 185	Foundations, caves, cisterns, wells.
'Auba, Kh.	S.	III. 194 276	<i>see</i> 'Uba, Kh.
'Auba, Wadi	S.	III. 195 276	<i>see</i> Mughir 'Uba.
'Auda, Kh.	G.	VIII. 119 125	Well, traces of ruins, surface pottery.
'Auda, Kh.	He.	XII. 142 113	<i>see</i> Beida, Kh.
'Aufar, Kh.	N.	VII. 171 178	Traces of settlement.
el 'Auja el Fauqa, Kh.	Jm.	X. 189 150	Ruins of settlement on partly artificial mound.
'Auja Hafir	Ba.	090 030	Partly artificial mound, remains of churches and monastic buildings with tessellated pavements and architectural fragments. Foundations of town and wells on the plain.
el 'Auja et Tahta, Kh.	Jm.	X. 195 150	Ruined buildings and foundations. Maqâm esh Sheikh Ibrahim. Ruined mills, conduits, reservoir. Traces of early settlement on bank of wadi.
'Aulam	T.	V. 197 230	<i>see</i> 'Ulam.
el 'Aura, Kh.	Ja.	VI. 133 172	Surface pottery, rubble and mosaic fragments, traces of press.
'Ausaj, Kh.	S.	III. 196 275	Foundations, heaps of stones. Rock tombs to south, cisterns.
'Ausat, Kh.	He.	XII. 146 105	<i>see</i> el Qûsatîn, Kh.
Avihayil	TK.	VI. 138 195	Ancient site. Surface pottery, rock-cuttings.
el 'Awantîya, Tell	G.	VIII. 117 137	Surface pottery on sand dunes.
el 'Azâzîma, Rujm	He.	XII. 144 111	Foundations.
'Aziz, Kh.	He.	XII. 158 093	<i>see</i> 'Uzeiz, Kh.
el 'Azizlyât, Kh.	S.	I. 212 292	Foundations, walls, cisterns.
'Azzâz, Kh.	Re.	IX. 148 157	<i>see</i> el 'Iddeisiya, Kh.
'Azzûn (er Ras)	TK.	VI. 156 176	Rock-cut pressing floor, cup marks, small reservoirs, tombs. To north wall (el Quseir), rock-cut cisterns.
'Azzûn, Kh. (Tabur)	TK.	VI. 139 178	Foundations of building, well, fragments of mosaic pavement, tombs.
'Azzûn, Kh.	N.	VII. 171 171	<i>see</i> er Ruweisûn, Kh.
'Azzûn Ibn 'Atma, Kh.	N.	VI. 152 170	Ruined mosque and other buildings of squared masonry north of village; rock cut cisterns; ancient material in village.
Ba'arna, Kh.	He.	XII. 156 109	Cisterns, foundations, tomb, caves. To north a press.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Bab Beit el Khirba	N.	VII. 175 173	Pool (rock-cut and built). Cistern, rock-cuttings, caves, cupmarks.
el Babliya, Kh.	G.	XI. 114 109	Rubble foundations, cisterns, surface pottery. Ancient well north of site.
Bablun, Kh.	H.	IV. 149 212	see Abu Hamád, Kh.
Badawiya, Tell	Nt.	III. 174 244	Artificial mound. Ruins of buildings, vaulted galleries, drafted masonry. Ruins of khan to east.
el Badd, Kh.	Jm.	X. 171 122	see Beit Bassa, Kh.
Badd el Burj, Kh.	RA.	IX. 167 156	Ruined watch-tower and buildings, vaults, tanks.
Badd Faluh, Kh.	Jm.	XIII. 171 119	Ruined walls, cistern.
Badd el Sawámi', Kh.	He.	XII. 141 115	Quarry, rock-cuttings, cistern, columbaria.
Badriya, Kh.	Bn.	V. 200 223	Foundations of buildings. Heaps of roughly dressed basalt stones.
Baghlán, Kh.	He.	IX. 137 122	Foundations, caves, cisterns, tombs, oil and wine presses cut in the rock.
el Bahá, Kh.	Ba.	XI. 110 093	Cisterns, traces of an old village. Surface pottery.
el Bahlawán, Kh. (Bawayik el Mashárfa)	Ba.	XII. 124 102	Scattered stones, fragments of mosaic, glass and pottery. Cistern, fragment of column shaft.
el Bahr, Rujm	Jm.	X. 198 131	Ruined buildings periodically submerged.
Bahr Beit Kufa (Bahrat Kufa)	Re.	IX. 146 153	Rubble masonry, dam.
Bakkita, Kh.	G.	XI. 108 110	Rubble foundations, surface pottery.
Bal'a	TK.	VI. 161 193	Tomb.
Balad esh Sheikh	H.	II. 154 242	Traces of ancient settlement, cisterns.
el Balala	G.	XI. 102 101	Remains of reservoir. Surface pottery.
Bal'ama, Kh.	J.	V. 178 206	Artificial mound. Ruined fort. Spring with rock-cut passage at foot of hill.
el Balaqiya, Kh.	TK.	VI. 133 182	Foundations, surface pottery, rubble, mosaic fragments.
Balás, Kh. (Musalla, Kh.)	G.	VIII. 116 124	Surface rubble, pottery, and tesserae, rubble pool; to south vaulted tomb chamber.
Baláta	N.	VII. 177 180	Ancient town partly excavated. Jami' 'Umari. Maqám en Nabi Yusuf.
Bal'ita, Kh.	RA.	VI. 156 162	see Tharida, Kh.
Balátun, Kh.	A.	III. 171 271	Ruined walls, cisterns, foundations, squared stones, rock-cuttings.
el Ballána, Kh.	S.	III. 192 258	Foundations, cisterns, rock-cuttings, walls. Remains of oil-presses. Sculptured lintel.
el Balu'	RA.	X. 170 148	Megalithic enclosure, quarry, flint chips.
el Balu', Kh.	A.	III. 178 266	Scattered stones. Surface pottery.
Banát Ya'qub, Kh.	S.	III. 209 269	Heaps of stones.
el Banáwi	Ba.	XII. 130 103	Ruined settlement, cave, rock-cut cisterns.
el Banáya	Re.	IX. 140 137	Ruined well, rubble foundations, pool.
Bani Dar, Kh.	He.	XII. 164 100	Ruined tower and foundations, cisterns, caverns, quarries.
Bani Fádil, Kh.	N.	VII. 186 165	Foundations of buildings, caves.

Name of Site	Sub-District	Map Reference	Description
Bani Na'im	He.	XIII. 166 103	Ancient buildings and architectural fragments in village. Mosque en Nabi Lât.
Bani Suheila	G.	XI. 086 084	Maqâm esh Sheikh Yusuf. Well. Traces of ruins at Jidr el Balad.
Banît, Kh.	S.	III. 199 206	see esh Sheikh Banît, Kh.
Banna, Kh.	A.	II. 167 276	Foundations, well, cisterns, rock-cuttings, tombs.
Bannâya, Kh.	He.	XII. 143 098	Foundations, rock-cut cisterns, caves.
Bannir	H.	IV. 161 223	see Giv'at Nu'ah.
Bâqâ el Gharbiya	TK.	IV. 155 202	Wells, cisterns, fragments of columns, mosaic pavement, rock-cut tomb.
Bâqâ esh Sharqiya	TK.	IV. 157 202	Cisterns, fragments of columns, capital.
Baqqâr, Kh.	He.	XII. 158 112	Ruined walls, foundations, cisterns, caves, Maqâm.
Baqra, Kh.	He.	XII. 142 112	Remains of building, foundations, rock-cut cisterns and caves, oil press, ancient road.
Barada, Kh.	Re.	IX. 151 141	Foundations, cisterns.
Barbara	G.	XI. 110 115	Three Maqâms with ancient materials.
Bardagha, Kh.	G.	VIII. 121 128	Artificial mound, foundations, domed building, ruined basin with round corner towers.
Bardala	N.	VII. 195 199	Foundations, rock-cut tombs, broken sarcophagi, grind-stone, caves.
Barfiliya	Re.	IX. 149 146	Cisterns, rock-cut press to east, ancient road.
Barghasha, Kh.	J.	V. 186 210	Remains of square fort with corner-towers. Foundations.
Barnîqiya, Kh.	TK.	VI. 145 172	Rubble foundations, reservoir. Surface pottery and tesserae.
Barqa	G.	VIII. 122 132	Remains of vault, rubble cistern. Rock-cuttings, surface pottery.
Barqît, Kh.	N.	VII. 175 169	see es Sâwiya, Kh.
Barra'ish, Kh.	Re.	VI. 153 162	Ruins of buildings and church, columns, bases, tessellated pavement, carved lintel, tombs, rock-cut cisterns, channels, cupmarks.
Barrat Qisâriya	H.	IV. 140 209-211	Traces of walls, surface pottery, glass and marble fragments in sand dunes.
Barrâta, Kh.	Ba.	XII. 123 088	Ruined cisterns, scattered stones, caves, olive-presses.
el Barrish, Rujm	Jm.	IX. 166 129	Cairn.
Barta'a	J.	IV. 159 209	Ruined village.
Baruk, Rujm	He.	XII. 164 096	see Bureik, Kh.
Barza, Kh.	A.	III. 180 269	Ruined buildings, foundations, fragments of column and base, rock-cut tank near spring.
el Basal, Kh.	He.	XII. 140 114	see Umm el Basal, Kh.
el Basal, Kh.	He.	XII. 148 119	see Umm el Basal, Kh.
Basaliya, Kh.	N.	VII. 193 178	Foundations of buildings, vault, remains of fort on bluff, cisterns.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
el Basâtîn, Kh.	N.	VI. 151 171	Ruined buildings with remains of oil-press, cistern.
Bash-sha, Kh.	G.	VIII. 115 124	Rubble cisterns. Surface pottery.
Bash-shit	Re.	VIII. 126 137	Traces of ruins, remains of building with niche.
el Bâsha, Kh.	He.	XII. 142 168	Foundations, caves, cisterns, tombs.
el Bâsha, Tell	Bn.	V. 203 210	see el Hamîr, Tell.
Basma, Kh.	J.	V. 177 211	Foundations. Rock-cut cisterns, caves. Surface pottery.
el Bassa	A.	II. 164 276	Village largely built of old material, mosaic pavements, cisterns, Rock-cut tombs.
Bassat Heit esh Shîd	Bn.	V. 196 211	Aqueduct.
Bassûm, Kh. (esh Sheikh Bassûm, Kh.)	T.	V. 196 238	Artificial hill, vaults, basalt ruins, columns and other ancient remains, caves.
Bât el Jabal, Kh.	A.	II. 164 277	Rock-cut and masonry walls, wine-presses, tombs, cisterns. Tanks cut in rock, caves.
Bat Shelomo (Umm el Jimâl, Kh.)	H.	IV. 151 223	Foundations, rock-cut tomb, architectural fragments.
Bât es Sih, Kh.	A.	III. 178 257	Ruined buildings, remains of church with apses, foundations, cisterns, rock-cuttings, carved lintel, architectural fragments.
Batâni esh Sharqi	G.	VIII. 124 129	Fragment of mosaic pavement, tank, foundations, surface pottery.
Batâshi, Kh.	Jm.	IX. 141 132	Remains of walls of hewn stones, heaps of stones, rock-cuttings.
el Batâshi, Tell	Jm.	IX. 142 132	Artificial mound with remains of fortification, wells. Surface pottery.
el Bâtîn, Kh.	RA.	X. 174 159	Foundations, rock-cut cisterns and tombs.
Bâtîn el Minawri	J.	VI. 167 199	Remains of settlement on prominent hill, rock-cuttings, presses, cisterns, spring, surface pottery.
Bâtîn el 'Ursh	Jm.	IX. 159 136	Watch-tower, heaps of stones. Cave to east.
el Bâtiya	Re.	IX. 137 142	Tessellated floor, surface sherds.
Batn el Hawa	Jm.	X. 173 131	Rock-cut tombs, cisterns, presses.
Batn es Saghir, Kh.	Jm.	IX. 159 132	see es Sugheiyar, Kh.
Batn et Tawil, Kh.	He.	IX. 136 125	Foundations of unhewn stones, surface flints, potsherds.
Batn el Yamani	Re.	IX. 145 152	Ancient cemetery, painted tomb.
el Batshân	G.	XI. 067 103	Tomb. Traces of ruins in sand dunes.
el Battikha, Tell	S.	I. 206 202	Artificial mound, surface pottery, scattered stones.
Battir	Jm.	IX. 163 126	Foundations of buildings, pool, caves, mosaic pavements. see also el Yahudiya, Kh.
el Baubariya, Kh.	N.	VI. 166 186	Extensive ruin with remains of triple vaulted building to west.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
el Bawāti, Kh. (el Hakamiya, Kh. Umm esh Sharāshih)	Bn.	V. 201 215	Ruined walls, foundations, milestones. Roman road, column fragments.
Bawayik el Mashārifā	Ba.	XII. 124 102	<i>see</i> el Bahlawān, Kh.
el Bawwāya, Kh.	Jm.	IX. 163 136	Ruins of buildings, well, ancient roads.
el Bayādir, Kh.	Jm.	X. 175 138	<i>see</i> Ras el Bayādir.
el Bazu'a, Kh. (Baz'awiya)	A.	III. 171 254	Remains of walls, foundations, olive- press, rock-outfittings, cave, cisterns.
Bazza, Kh.	G.	VIII. 117 123	Foundations and surface pottery over extensive area.
el Badd, Kh.	Jm.	X. 171 122	<i>see</i> Beit Bassa, Kh.
Beersheba	Ba.	XV. 130 072	Mosaic pavements, foundations, wells. Mounds with foundations and surface pottery east of the town.
el Beida, Kh.	H.	IV. 165 236	<i>see</i> Bir el Beidar, Kh.
el Beida, Kh.	Re.	IX. 148 156	Foundations. Olive-press, rock-cut cis- terns. Surface sherds and white tes- serae, quarries.
el Beida, Kh. (Auda, Kh.)	He.	XII. 142 113	Caves, cisterns, heaps of stones.
el Beida, Kh. Tell	He.	XII. 146 117	Foundations of buildings, carved lintels, fragment of column with cross, caves, cisterns, surface pottery.
el Beida, Tell	Nt.	IV. 169 232	Artificial mound.
Beidūs, Kh.	H.	IV. 153 207	Ruined village; building with door-posts, drafted masonry. Monolithic gate, cave, cisterns. To west: cemetery with rock- cut tomb, broken sarcophagus, rock- cut wine press. To south: reservoir, spring, head with arch.
el Beika, Kh.	H.	IV. 143 204	Foundations, limestone sarcophagus, sur- face pottery, column shafts.
Beikat Abu Hadba	Ba.	XII. 135 087	Heaps of stones and surface pottery, caves, well. Cisterns, decorated lintel reused.
Beikat Abu Mu'ailiq	Ba.	XI. 100 091	Ancient site. Cisterns and well.
Beikat es Sani'	Ba.	XI. 108 088	Ruins of cattle-shed.
Beiram, Kh.	He.	XII. 138 109	Foundations, heaps of stones.
Beisan	Bn.	V. 198 212	Ancient site, containing ruined city wall, foundations of buildings, a hippo- drome, theatre, medieval buildings re- used in present town mosque; tombs, bridges. Aqueduct. Architectural fragments. <i>see also</i> : el Husn, Tell; el Jisr, Tell; el Mastaba, Tell; el Kharāyib.
Beisiya, Kh.	He.	XII. 134 119	Foundations, heaps of stones, wells in bed of wadi.
Beit 'Affa	G.	XII. 122 119	Village built on debris of ancient settle- ment. Maqam. Architectural fragments, traces of ruins in the Wadi er Rana.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Beit 'Alam, Kh.	He.	XII. 145 110	Ruined buildings, caves, cisterns. To east remains of an ancient road and rock-cut channel.
Beit Alfa	Bn.	V. 191 214	Remains of synagogue with mosaic pavement.
Beit Amîn, Kh.	N.	VI. 152 171	<i>see</i> Beit Yamin, Kh.
Beit 'Amir, Kh.	He.	XII. 136 101	Foundations, heaps of stones.
Beit 'Amra, Kh. (Beit Imra, Kh.)	He.	XII. 155 095	Extensive ruin, remains of two churches and other buildings, ruined walls, press, cisterns, drafted masonry, column, shafts, lintels.
Beit 'Arif	Re.	IX. 143 152	<i>see</i> Ben Shemen.
Beit 'Awwa, Kh.	He.	XII. 145 102	Ruined buildings, remains of an apse, foundations, columns, font, cisterns cut in the rock, caves.
Beit Ba'ir, Kh.	He.	XII. 145 103	Ruined walls and foundations; caves, cisterns, press stones and mill stones; door posts: stone tanks, tomb-cave.
Beit el Bân	He.	XII. 145 105	Foundations, caves. Cistern to north.
Beit Bassa, Kh.	Jm.	X. 171 122	Ruined walls, rock-cut tomba.
Beit Bazzîn, Kh.	N.	VI. 165 162	Ruined walls and foundations, cisterns, caves, watch-tower. Surface pottery.
Beit Dajan	N.	VII. 185 178	Watch-tower, cisterns, rock-cut tomba.
Beit Dajan	Ja.	IX. 134 157	Fragment of ancient building in el Qal'a. Walls. Architectural fragments, tomb.
Beit Darâs	G.	VIII. 120 126	Foundations.
Beit Darâs	G.	XI. 109 108	Rubble foundations. Vaulted chambers.
Beit 'Einân, Kh.	He.	XII. 162 108	Ruined church with column-shafts, capitals, foundations, tower, reservoirs (with pipe-line), cisterns, mosaic floor. Ruins of buildings to south.
Beit Fajjâr	Jm.	XII. 165 115	Foundations of buildings and drafted masonry in village. Mosaic pavements. Remains of press. Rock-cut tomba. Cisterns, caves.
Beit Far, Kh.	Re.	IX. 142 134	Walls, foundations, caves. Scattered stones.
Beit Fasad, Kh.	He.	XII. 149 119	Remains of buildings. Foundations, cisterns, caves, tombs, rock-cut press.
Beit el Habs, Kh.	N.	VI. 163 166	Ruined vaulted chamber, remains of walls, heaps of stones.
Beit Hanân	Re.	VIII. 129 149	Mosaic pavement with inscription, foundations.
Beit Hanân	G.	XI. 106 106	Traces of ancient buildings, two Maqâms, a pool.
Beit Ikâ	He.	IX. 151 123	Ruined walls, caves; press stone, cistern with arched entrance.
Beit Ilsa	Jm.	IX. 167 136	Ruined vaults. Foundations.
Beit Iifa, Kh.	Bn.	V. 190 214	Foundations of buildings, walls, door posts, column, heaps of stones, broken sarcophagi.
Beit Illu (Beitillu)	RA.	IX. 161 154	Quarries and tomb caves.
Beit 'Imra, Kh.	He.	XII. 155 095	<i>see</i> Beit 'Amra, Kh.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Beit Imrin	N.	VII. 171 189	Traces of walls, sarcophagus used at spring, rock-cuttings, remains of tanks.
Beit Iryâ, Kh.	A.	II. 170 272	Ruined walls, cisterns.
Beit Irza, Kh.	Jm.	IX. 168 127	Cisterns, caves, tombs.
Beit 'Itab	Jm.	IX. 155 127	Remains of fort.
Beit Jabr el Fauqâni	Jm.	X. 190 139	Walls, vault.
Beit Jabr et Tahtâni	Jm.	X. 191 140	Small fort with fosse, ruined tank, aqueducts.
Beit Jâla	Jm.	IX. 168 125	Rock-cut cell with mosaic beneath church of St. Nicholas. Tomb caves.
Beit Jann	A.	III. 166 263	Ancient vaults and stones incorporated in village, cistern, springs and rock-cut tombs.
Beit Jann, Kh.	T.	V. 197 236	Ruins of settlement, foundations, architectural fragments, cisterns, rock-cut tombs.
Beit Jibrin	He.	XII. 140 113	Remains of church, fortifications, tunnel vaults, house with mosaic floors, other buildings, architectural remains. Tombs, caves, columbarium.
Beit Jidya, Kh.	N.	VI. 164 186	Ruined houses, cisterns, rock-cut and built pool; press. Cupmarks in rock.
Beit Jiffa, Kh.	TK.	VI. 156. 179	Walls, cisterns, ruined dome, rock-cut tombs.
Beit Jimâl	Jm.	IX. 148 126	Remains of church with mosaic. Tomb.
Beit Jirja	G.	XI. 110 112	Ancient foundations, well. Foundations east of village (er Rasm).
Beit Kanûn, Kh.	He.	XII. 151 112	Foundations, cisterns.
Beit ha-Kerem	Jm.	IX. 168 132	Megalithic constructions.
Beit Khalil er Rahmân	He.	XII. 160 107	see Ramat el Khalil.
Beit Kheirân, Kh.	He.	XII. 160 112	Remains of buildings and barrel vaults within walled enclosure. Cisterns.
Beit Kîka, Kh.	Jm.	IX. 169 135	Two ruined vaults. Rock-cut cisterns and cave.
Beit Kûfa, Kh.	Re.	IX. 146 153	Foundations of settlement.
Beit Lâhiya	G.	XI. 102 106	Fragments of columns, capitals and bases. Maqâm ash Sheikh Salim Abu Musallam.
Beit Lahm	H.	IV. 166 235	Ruins of buildings including church; column shafts, capitals, base. Cisterns.
Beit Lajûa, Kh. (el Butma, Kh.)	G.	XI. 110 112	Artificial mound, foundations, surface pottery.
Beit Lâm, Kh.	He.	XII. 149 112	Cisterns, caves, foundations, ruined walls. To south-west circular rock summit (altar?).
Beit Lei, Kh.	He.	XII. 143 108	Foundations, ruined walls, caves, cisterns, shaft of column.
Beit Lîd	TK.	VI. 163 185	Old material in village. Rock-cut pool 1 km. to south-west. Rock-cut tombs and cisterns to east.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Beit Lîd, Kh. (Hannûna)	TK.	VI. 140 192	Tomb, caves. Foundations of settlement, cistern. Square stones, marble capital, column shafts.
Beit Mâmin, Kh.	G.	XII. 122 116	Remains of rubble walls, well, column shafts.
Beit Maqdâm, Kh.	He.	XII. 147 105	Walls, foundations, cisterns, caves.
Beit Mirsim, Kh.	He.	XII. 141 096	Ruined walls and foundations; caves, mosaic floors. Remains of church converted into mosque, (Maqdâm en Nabi Handal).
Beit Mirsim, Tell	He.	XII. 141 096	Artificial mound partly excavated, with remains of outer wall and town.
Beit Mizza, Kh.	Jm.	IX. 165 134	Traces of settlement. Rock-cut cave.
Beit Nabâla	Re.	IX. 146 155	Stone door posts, cisterns at er Ras Abu Ya'qûb.
Beit Nasib el Gharbiya, Kh.	He.	XII. 150 111	Square ruin with enclosing wall and gate to east. Rock-cut and masonry tombs to south, cisterns.
Beit Nasib esh Sharqiya, Kh. (Beit Nasif)	He.	XII. 151 110	Ruined houses, foundations, door posts, cisterns. Large dressed stones to north.
Beit Nattîf	He.	IX. 150 123	Foundations, tombs, cisterns. Mosaic pavement, Roman milestones on 'Allâr road, columns.
Beit Nûba	Re.	IX. 153 140	Ancient foundations, rock-cut tomb.
Beit Nûshif, Kh.	RA.	IX. 155 143	Ruined walls, scattered tesserae, mouth of cistern.
Beit Qâd	J.	V. 184 208	Old mosque with ancient material, lintel in courtyard. To south ruined reservoir.
Beit Râs, Kh.	J.	IV. 162 221	Traces of settlement, surface pottery and dressed stones on hill. Rock-cut tombs on slopes.
Beit Rush, Kh.	He.	XII. 144 097	see er Rush et Tahta, Kh.
Beit Safâfa	Jm.	IX. 169 128	Two storeyed vaulted building (el Burj) in the village. Rock-cut tomb to east with carved pilaster.
Beit Sâhûr	Jm.	X. 171 123	Caves, cisterns. Tombs. Remains of monastic buildings, mosaic.
Beit Sallûm, Kh.	N.	VI. 167 182	Foundations, heaps of stones. On north rock-cut tombs. Rock-cut cisterns.
Beit Sâma, Kh.	TK.	VI. 158 190	Remains of watch-towers. Ruined walls and vaults, column shafts and architectural fragments. Masonry wells, rock-cut cisterns. Tombs to south and south-west.
Beit Sam'an, Kh.	G.	XI. 115 115	Rubble foundations, surface sherds, tesserae and marble fragments.
Beit Sâwîr, Kh.	He.	XII. 162 118	Ruined tower, foundations, cisterns, cave with stairs.
Beit Seila, Kh.	RA.	IX. 164 143	Ruined walls, vaults, rock-cut cisterns, caves, reservoir.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Beit Sha'ar, Kh.	He.	XII. 162 117	<i>see</i> Deir Sha'ar.
Beit ash Shabab, Kh.	Jm.	IX. 162 137	Foundations, rock-cut remains of press.
Beit Shanna	Re.	IX. 149 143	Foundations.
Beit Sikariya, Kh.	Jm.	XII. 161 118	Ruined walls, capitals, cisterns cut in the rock, lintel, fragments of columns.
Beit Sira	RA.	IX. 154 144	Old foundations, caves, circular pool.
Beit Sasin	Re.	IX. 148 135	Ruined walls, foundations.
Beit Ta'mir, Kh.	Jm.	X. 172 121	Stone with cup-markings, square vat, rock-cut tombs.
Beit Thal	Jm.	IX. 157 137	Foundations. Maqams with reused ancient columns.
Beit Tima	G.	XI. 116 115	Cistern, tessellated pavement, inscriptions. Capitals and architectural fragments in mosque and village.
Beit 'Ur el Fauqa	RA.	IX. 161 144	Ancient walls and foundations in village. Remains of Crusaders' tower (el Burj). Pool.
Beit 'Ur et Tahta	RA.	IX. 158 145	Ancient foundations and mosaic pavement in village, architectural fragments, ruins of chapel to north, wine-press, tomb.
Beit Yamin, Kh.	N.	VI. 152 171	Remains of walls, cisterns, rock-cut tombs. To east reservoir. Well of en Nabi Yamin. To north-east mosaic pavement.
Beit Zi'ta, Kh.	He.	XII. 162 114	Ruined walls, foundations, cisterns, aqueduct, tower, press, well, circular furnace.
Beitilla	RA.	IX. 161 154	<i>see</i> Beit Illu.
Beitin	RA.	X. 173 145	Foundations of ancient settlement. Pool, cisterns, caves, rock-cuttings, architectural fragments.
Beituniya	RA.	IX. 166 144	Ruined medieval building with arch (Bab el Balad), mosaic floor, caves, tombs, rock-cut pools and cisterns, rock-cut press, column fragments. To east of village ruined medieval vault.
Beiyarat Bureij (Umm Zubeila, Kh.)	Jm.	IX. 143 127	Rock-cut cistern and wine press.
Beiyin, Kh.	T.	V. 187 239	Ruins, cisterns, caves, tombs, presses, masonry well, rock-cut basins.
Beiyadat, Kh.	He.	XV. 162 079	Traces of settlement, caves, cisterns.
Beiyadat, Kh.	Jm.	X. 195 153	Watch-towers, artificial mound. Ruined buildings and foundations of houses.
Beiyas, Kh.	He.	XII. 161 119	Foundations, rock-cut cisterns, caves.
Ben Shemen (Beit 'Arif, el Khirba)	Re.	IX. 143 152	Low mound with surface pottery at el Khirba. Rock-cut tombs.
Benei Beraq	Ja.	VI. 135 166	Traces of settlement, mosaic pavement. Remains of dam in wadi, tombs.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Benyamina	H.	IV. 146 214	Artificial mounds in eucalyptus forest, with surface pottery, marble fragments and tiles. Including Maqbarat el Bu-reij: foundations, columns. Artificial mound on west, tombs, quarries.
Beth Shemesh	Jm.	IX. 148 129	see Rumeila, Kh.
Bethlehem	Jm.	IX. 170 124	Ancient site. Church of Nativity, and adjoining Byzantine and medieval buildings. Rock-cut tombs, cisterns, aqueducts.
Bidya	H.	VI. 157 169	Rock-cut tombs, pool, ruined watch-tower. Second pool to north-west.
el Bi'na	A.	III. 176 259	Artificial mound, cisterns, under-ground chambers, partly built, partly rock-cut. Rock-cut tombs.
B'inna, Kh.	Re.	IX. 149 155	Ruined walls and foundations.
Bint Nûh, Kh.	Jm.	IX. 155 125	Heaps of stones, ancient terrace walls, rock-cut tombs, spring with arched vault.
el Bir, Kh.	H.	IV. 164 236	Artificial mound. Wall, foundations, built well.
el Bir, Kh.	Jm.	IX. 143 139	Foundations, surface pottery and rubble, rock-cuttings.
el Bir, Kh.	G.	XI. 105 098	Surface pottery, ruined cisterns.
el Bir, Kh.	He.	XII. 140 104	Traces of settlement, caves, large pool.
Bir el 'Abd	TK.	VI. 148 199	Surface pottery and stones, built well.
Bir Abu Daraj	N.	VII. 191 170	Well, cairn of unhewn stones.
Bir Abu Jureida	Ba.	XIV. 096 075	Ancient well, tanks. Mosaic pavement.
Bir Abu Mansur	Ba.	XII. 124 089	Traces of ancient settlement, foundations.
Bir Aiyûb	Jm.	X. 172 130	Well.
Bir el Autâd	He.	IX. 141 129	see Umm el Autâd, Kh.
Bir el Bal'ama	J.	V. 178 206	see Bal'ama, Kh.
Bir el Beidar, Kh.	H.	IV. 165 236	Artificial mound, rock-cut tombs.
Bir Beit el Bayâda	RA.	IX. 156 140	Foundations, wall, barrel-vaulted cistern, caves.
Bir Birein	Ba.	000 020	Traces of settlement on ridge, dry stone building, stone circles, flint cairn south-east of well. Surface pottery.
Bir el Biyâr, Kh.	RA.	IX. 168 140	Traces of settlement, walls, foundations, cisterns.
Bir Bunduq, Kh.	Re.	VI. 147 160	Foundations on small knoll, cisterns, surface pottery.
Bir Bûrin	TK.	IV. 153 203	Masonry well, scattered building stones.
Bir ed Dawali, Kh.	RA.	IX. 165 144	Foundations, tank with tessellated pavement.
Bir Dawûd	He.	XII. 145 102	Rock cistern, tombs, well.
Bir ed Duhdâh	He.	XII. 160 107	Foundations, caves, rock-cut tombs, wells.
Bir el Gharbi, Tell	A.	II. 166 256	Artificial mound, scarped; foundations of walls; well to south-west, broken columns.

Name of Site	Sub-District	Map Reference	Description
Bir el Hajj Ramadan	He.	XII. 163 117	Vaulted cistern. Traces of building with niche.
Bir el 'Idd, Kh.	Jm.	IX. 151 134	Ruined walls, caves, cistern, well.
Bir Ijda	He.	XII. 160 107	Well, traces of buildings.
Bir Iktil, Kh.	A.	II. 168 265	Extensive ruins, dressed masonry, foundations, wine and olive presses, cisterns, broken columns, tombs.
Bir el 'Iraq, Kh.	RA.	IX. 165 144	see Bir esh Shâfi'.
Bir el Jân, Kh.	N.	VI. 154 172	Foundations.
Bir el Jokhadar	G.	VIII. 121 127	Well, cisterns, foundations.
Bir Kafr Nabîd, Kh.	A.	II. 163 274	see Kanîsat el 'Amari.
Bir el Khazna	A.	II. 164 270	Small ruin on top of plateau. Heaps of stones, foundations, two rock-cut cisterns.
Bir Khuweilfa	Ba.	XII. 136 089	Ruins of hill south of the well, foundations, caves.
Bir el Leimûn	Re.	VIII. 126 140	Ruined pool.
Bir el Leimûn	Jm.	IX. 145 128	see el 'Uqda, Kh.
Bir el Maksûr, Kh.	H.	III. 171 242	Ruined walls, foundations, door posts, column fragments, caves, tombs cut in the rock, well.
Bir Mureitiba	Ba.	XV. 156 045	Ancient terrace wall, area of ancient cultivation, walls and towers.
Bir Nabala	Jm.	IX. 169 139	Remains of vaults.
Bir en Najjâr	Re.	IX. 148 142	Cistern.
Bir Nâsir, Kh.	RA.	IX. 161 145	see el Qureina, Kh.
Bir el Qantara	Jm.	IX. 148 132	Tank.
Bir el Qasr, Rujûm	He.	XII. 147 091	Foundations of buildings, presses, rock-cut cisterns, tomb.
Bir el Qattar	Jm.	X. 184 126	Cistern, rock-cut cave, masonry.
Bir er Rugeish (er Rugeish, Tell)	G.	XI. 086 091	Iron Age cemetery.
Bir es Saharij	G.	VIII. 124 124	see es Saharij, Kh.
Bir esh Shâfi' (Bir el 'Iraq, Kh.)	RA.	IX. 165 144	Ruined walls and foundations of rectangular buildings.
Bir esh Sheikh	S.	IX. 196 267	Ruined dolmen.
Bir Shuqeir	G.	VIII. 110 124	Rubble foundations, pottery, pool.
Bir esh Shuweihâ, Kh.	N.	VII. 186 179	see Shuweihâ, Kh.
Bir es Sinjib	J.	V. 178 206	Well with rock-cut passage.
Bir Summeil	G.	XII. 130 117	Well, surface pottery, marble columns.
Bir Tibis, Kh.	Nt.	V. 181 227	Traces of settlement.
Bir Wadi Fa'i	Ba.	XVI. 171 082	Ancient well.
Bir el Wastîya	G.	XII. 128 117	Remains of a cistern and channel. Rubble foundations, surface pottery.
Bir Ya'qûb (Jacob's Well)	N.	VII. 177 180	Well, architectural fragments.
Bir ez Zeibâq	Re.	IX. 139 150	Domed building over well.
Bir Zeit, Kh.	RA.	IX. 168 153	Ruined walls and vaults, cisterns, rock tombs.
el Bira	Bn.	V. 197 223	Ruins of village, columns.

Name of Site	Sub-District	Map Reference	Description
el Bira	RA.	X. 170 146	Remains of medieval church, khan with vaults and glacis to west, pool. Vault with press. Arabic inscriptions. Rough enclosures of large stones about 1200 m. north of the village on the east side of the Nablus road. (X. 170 147)
el Bira, Kh.	G.	VIII. 114 120	Traces of ruined buildings, foundations, cisterns, surface pottery.
el Bira, Kh.	Re.	IX. 147 158	Ruined walls, foundations, heaps of stones, rock-cut caves, wells, cisterns, three pools, ruined church, columns, quarries, tombs.
el Bira, Kh.	Jm.	IX. 165 121	Remains of buildings, oil and wine presses, tessellated floor and vats, cisterns, rock-cut cave with stair, threshing floor.
el Bira, Kh.	He.	XII. 143 094	Walls, caves, tombs.
Birein, Kh.	He.	XII. 164 100	Remains of square tower, caves, cisterns, rock-shelters, traces of ancient roads.
Birkat Abu et Tauq	He.	XII. 141 095	see el Burj, Kh.
Birkat 'Ali edh Dhahr	T.	III. 202 253	see et Tâbgha.
Birkat el Beida	A.	III. 185 252	Ruined pool.
Birkat Bint es Sultân	Jm.	XIII. 173 120	see Birkat el Hammam.
Birkat el Fakht (Sde Nahum)	Bn.	V. 195 215	Vaulted cistern.
Birkat el Hammam (B. Bintes Sultân)	Jm.	XIII. 173 120	Remains of pool, traces of ruins.
Birkat el Jamus	Re.	IX. 139 148	Large masonry pool.
Birkat Juljuliya	Jm.	X. 106 140	see en Nitla, Tulûl.
Birkat el Juba	Jm.	X. 177 126	Masonry pool.
Birkat Musa	Jm.	X. 192 139	Pool fed by an aqueduct.
Birkat er Rabba	Re.	VI. 146 161	Pool.
Birkat Tarjam	S.	I. 201 282	Dolmen.
Birkat Timsâh	H.	IV. 144 218	see Kabâra, Kh.
Birkat el Waqa'	Re.	IX. 147 158	Ruined pool.
el Biriya, Kh.	Re.	IX. 147 150	Traces of settlement. Accumulated debris. Stones, cisterns.
Bishr, Kh.	He.	XII. 143 106	Foundations, heaps of stones, caves, cisterns.
Bism, Kh.	He.	XII. 153 096	Walls and foundations. Remains of building with column shafts and lintel, cisterns, caves, tombs, rock-cut pool.
el Biss, Kh.	He.	XII. 146 113	Ruins of three buildings. Rock-cut cave with stairs and niches, cisterns, caves.
el Biyar, Kh.	A.	III. 179 272	Ruined walls, pool. Mosaic, cut stones, cisterns, olive-presses, tombs.
el Biyar, Kh.	H.	IV. 161 213	Scattered stones.
el Biyar, Kh. (er Rasm)	G.	VIII. 119 122	Ruined rubble constructions, cisterns, surface pottery.

Name of Site	Sub-District	Map Reference	Description
el Biyâr, Kh. (Qeduma, Ta'abiya, Kh.)	G.	VIII. 123 127	Foundations, cisterns.
el Biyâr, Kh.	RA.	IX. 168 140	see Bir el Biyâr, Kh.
el Biyâr, Kh.	Jm.	IX. 169 137	see Farraj, Kh.
el Biyâr, Kh.	G.	XI. 109 108	Cisterns, foundations, surface pottery.
el Biyâr, Kh.	Ba.	140 100	Roman road, remains of houses, cemetery.
Biyâr 'Ar'ara	Ba.	XV. 148 062	Remains of enclosure walls.
Biyâr el Ka'ba, Kh.	G.	VIII. 123 127	see el Biyâr, Kh.
Biyâr el Qasals (el Qasals, Kh.)	Jm.	X. 174 124	Foundations, walls, mosaic pavements, rock-cut cisterns and tombs.
el Biyâra, Kh.	A.	III. 174 290	Ruined walls, apse, remains of press, cisterns, dressed stones.
Brukin	N.	VI. 160 164	see Burqin.
Bûda, Kh.	A.	II. 164 296	Foundations, caves, cisterns, tombs.
Budghush, Kh.	He.	XII. 139 094	Foundations, caves, rock-cisterns, surface pottery.
Budiya, Kh.	S.	III. 186 272	Ruined walls, cisterns, columns (standing), presses, rock-cut tombs.
Budrus, Kh.	Re.	IX. 148 153	Ruined walls, doorposts, cisterns cut in the rock, tombs, oil press with up-rights.
Bu'eina	Nt.	III. 184 246	Vault, tombs, rock-cut pool.
el Buheira, Kh.	Ba.	XII. 133 110	Mosque (ancient church).
el Buqei'	Jm.	IX. 169 133	Scattered stone, rubble and pottery.
Buqei' Dan, Kh.	Jm.	X. 176 133	Ruined walls and foundations.
el Buqei'a	A.	III. 182 264	Traces of ruins.
			Foundations, architectural fragments, rock-cut tombs, caves, carved stones reused in the synagogue, presses.
el Burak (Solomon's Pools)	Jm.	IX. 166 122	Pools, aqueducts, spring head.
el Burak, Kh.	H.	IV. 156 214	Traces of ruins.
el Burak, Kh.	N.	VI. 161 168	Rock-sunk tombs, rock-cut cisterns, wine press.
Burbâra	RA.	IX. 157 158	see 'Abâd.
Bureida, Kh.	Ba.	XII. 138 098	Foundations, caves, cisterns, well.
el Bureij	Ba.	XI. 093 094	Foundations, rubble remains, pool, surface pottery and marble chips on rising ground.
el Bureij, Kh.	N.	VI. 161 168	see el Burak, Kh.
el Bureij, Kh.	Jm. RA.	IX. 158 141	Traces of ruins.
el Bureij, Kh. Tell	H.	IV. 147 214	Low mound, foundations. Granite columns. Heaps of stones, marble fragments, broken sarcophagus.
Bureik, Kh. (Rujm Baruk)	He.	XII. 164 006	Watch-tower, caves.
el Bureika, Kh.	H.	IV. 149 216	see el Khirba.
Bureikût, Kh.	He.	XII. 164 117	Ruined walls, foundations, cisterns, a rock-cut pool, caves.
Bureir	G.	XI. 116 109	Well, ancient stones and architectural fragments in village.
Burhan, Kh.	N.	VI. 148 172	see Miryam, Kh.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Bārīn	N.	VII. 174 177	Caves, rock-cut wine presses and vats; wall of ancient materials.
Bārīn, Kh.	TK.	VI. 149 191	Artificial mound, foundations.
el Burj (el Habis, Qal'at Tantûra)	Re.	IX. 152 145	Ruined tower, mosaic pavement.
el Burj	S.	III. 190 267	Ruined watch-tower.
el Burj (Burj el Jaj)	G.	IX. 131 133	Surface pottery and rubble.
el Burj, Kh.	H.	IV. 143 224	see Tantûra.
el Burj, Kh.	TK.	VI. 145 192	see Burj el 'Atut.
el Burj, Kh.	RA.	VII. 174 181	Ruined tower and walls, rock-cut tombs, cisterns, cup-marks.
el Burj, Kh.	He.	IX. 153 123	Tower with carved lintel, cistern, wall foundations. Remains of press with up-rights.
el Burj, Kh.	Jm.	IX. 168 137	Remains of tower, foundations of buildings, tomb.
el Burj, Kh.	RA.	IX. 169 148	Remains of tower.
el Burj, Kh.	RA.	X. 175 156	see Burj el Lisâna.
el Burj, Kh. (Birkat Abu et Tauq, Qal'at el Burj)	He.	XII. 141 095	Ruined medieval castle. (Qal'at el Burj) with rock-cut fosse. Caves. Pool (Birkat Abu et Tauq). Foundations.
el Burj, Kh.	He.	XII. 151 111	see Burj Beit Nasif.
Burj el 'Atut (el Burj, Kh.)	TK.	VI. 145 192	Remains of tower, vaults, traces of pool, foundations.
Burj el Baiyâra	He.	XII. 141 094	Remains of fort, rock-cut caves, foundations.
Burj Bardawil	RA.	X. 173 155	Ruins of castle. Tunnel vaults, drafted masonry. Well.
Burj Beit Nasif (el Burj, Kh.)	He.	XII. 151 111	Ruined vault, remains of wall to west, foundations, vaulted cisterns.
Burj Beitîn	RA.	X. 173 148	Ruins of fort. Foundations of church and monastery. Traces of portico, cistern, tomb, caves.
Burj Daiyîqat el Amîrîn	Ba.	XV. 122 096	Block-house.
Burj el Far'a, Kh.	N.	VII. 183 188	Ruined enclosure wall, tower, unfinished fosse or pool, presses.
Burj el Hammar	Jm.	X. 180 125	Small ruin with tumulus in centre, remains of arched buildings.
Burj el Hanîya, Kh.	Re.	IX. 147 159	Foundations of tower. Rock-cut cistern.
Burj el Haska	He.	XII. 159 108	Tower, traces of ruined mosque and other buildings (including el Habis). Cave with press.
Burj el Jaj	G.	IX. 131 133	see el Burj.
Burj el Lisâna (el Burj, Kh.)	RA.	X. 175 156	Ruined walls, gateway, tower. Remains of building with fallen columns and bases, cisterns.
Burj el Mâlih	N.	VII. 193 193	Ruined fortress. Remains of vault; drafted and rough-hewn masonry.
Burj Masr	A.	III. 177 273	Ruins of tower.

Name of Site	Sub-District	Map Reference	Description
Burj Qarrīt (Qarrīt, Kh.)	Jm.	X. 177 130	<i>see</i> el Kharāyib, Kh.
Burj es Sahl	H.	II. 162 243	Mound probably artificial. Ruins of tower, masonry well to west.
Burj es Sār, Kh.	He.	XII. 159 110	Tower, ruins, rock-cut tombs.
Burj et Tāt	Jm.	IX. 168 133	Foundations, rock-cut cisterns, pool, press, tombs.
el Burjaliya	G.	XII. 132 112	Foundations, caves, stones, fragments of mosaic pavement.
el Burjaliya, Kh.	G.	XI. 098 094	<i>see</i> el Wuheidi, Kh.
el Burnāt, Kh.	Re.	IX. 147 157	Foundations. Heaps of stones, caves, rock-cut cisterns.
Burnāt, Tell	He.	XII. 138 115	A mound partly artificial; terrace walls; square enclosure on summit.
Burnāta, Kh.	He.	XII. 138 116	Foundations, heaps of stones, cisterns, caves.
Burqa	N.	VI. 168 190	Rock-cut caves.
Burqin	N.	VI. 160 164	Ancient remains, tombs. Fragments of cornice.
el Bustān, Kh.	H.	IV. 151 234	Ruined walls, foundations, caves, rock-cuttings, rock-cut tombs.
el Bustān, Kh.	He.	IX. 147 121	<i>see</i> el Mas'ud, Kh.
el Butm, Kh.	He.	XV. 148 097	Foundations, caves.
el Butma, Kh.	G.	XI. 110 112	<i>see</i> Beit-Lajās, Kh.
el Buwaiyira, Kh.	Re.	IX. 151 142	Foundations of rectangular building with cisterns.
el Buweib, Kh.	He.	XIII. 165 097	Walls, cisterns.
el Buzeiriya, Kh.	A.	III. 178 277	Walls and foundations of houses, door-posts, parts of olive-presses, cisterns, column fragments, stone coffins with lids.
Caesarea (Qisāriya)	H.	IV. 140 212	Remains of Roman town, walls, harbour, hippodrome, theatre, temple. Crusader walls, glacis, fosse, vaults, basilica. Foundations, architectural fragments, mosaics, rock-cuttings, aqueducts.
Dabāyib 'Antar	Bn.	V. 196 206	<i>see</i> Dabāyib en Nawar.
Dabāyib Jurat el Fijil	Bn.	V. 197 213	<i>see</i> el Mastaba, Tell.
Dabāyib en Nawar (Dabāyib 'Antar)	Bn.	V. 196 206	Ancient cemetery, tumuli, stone coffins, surface pottery.
Dabāyib et Tuwāl	Bn.	V. 199 213	Foundations of walls, cut stones, mosaic floor, rock-cut tombs.
Dabbat el Khan	A.	II. 165 251	Roman milestones, road station.
Dabbat el Mughr	Nt.	III. 187 243	Caves.
Dabbat el Mughr	TK.	VI. 139 183	Caves or tombs.
Dabbat Tell Hamār	S.	III. 192 271	Tomb.
Dabbura, Kh.	Nt.	V. 186 234	Heaps of stones, foundations, tombs and cisterns cut in the rock.
Dabbūriya	Nt.	V. 185 233	Foundation of church. Remains of fort (under mosque). Arabic inscription. Tombs, cisterns; mosaic floor.
Dabbus el 'Abd	Jm.	X. 166 137	Milestone.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Dabu	Bn.	V. 189 226	Ruins of village and of small mosque. Heaps of stones.
ed Dafayis, Kh. (Dufeis, Kh.)	H.	IV. 150 315	Ruined walls. Scattered foundations and stones, surface pottery.
Dahi, Kh.	H.	IX. 152 123	Foundations.
ed Dakâkin	Re.	VIII. 121 145	<i>see</i> Minat Rubin.
ed Dakki, Kh.	Jm.	X. 177 130	<i>see</i> el Kharâyib, Kh.
Daldâm, Kh.	G.	XI. 116 114	Scattered stones, ruined cisterns, surface pottery.
Dalhamiya, Kh.	T.	V. 204 229	Artificial mounds. Surface stones and pottery.
ed Dâliya, Kh.	RA.	IX. 154 146	Foundations, rock-cut cisterns, tomb, presses, column fragments, ancient road.
Dâliyat el Karmil	H.	IV. 153 233	Foundations, cisterns, tombs, rock-cut- tings, presses, architectural fragments in village.
Dallâta	S.	III. 197 270	Tombs, foundations, caves, cisterns, circ- ular pool.
Daluq	N.	VII. 190 172	Pile of stones.
ed Dâmiya	N.	VII. 185 168	Scattered heaps of stones, cisterns.
ed Dâmiya, Kh.	T.	V. 194 239	Extensive ruins, foundations, pool, olive-press, fragments of columns.
ed Dâmân	A.	II. 167 254	Well, ancient remains to west of village.
ed Dâmân, Kh. (ed Duweimin, Kh.)	H.	IV. 152 238	Ruined walls, rock-cut tombs and cis- terns, rock-cut pool, cornice fragments.
Dâniyân, Kh.	A.	II. 161 277	Heaps of stones.
Daqla, Kh.	RA.	IX. 168 159	<i>see</i> Jarwân, Kh.
Daqûriya, Kh.	G.	VIII. 121 129	Surface pottery and rubble.
ed Dar, Kh.	He.	IX. 151 123	<i>see</i> es Sarâsira, Kh.
Dar ed Darb (Deir ed Darb)	N.	VI. 160 170	Rock-cut tombs, watch-towers.
Dar ed Dîb, Kh.	N.	VII. 171 165	Foundations of buildings, rock-cut cis- terns and caves. Pottery.
Dar Haiya, Kh.	RA.	X. 177 150	Foundations of walls, rock-cut cisterns, oil press, two wells.
Dar el Hamad, Kh.	N.	VI. 160 166	<i>see</i> Hamad, Kh.
Dar Ibrahim, Kh.	RA.	IX. 158 157	Foundations, heaps of stones, column fragment, cisterns cut in the rock.
Dar Mustafa, Kh.	Re.	IX. 153 138	Traces of foundations, rock-cut cisterns, pool with steps.
ed Darajat, Kh.	Ba.	XV. 157 097	Caves.
Darajat Wadi es Sana'	He.	IX. 153 124	<i>see</i> Shallâlat Umm el 'Umdân.
ed Darbi, Kh. Rujm	He.	XII. 133 118	Scattered stones, surface pottery.
Dash-sha, Kh. (Araka, Kh.)	N.	X. 195 159	Ruined walls, pool, tower, enclosures, aqueduct from Kh. Fasâyil.
Dasra, Kh.	Re.	IX. 150 156	Ruined walls. Rock-cut cisterns and caves, tombs, remains of a tower.
Da'uk, Kh.	A.	II. 162 253	Ruined walls, foundations, cisterns.
Da'wajiya, Kh.	S.	III. 191 269	Foundations, heaps of stones, pressing floor and rock-cut vats.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Dawarta	N.	VII. 177 179	Remains of vaulted rooms. Loose tesserae.
ed Dawasa, Kh.	He.	XV. 148 097	see el Butm, Kh.
ed Dawcima	He.	XII. 142 105	Village on ancient site, well, rock-cut cistern, tombs.
ed Dei'a, Kh.	S.	I. 211 293	Low artificial mound, traces of walls, surface pottery.
ed Deidaba, Kh.	A.	II. 167 262	Foundations of walls, dressed stones, moulded fragments, rock-cut tombs and cisterns, fragments of mosaics.
Deidaban, Kh.	J.	VII. 172 194	Remains of masonry.
ed Deir	T.	V. 195 236	Foundations, heaps of stones, cistern, column shaft, capital, lintels.
ed Deir	Re.	VIII. 126 142	Remains of buildings, rock-cut tombs.
ed Deir	He.	XII. 143 093	see ed Duma, Kh.
ed Deir, Kh.	H.	II. 148 245	Ruins of the monastery of St. Brocardus, caves. Vaulted tunnel.
ed Deir, Kh. (Kh. Nashā)	N.	VI. 148 169	Ruins of two buildings. Rock-cut pool to west, ruined building and cistern, masonry, pool.
ed Deir, Kh.	RA.	VI. 165 162	Ruined monastery consisting of vaulted rooms, walls and foundations. Rock-cut tombs, pool, cisterns and press, traces of white mosaic floor.
ed Deir, Kh.	N.	VI. 163 185	see ed Duweir, Kh.
ed Deir, Kh.	N.	VII. 171 173	Foundations and walls, vaults, rock-cut cisterns, cup-marks.
ed Deir, Kh.	N.	VII. 187 191	Heaps of stones, foundations.
ed Deir, Kh.	Jm.	IX. 160 192	Ruined vaults and buildings, foundations, street, rock-cut cisterns.
ed Deir, Kh.	He.	XII. 152 118	Ruined walls, foundations, rock-cut caves and cisterns.
ed Deir, Kh. (Wadi el Jihar)	He.	XIII. 174 104	Remains of church and monastery consisting of walls, rock-cuttings, wall paintings, mosaics, chancel-post, decorated slabs, caves, tombs.
ed Deir, Rujm	Jm.	IX. 163 129	Cairn.
ed Deir, Rujm	He.	XII. 157 096	Remains of square building on hill-top, well.
Deir Abu 'Ali	He.	IX. 151 125	Remains of monastery consisting of ruined walls and doors; cisterns, press, caves.
Deir Abu Mash'al	RA.	IX. 156 156	Rock cut pool with steps; vaulted cisterns. West of village remains of tower. Pavement over arched cistern. Rock-cuttings and tombs. Old masonry in village.
Deir Abu Qābūs	Jm.	IX. 151 133	Ruined walls, cisterns. Remains of presses, rock-cut tombs.
Deir Abu Salama	Re.	IX. 146 151	Rock-cut tomb with Greek inscription, 1200 metres west of village.
Deir Abu Sukūb	RA.	X. 181 158	Remains of a monastery. Fallen walls and foundations. Surface pottery.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Deir 'Alla, Kh.	Re.	IX. 149 150	Ruined town. Roman road, milestones, rock-cut cisterns, pool, rock-tombs.
Deir 'Amr, Kh.	Jm.	IX. 150 132	Ruined walls, cisterns, caves.
Deir el 'Amud, Kh.	Jm.	X. 173 125	Foundations, cisterns.
Deir el 'Arabi, Kh.	Re.	IX. 152 158	Remains of monastery with ruined walls, vault, pools. Ornamented lintel, cisterns, column shafts, pressing floor and vat.
Deir el Arba'in	He.	XII. 150 104	<i>see</i> er Rumeidi.
Deir el Asad	A.	III. 176 260	Remains of Crusaders' church. Barrel vault to north; two towers. Caves, rock-cut tombs.
Deir el 'Asal esh Shāmiya, Kh.	He.	XII. 145 096	Ruined buildings, remains of church with three apses, caves, cisterns. Press with uprights, tombs, well.
Deir 'Asfur	Jm.	IX. 148 125	Ruined buildings, foundations, mosaics, presses, cisterns.
Deir el Ashiq	He.	IX. 140 131	Pool, foundations, scattered and heaped stones, caves, wall, cistern.
Deir el 'Azar (Deir el Ashar)	Jm.	IX. 160 135	Mosaic pavements, capitals, architectural remains, rock-cut wine press, cisterns, surface pottery.
Deir Bajjāla, Kh. (Deir Ibjāla)	N.	VI. 166 169	Ruined walls and vaults.
Deir el Balah	G.	XI. 088 092	Remains of church beneath mosque (el Khadr). Inscriptions in mosque. Including er Rasm to east and Tell esh Shuqaf (surface pottery).
Deir Ballut	N.	VI. 153 163	Foundations, rock-tomb.
Deir el Banāt	Jm.	IX. 162 134	<i>see</i> Iqbala, Kh.
Deir el Banāt	Jm.	IX. 166 121	Large ruined building with drafted masonry. To north rock-cut aqueducts.
Deir el Bunduq	N.	VII. 174 180	<i>see</i> Hawakir Bana.
Deir el Butm, Kh.	He.	IX. 138 193	Foundations, cisterns, caves.
Deir Daqla, Kh.	Re.	VI. 152 162	Ruined buildings, vaults, walls, pool, rock-cut cisterns, tessellated pavements. To west press with tessellated floor and vats, tombs.
Deir ed Darb	N.	VI. 160 170	<i>see</i> Dar ed Darb.
Deir Dhakir	Re.	IX. 143 139	Foundations of buildings, caves, well.
Deir Dosi	Jm.	X. 177 125	<i>see</i> Deir Ibn 'Ubeid.
Deir ed Dubban	He.	IX. 140 120	Foundations, fragments of mosaics, tombs, rock-cut press.
Deir ed Duma, Kh.	He.	XII. 148 093	<i>see</i> Duma, Kh.
Deir Dusāwi, Kh.	G.	XI. 107 101	Foundations, surface pottery, rubble cisterns.
Deir el Fiqya, Kh.	RA.	VII. 176 161	<i>see</i> Ras ed Deir, Kh.
Deir Ghannam, Tell	Jm.	X. 193 143	Traces of ruins, heaps of stones. Two presses, artificial mound, architectural fragments.
Deir el Ghāwi	He.	XII. 142 096	Caves, ruined walls, ancient road, rock-cut press.
Deir Ghazzāla	J.	V. 184 212	<i>see</i> Wa'rat el Kabbāra.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Deir Habib, Kh.	S.	III. 198 277	Ruined enclosures, heaps of stones, cistern.
Deir Hajla	Jm.	X. 198 136	Mosaic pavements, medieval monastery rebuilt.
Deir Hanna	A.	III. 184 252	Fortified village, rock-cut cisterns, tombs, pool. Five ruined towers outside the village.
Deir Harrasha, Kh.	RA.	IX. 164 150	Foundations of building, rock-cut wine-press to east. Remains of town, detached tower to south-east. Ancient roads. To north plastered cistern; tomb cave to east at foot of hill.
Deir Hassân, Kh.	RA.	IX. 160 146	Traces of a small ruin. Rock-cut cisterns and tombs to north of the site.
Deir el Hawa	J.	IV. 164 217	Foundations, scattered stones.
Deir el Hawa	Jm.	IX. 154 129	Carved stones, columns and chancel post reused in village. Ruined walls, terraces, cisterns, caves and quarries in vicinity.
Deir el Hawa	He.	XII. 143 086	Ruined monastery, foundations, cistern, ancient road, rock-cut wine press.
Deir el Hawa esh Sharqiya	Jm.	IX. 155 129	Rock-cut and built pool. Cisterns. Rock-cut tombs. A mosaic floor, buried.
Deir Ibjâla	N.	VI. 166 169	<i>see</i> Deir Bajjâla, Kh.
Deir Ibn 'Ubeid (Deir Dosi)	Jm.	X. 177 125	Ruined church partly reconstructed, foundations, mosaic pavement, crypt with tombs, columns, capitals, bases.
Deir 'Isfin, Kh.	TK.	VI. 146 184	Foundations, vault (el Hammam), cisterns, fragments of tessellated pavement.
Deir Istiyâ	N.	VI. 163 171	Two mosques (Jami' en Amisiya, Jami' Deir Istiyâ), Maqâm Istiyâ, ancient wall.
Deir Jarir	RA.	X. 178 152	Rock-cuttings and some ancient stones. Remains of Crusader church and castle, oil presses. Partly ancient building to south of village.
Deir Kharûf, Kh.	He.	XII. 137 102	Foundations, heaps of stones, caves.
Deir el Lauz, Kh.	He.	XII. 152 089	Foundations, heaps of stones, pool, press, cisterns cut in the rock.
Deir Mar Jiryis (Deir el Qilt)	Jm.	X. 189 139	Hermitage incorporated in modern monastery, rock-cut cells, frescoes, mosaic floors, architectural fragments, Cufic inscription.
Deir Mar Sâbâ	Jm.	X. 182 123	Monastery.
Deir el Mir	N.	VI. 154 163	Vaulted building, ruined walls, cisterns.
Deir el Muheisin	Re.	IX. 144 137	Foundations, cisterns.
Deir el Muheisin	He.	XII. 142 099	<i>see</i> Umm esh Shuqaf, Kh.
Deir Mukallik (Magharat Deir Mukallik)	Jm.	X. 187 132	Monastery, remains of tessellated pavement, rock-cut cistern, painted niches in the rock.
Deir el Mûs, Kh.	He.	XII. 137 098	Ruined walls, cisterns, tombs, caves.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Deir el Mûs, Kh.	He.	XII. 146 116	Ruined buildings, foundations, cisterns, rock-cut tombs, caves, remains of press.
Deir Nakh-knas	He.	XII. 143 114	A ruined pool, cave with niches, cistern.
Deir Nastâsiya	RA.	IX. 137 158	<i>see</i> 'Abûd.
Deir en Nizam	RA.	IX. 161 157	Rock-cut caverna. Tombs, columbarium.
Deir en Nu'man, Kh.	Re.	IX. 138 129	Ruined walls, foundations, caves ('Irâq en Nu'man), cisterns, fragments of column-shafts.
Deir Qal'a	N.	VI. 154 163	Ruined monastery, pools, caves. On north ancient path with retaining walls and rock-cut steps.
Deir Qâlûs, Kh.	RA.	IX. 156 143	Traces of old foundations, cisterns.
Deir el Qassîs, Kh.	N.	VI. 153 167	Quarries, rock-cut tomb.
Deir el Qilt	Jm.	X. 189 139	<i>see</i> Deir Mar Jiryis.
Deir Quruntul (Jebel Quruntul)	Jm.	X. 191 142	Architectural fragments.
Deir Râfât	He.	XII. 156 088	Foundations of a monastery, cistern, cave.
Deir Râzi, Kh.	He.	XII. 154 097	Walls, cisterns, caves, rock-cut tombs.
Deir er Ruhbân, Kh.	Re.	IX. 145 138	Foundations of buildings, cisterns, caves.
Deir Sa'd (Rasm 'Abd el Hamid)	He.	XII. 140 109	Foundations of buildings, heaps of stones.
Deir Sa'ida	He.	XII. 143 085	Foundations, heaps of drafted masonry.
Deir Sallâm, Kh.	Jm.	IX. 151 125	Traces of settlement, rock-cut wine press, cisterns.
Deir Sallâm, Kh.	Jm.	X. 173 139	Ruined walls, remains of vaulted building, caves with vaults.
Deir Sam'an, Kh.	N.	VI. 155 164	Ruins of monastery, with drafted masonry, rock-cut reservoirs, cisterns, rock-cuttings. Press with vat.
Deir Sâmit, Kh.	He.	XII. 148 103	Foundations, caves, cisterns.
Deir Sanna	Jm.	X. 174 130	Tombs, rock-cut cisterns, wine press.
Deir Sha'âr (Beit Sha'âr, Kh.)	He.	XII. 162 117	Remains of church with mosaic pavement, ruined buildings, caves, remains of an ancient road, rock-cut tombs, olive-presses.
Deir Shabâb el Qibliya, Kh.	RA.	X. 174 149	Small ruined building with barrel vaults and rough masonry.
Deir Shabâb esh Shamaliya	RA.	X. 174 149	Ruined buildings including church and tower. Vaults, cisterns. To north enclosure of rude blocks.
Deir esh Shams, Kh.	He.	XII. 152 091	Ruined walls, an ancient road, press cut in the rock, cisterns, caves.
Deir esh Sharif, Kh.	RA.	IX. 160 154	Ruined buildings of roughly dressed stones, rock-cut cistern and tomb.
Deir esh Shatir	He.	XII. 143 112	<i>see</i> esh Sheikh Barrâq, Kh.
Deir Shubeib	Re.	IX. 149 133	Ruined buildings, foundations, cisterns, caves.
Deir es Sida, Kh.	RA.	IX. 166 151	Building of well-dressed stones; ruined walls.
Deir es Sidd, Kh.	Jm.	X. 176 135	Foundations, heaps of rough stones, caves, cisterns, rock-cuttings.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Deir es Sûdân	RA.	X. 164 160	Traces of foundations, loose masonry.
Deir es Sûq (Deir ez Zaqq, Mishmish, Kh., es Sûq, Kh.)	Jm.	X. 175 127	Remains of square building with a vaulted cistern at north-west corner of polygonal enclosure wall.
Deir Surur	TK.	VI. 182 187	Ruins of town, walls of dressed stone, capitals, reservoirs, mosaic pavement, cisterns, tombs.
Deir Surur, Kh.	RA.	IX. 160 157	Foundations, heaps of stones, cisterns cut in the rock.
Deir et Tahûna	Jm.	IX. 148 131	<i>see et Tahûna, Kh.</i>
Deir Ta'arîf	Re.	IX. 144 155	Low mound with surface pottery, tombs, caves and cisterns cut in the rock, vaults, wine press, architectural fragments, sarcophagus.
Deir el 'Uqbân, Kh.	RA.	IX. 168 154	Ruined walls, foundations, column bases, watch-tower.
Deir Yasin	Jm.	IX. 167 123	Medieval walls and vaults in village. Tombs.
Deir Zanûta	He.	XII. 149 086	Remains of square tower within enclosure wall, cave, pool and cistern.
Deir ez Zaqq	Jm.	X. 175 127	<i>see Deir es Sûq.</i>
Deirabân, Kh.	TK.	VI. 159 188	Foundations, cisterns, traces of ruins.
ed Deirât, Kh.	He.	XIII. 165 095	Ruined buildings, subterranean magazines, caves, cistern.
Deiri, Kh.	Jm.	IX. 154 128	Foundations, cistern.
Deiriya, Kh.	RA.	IX. 156 145	Rough walls of flint. Foundations.
edh Dhahab, Tell	G.	XI. 102 107	Artificial mound, surface pottery, and marble fragments.
edh Dhahab, Kh. Tell	G.	XI. 114 102	Surface pottery.
edh Dhâhîriya	He.	XII. 147 091	Tower (el Husn), caves, tombs, presses, cisterns, quarry. Maqâms: Umm el Fadel and esh Sheikh Ahmad el Qimari. Chancel post, press stone.
Dhahr Abu Qutûf	G.	XI. 106 118	<i>see Abu Qutûf.</i>
Dhahr ed Dabdah	He.	XII. 159 107	<i>see ed Dabdah, Kh.</i>
Dhahr el 'Iraq	T.	III. 193 245	<i>see el 'Eika, Kh.</i>
Dhahr Makmish	Ja.	VI. 131 174	<i>see Makmish.</i>
Dhahr el Manâsîf (Manâsîf, Tell)	TK.	VI. 152 176	Scattered stones, rock-cut cisterns.
Dhahr el Mazra'a	A.	II. 160 267	Rock-cut tombs, quarries, foundations.
Dhahr Umm el Haiya	TK.	VI. 138 194	Rock-cut tombs and caves (Magharat Abu Samaha) in the ridge so called.
Dhahrat el 'Aqd	G.	VIII. 121 120	Rubble foundations, domed cistern, surface pottery over extensive area.
Dhahrat Hammâd, Kh.	J.	IV. 161 216	Scattered stones.
Dhahrat el Humeim (Eitayim, Kh.)	A.	II. 160 268	Foundations, traces of mosaic floors, surface pottery, pool, cisterns, tombs, presses.
Dhahrat Humsa	N.	VII. 197 178	<i>see Umm Hajar, Kh.</i>
Dhahrat el Jisr	Re.	VIII. 126 147	<i>see el Jisr.</i>
Dhahrat el Kharâb	Re.	VIII. 124 139	Hill with surface pottery, rubble and dressed stones.
Dhahrat Makmish	Ja.	VI. 131 174	<i>see Makmish.</i>

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Dhahrat Seiyāh	Re.	VIII. 125 140	<i>see</i> es Seiyāh, Kh.
Dhahrat et Tell	A.	II. 164 268	Extensive ruins with enclosing wall of rough blocks.
Dhahrat et Tūta (ez Zarnūq)	G.	VIII. 118 133	Artificial mound in sand, surface pottery, rubble foundations, heaps of stones.
Dhahrat Umm 'Amir	Ba.	XI. 090 095	Foundations of walls, surface pottery, marble and tile fragments.
Dhakar, Kh.	He.	IX. 138 121	Foundations, cisterns, caves.
Dhāna, Wadi	Ba.	XVI. 171 048	Dams, embankment and reservoir, Roman road, remains of buildings.
edh Dhib, Khurab	He.	XII. 150 111	Heaps of stones to south-west, cisterns and presses, ancient road.
edh Dhirā', Kh.	G.	VIII. 114 121	Surface pottery, rubble stones.
edh Dhiyāb, Kh.	N.	VII. 179 178	<i>see</i> Ibn Nāsir, Kh.
edh Dhiyāba, Tell	Bu.	V. 204 211	Group of artificial mounds, surface pottery.
edh Dhuheiriya, Kh.	Re.	IX. 144 150	Foundations, rock-cut cisterns, cave with rubble vault, surface pottery.
edh Dhuqqā'a, Maghārat	He.	XII. 158 104	Cave with arched entrance.
Dihna, Kh.	He.	XII. 144 108	Foundations, caves, cisterns.
ed Dilba, Kh.	He.	XII. 155 099	Ruined walls, foundations, drafted masonry, cistern, tomb, caves.
ed Dilba, Kh.	He.	XII. 164 113	Ruined walls, foundations, caves, aqueduct, mosaic floor, reservoir.
Dimdim, Kh.	He.	IX. 135 125	Small ruin, foundations, caves, rock-cut wine press.
Dimra	G.	XI. 109 107	Foundations, ancient cemetery (Sha'fat Abu Jāuha). To east caves, column-shafts and capitals.
Din'ila, Kh. (Nu'eila, Kh.)	A.	III. 173 274	Ruins of buildings. Foundations, presses, cisterns.
ed Disi, Kh.	RA.	X. 177 150	Ruined walls, foundations, rock-cut cisterns, cave.
ed Dubba, Kh.	Re.	VIII. 121 148	Foundations, cisterns, mound, mosaic pavements, surface pottery, marble, glass.
Dubeidiba, Kh.	RA.	X. 170 144	Walls, foundations, heaps of stones, tombs.
Dūbil, Kh.	H.	IV. 154 233	Foundations, cisterns, rock-cut tombs, mosaics, column fragments.
ed Dudabān, Kh. Tell	H.	IV. 147 213	Artificial mound, remains of oil-press, surface stones and pottery.
Dufeis, Kh.	H.	IV. 150 215	<i>see</i> Dafayis, Kh.
Dufna, Kh.	S.	I. 211 292	Foundations, traces of ruins, rock-cut presses. Two mounds.
ed Duhdah, Kh. (Ramat el 'Amla)	He.	XII. 159 107	Foundations, cisterns, rock-cut caves and tombs, column bases, capital.
ed Dubeisha, Kh.	Re.	VIII. 128 143	<i>see</i> el 'Ajjūri, Kh.
Duldub, Kh.	G.	XI. 116 114	<i>see</i> Daldūm, Kh.
Duma	N.	VII. 185 162	Remains of a church, columns, bases, mosaic pavement, rock-cut tombs, cisterns.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Duma, Kh. (ed Deir)	He.	XII. 148 093	Remains of ruined church with columns, ruined walls and foundations, tombs, cisterns, caves. Fruit press cut in the rock, rock-cut steps.
Dûra	He.	XII. 153 102	Remains of tower with drafted masonry, tessellated floor, architectural fragments, cistern.
Dûra el Qar'	RA.	X. 172 151	Underground rock-cut chamber, constructions of roughly squared stones.
ed Dureiba, Rujm	Jm.	IX. 164 128	Cairn.
Dureibât Abu Qutûf	G.	XI. 106 118	see Abu Qutûf.
Dureibât es Sawârîf (es Sawârîf, Kh.)	G.	VIII. 109 122	Vaulted tombs.
Dureibât esh Sheikh Hammûda (Sûq Mâzin, Kh.)	Ba.	XI. 088 086	Traces of extensive ruins. Rubble cisterns and square stones.
Dureihima, Kh.	H.	IV. 144 225	Foundations, sunk court with steps, column shafts, capital, rock-cut tombs with columbaria.
ed Dureihima, Kh.	RA.	IX. 163 142	A ruined tower, cisterns, two wells beside the Roman road.
ed Dureish, Kh.	RA.	IX. 155 144	Foundations, heaps of stones, caves, cisterns.
Durûr, Kh. Tell	TK.	IV. 147 203	Artificial mounds.
Durûsiya, Kh.	He.	XII. 144 118	Watch-tower (el Muntar), foundations, caves, ruined pool, cisterns.
Dustri, Kh.	H.	IV. 145 233	see 'Athlit.
ed Dusugiya	TK.	VI. 141 190	see Umm el Fulûs.
Duthân, Tell	J.	V. 173 202	Artificial mound, well, architectural fragments.
ed Duwâra, Kh.	Jm.	X. 178 141	Cave, ruined walls.
ed Duweiba, Kh.	H.	IV. 158 232	Ruin of small village, well-cut stones, tombs, cisterns, sarcophagus half cut from rock, press.
Duweima	N.	VII. 177 179	Roman villa (?), pillars, tessellated pavement, pottery.
ed Duweimin, Kh.	H.	IV. 152 238	see ed Dâmûn, Kh.
ed Duweir, Kh.	A.	III. 178 208	Row of sacophagi, foundations, cisterns cut in the rock.
ed Duweir, Kh.	T.	V. 209 232	Artificial mound, foundations and walls (basalt) of fort, surface pottery and flint flakes.
ed Duweir, Kh.	N.	VI. 151 160	Foundations of building with rock-cut cisterns and tower, lintel with cross, ancient road to Kh. Sarisiya.
ed Duweir, Kh.	RA.	VI. 157 162	Ruined church and monastery, rock-cut tank, press, rock-cut tunnel at spring.
ed Duweir, Kh.	N.	VI. 160 167	Remains of walls, caves and cisterns.
ed Duweir, Kh.	TK.	VI. 165 185	Ruins of building, rock-cut cisterns and caves.
ed Duweir, Kh. (Umm es Suweida, Kh.)	He.	XII. 136 108	Ruined walls in rough stone, foundations, enclosure, caverns, cisterns, press, heaps of stones.

Name of Site	Sub-District	Map Reference	Description
ed Duweir, Tell	He.	XII. 136 108	Artificial mound. Remains of fortress, city walls, buildings, gate, fosse, ancient road, tombs in valley and slopes.
ed Duyûk	Jm.	X. 191 143	Foundations of synagogue, tombs, caves, buried mosaics, dam.
ed Duyura, Kh.	Re.	VI. 153 161	Traces of ruins, foundations, scattered stones.
el 'Eika, Kh.	T.	III. 193 245	Heaps of stones, foundations of small square tower, small cistern.
(el Muntar, Dhahr el 'Iraq, el 'Eita, Kh.)			
'Eilabân	T.	III. 188 250	Rock-cut sarcophagus.
'Ein Abu Zureiq	H.	IV. 162 227	see Abu Zureiq, Tell.
'Ein el 'Af, Kh.	A.	III. 180 259	Foundations, heaps of stones, dry stone walls, mill stone, press.
'Ein el 'Aqd	Re.	IX. 151 139	Spring, remains of conduit.
'Ein el 'Asî	Bn.	V. 192 212	Tombs, basin.
'Ein el 'Atân	Jm.	IX. 166 121	Spring, aqueduct.
'Ein el Badiya	S.	III. 186 272	Rock-cut reservoir.
'Ein el Bahha	He.	XII. 157 105	Ruined mosque near spring.
'Ein el Ba'ida	T.	V. 193 239	Basalt trough, basin of squared masonry.
'Ein el Ba'ida	N.	VII. 180 185	On spur south-west of spring, ruin of rough stones.
'Ein el Baqî'	Jm.	IX. 162 124	Pool, to north rectangular building (el Habs).
'Ein Beit Ilma	N.	VII. 174 182	Vaulted building over spring.
'Ein el Bustân, Kh.	S.	III. 199 266	Foundations, heaps of stones.
'Ein ed Dhirwa (Qasr Islayin)	He.	XII. 160 110	Ancient quarry, rock-cut tombs and caves, foundations of dressed masonry, Roman milestone, rock-cut channel.
'Ein ed Dilba	He.	XII. 155 099	Ancient reservoir, aqueduct.
'Ein Dufna	N.	VII. 176 180	Remains of building enclosing spring, round tower and aqueduct.
'Ein Dûk	Jm.	X. 191 143	see ed Duyûk.
'Ein 'Eina Kh.	N.	VII. 179 165	Traces of settlement, piles of stones.
'Ein Fâra, Tell	Jm.	X. 179 128	Remains of aqueduct and bridge, cave dwellings, tombs; reservoir to north.
'Ein el Fawwâr	Jm.	X. 183 139	Pool, foundations of chapel with mosaics, aqueduct, cave dwellings.
'Ein Gev	T.	III. 210 241	Artificial mound, surface stones and pottery.
'Ein Ghabâti	S.	III. 186 269	Square basin cut in the rock.
'Ein el Ghawardai	A.	III. 179 273	Steps cut in the rock.
'Ein el Haiya, Kh.	Bn.	V. 199 226	Foundations of buildings.
'Ein el Halfa, Kh. (el Hafna, Kh.)	RA.	IX. 167 150	Walls and foundations of buildings, cisterns, oil press, door posts.
'Ein Hanniya	Jm.	IX. 165 128	Remains of basilica, niche over spring, aqueduct.
'Ein el Harâmiya	RA.	X. 174 156	Rock-tombs, cisterns, conduit, reservoir.
'Ein el Harâmiya, Kh.	N.	VII. 178 168	Remains of early settlement, heaps of stones.
'Ein Haud	Jm.	IX. 155 127	Spring, pools connected by tunnel.
'Ein Haur, Kh.	A.	II. 167 276	Heaps of stones.
'Ein 'Imran, Kh.	He.	XII. 155 100	Ancient springs, reservoirs, surface pottery.

Name of Site	Sub-District	Map Reference	Description
'Ein Isma'il	H.	IV. 150 216	Square shaft leading into a tunnel. Flight of steps.
'Ein el Jadida	Jm.	IX. 164 129	Vaulted chamber, chapel, wine press, mosaic floor, retaining wall, reservoir.
'Ein el Jama'in	Bn.	V. 192 212	see Humûd, Tell.
'Ein Jidi (Engeddi)	Jm.	XIII. 188 097	Ruined mill.
'Ein el Juhaiyir	Jm.	X. 197 131	Circular pool.
'Ein el Jusaq	Bn.	V. 192 212	Remains of dam and reservoir, column.
'Ein Kafr Fâr'ât	N.	VI. 169 185	see Kafr Fâr'ât, Kh.
'Ein el Kanisa, Kh.	Jm.	IX. 166 124	Ruined chapel, caves, foundations.
'Ein Kârim	Jm.	IX. 166 131	Rock-cut tombs, mosaic, foundations.
'Ein el Lauza, Kh.	RA.	IX. 167 148	see Abu Lauza, Kh.
'Ein el Maddû	Bn.	V. 193 210	Ruined masonry. To the north-east of it artificial mound. Aqueduct.
'Ein Mahûsh	Jm.	IX. 166 133	Fountain, remains of building.
'Ein el Mâliha	He.	VIII. 124 150	Surface pottery, prehistoric flints.
'Ein Mazârîb	S.	III. 182 268	Tombs.
'Ein el Muheima, Kh.	RA.	IX. 166 151	Heaps of stones, remains of buildings.
'Ein Musharriqa, Kh.	RA.	IX. 166 159	Building with drafted stones, press, cis- terns, architectural fragments, rock- cut tombs.
'Ein Naara	Bn.	V. 197 208	Roman tombs.
'Ein el Qabu	Jm.	IX. 161 126	Ruined building (el Kanisa).
'Ein el Qanâ	He.	XII. 159 106	Aqueduct, cisterns, baths, rock-cut presses. Old garden towers.
'Ein Qaryân	N.	VII. 175 181	see Nablus.
'Ein Qibiryân	Jm.	IX. 166 124	Ancient spring and pool.
'Ein Qinyâ	RA.	IX. 164 148	Ruins, tomb cave.
'Ein er Ridhgha	N.	V. 200 201	Masonry near spring.
'Ein es Sâbur, Tell	S.	I. 204 292	Rock-cut tombs (Roman cemetery).
'Ein es Sâkât	N.	VII. 202 197	see es Sâkât, Kh. Tell.
'Ein es Sâlih	S.	III. 198 260	Two sarcophagi, a cave, a wine press.
'Ein Sâlih	Jm.	IX. 166 122	Chamber, once vaulted. Flints, cistern below pavement.
'Ein Sâmiya	RA.	X. 182 155	Ruined settlement and caves.
'Ein Sâra	He.	XII. 159 106	Rock-cuttings.
'Ein Sârin	N.	VII. 177 179	Conduit and reservoir. Ruined build- ings, remains of vault (el Qasr), rock- cut tombs.
'Ein Shams	Jm.	IX. 148 129	see Bumeila, Kh.
'Ein Siniyâ	RA.	X. 172 153	Rock tombs, one with Hebrew inscrip- tion.
'Ein Tulma, Kh.	Jm.	IX. 166 134	Medieval vaults, ruined walls, cistern, conduit.
'Ein et Tût, Kh.	Jm.	IX. 166 133	Ruined vaulted buildings, cistern and trough.
'Ein Umm el Faraj	H.	II. 148 245	Rock-cut basin and chamber, masonry pool.
'Ein Umm Rukba	He.	XIII. 165 008	see Umm Rukba, Kh.
'Ein Umm esh Sharâiyit, Kh.	He.	IX. 170 144	Foundations, tombs, quarries.
'Ein el Wahsh	Jm.	IX. 159 127	Rock-cut tomb.

Name of Site	Sub-District	Map Reference	Description
'Ein el Weiba	Ba.	160 000	Surface pottery.
'Ein Wered	TK.	VI. 144 186	Surface pottery and rubble.
'Ein Yabrâd	RA.	X. 173 151	Rock-cut tomb.
'Ein Yâhu	Jm.	IX. 166 123	Ruins of monastery, marble columns, tombs.
'Ein Yarqa (Qasr 'Ein Yarqa)	Ba.	150 030	Ruined fort. Rock-cut stairs to spring.
'Ein Yûnis	Jm.	X. 200 141	Pool.
'Ein ez Zeitûn	S.	III. 196 265	Terraced ancient site.
'Ein ez Zu'qa, Kh.	Bn.	V. 199 223	Ruined masonry and scattered stones.
'Einûn, Kh.	N.	VII. 187 190	Ruined village with walls, vaults, Maqâm, cisterns. Tank with steps. Rock-cuttings, cup marks.
el 'Eita, Kh.	T.	III. 193 245	see el 'Eika, Kh.
el 'Eitawiya, Kh.	A.	II. 164 252	Ruined settlement, stone heaps, masonry well.
'Eitayim Kh.	A.	II. 160 263	see Dhahrat el Humeima.
'Eitûn, Tell	He.	XII. 143 100	Artificial mound with remains of walls, foundations, heaps of stones, rock-cuttings, well, rock-cut caves.
el 'Eizariya	Jm.	X. 175 131	Remains of tower and convent, tombs, mosaics, foundations.
Engeddi	Jm.	XIII. 188 097	see 'Ein Jidi.
Fâghûr, Kh.	Jm.	XI. 164 119	see Zakanda, Kh.
Fahas, Kh.	TK.	VI. 156 182	Watch-tower.
el Fahja, Rujm	He.	XII. 163 097	Tower, rock-cut cistern.
Fahma	J.	VI. 167 199	Barrel-vaulted building (el Baubariya); Crusaders' church used as mosque; rock-cut tombs.
Fajim, Tell	G.	XI. 058 083	Mound of pottery fragments.
Fajja	Ja.	VI. 141 166	Foundations, reused ancient stones, column-shafts and capitals, sarcophagus.
Fakhakhir, Kh.	N.	VI. 160 166	see Hamad, Kh.
Falama (Falamiya)	TK.	VI. 152 181	Rock-cut tombs.
el Fallâh, Kh. (Sha'b el Fallâh)	He.	XII. 143 114	Rock-cuttings, foundations.
Fallâh, Magharat Wadi (en Natif)	H.	IV. 148 236	Cave with prehistoric remains.
el Falûja	G.	XII. 126 115	Maqâm with inscription (esh Sheikh Ahmad Falûja).
el Fandaqumiya	J.	VI. 169 192	Cave, tombs, traces of old remains.
Fânis, Kh.	A.	III. 179 272	Foundations of walls, cut stones, cisterns, rock-cut tombs, olive-press and grinding stones.
Faqâs, Kh.	N.	VI. 167 176	see Ifqâs, Kh.
el Faqîra	G.	VIII. 118 137	Small mound with foundations, surface pottery.
Faqqû'a	J.	V. 188 211	Traces of ancient settlement, rock-cut tombs and cisterns.
el Far, Kh.	Ba.	XIV. 107 074	Traces of extensive ruins, foundations, wells, marble fragments, a capital, small column.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
el Far, Tell	H.	II. 160 242	Artificial mound, foundations.
el Far, Tell	Nt.	V. 177 226	Low mound with surface pottery, well.
el Far, Tulul	G.	XI. 107 101	<i>see</i> el Humr, Tulul.
el Far'a, Kh. Tell	N.	VII. 182 183	Artificial mound, foundations, caves, rock-cuttings, mosaic pavement.
el Far'a, Tell	Ba.	XIV. 100 077	Artificial mound partly excavated, ancient cemeteries, masonry embankment.
Farad, Kh.	He.	IX. 140 130	Rock-cut cisterns, foundations, caves, scattered stones.
Farah, Kh.	N.	VI. 152 172	<i>see</i> el Ashqar, Kh.
el Farahand, Tell	G.	VIII. 113 124	Small mound with surface pottery.
el Farâni, Tell	G.	VIII. 113 124	Artificial mound, tombs, rubble foundations.
Far'ata	N.	VI. 166 177	Cisterns, remains of sarcophagus.
Fârisiyya, Kh.	TK.	VI. 165 193	Foundations of buildings, doorposts and sills; traces of walls, remains of presses, cisterns.
Farkha, Kh. Tell	A.	II. 165 268	Heaps of stones, traces of foundations.
Farrâdiya	S.	III. 190 260	Square building (Maqâm esh Sheikh Mansur), building with arch and niche in cemetery, cave and tombs-cut in the rock.
Farrâj, Kh.	Jm.	IX. 169 137	Rock-cut tombs and cisterns, rock-cut and masonry pool to west.
(Kh el Biyâr)			
Farwa, Kh.	N.	VII. 180 195	Ruined walls, foundations, fragments of columns, dressed stones, caves, ancient road with causeway.
Farwâna, Tulul	Bn.	V. 196 208	Artificial mounds.
Fasâyil, Kh.	N.	X. 192 159	Extensive ruins, foundations, mills, remains of aqueduct, Roman road.
Fasil Danyâl, Kh.	A.	III. 178 272	Foundations and remains of walls, cisterns, sarcophagi, dressed stones and architectural fragments in village, mosaics.
Fass el Jamal, Tell	N.	VII. 201 192	Artificial mound.
Fassa, Kh.	RA.	IX. 162 158	Ruins of buildings, foundations, loose masonry.
Fassâsa, Kh.	He.	XII. 136 114	Foundations.
Fassûta	A.	III. 179 272	Foundations, architectural remains, decorated lintels in village, cisterns and tombs, rock-cut sarcophagus.
Fattâta, Kh.	Ba.	XII. 129 111	Traces of settlement, caves, cisterns, rock-cut chambers, ancient well.
Fattûh, Kh.	He.	XII. 160 095	Walls, foundations, caves, cisterns, rock-cuttings.
Fatûm, Kh.	He.	XII. 147 117	Foundations, cisterns with steps, caves.
Fâtûna, Kh.	Re.	VIII. 126 138	Rubble cisterns, scattered stones, surface pottery.
Fa'ûsh, Kh.	RA.	IX. 155 145	<i>see</i> Nijmat el Haudali, Kh.
Fawâqisa, Kh.	Jm.	IX. 168 129	Traces of extensive settlement, rock-cut press and caves, cisterns, surface pottery, quarries.

Name of Site	Sub-District	Map Reference	Description
el Fawwâr	He.	XII. 156 108	Old well.
el Fawwâra, Kh.	Ba.	XII. 129 101	Surface pottery, stones, scattered glass.
Fir'a, Kh.	He.	XII. 151 106	Spring vaulted over, ruined building, foundations, masonry well, rock-cut caves.
Firâsîn, Kh.	J.	IV. 160 204	Artificial mound, foundations, columns, bases, flagstone pavement; to north rock-cuttings, cisterns, caves.
Fir'im	S.	III. 200 265	Remains of buildings, tombs cut in the rock, caves, presses, rock-cuttings.
Firjâs, Kh.	He.	XII. 146 104	Foundations of buildings, caves, cisterns.
el Firr, Tell	Bn.	V. 188 216	Artificial mound, Roman milestones.
Fuheidî, Kh.	Ba.	XII. 134 110	see el 'Ajalân, Kh.
Fuk-ha, Kh. (Kufr Dukk, Kh.)	N.	VII. 184 193	Foundations, caves, cisterns.
Fukheikhira, Kh.	H.	II. 168 225	Foundations of walls, scattered stones.
el Fukheit, Kh.	He.	XIII. 166 087	Ruined walls, cisterns, caves.
el Fukhkhar, Kh. Tell	N.	VII. 185 181	Traces of ruins.
el Fukhkhar, Tell	A.	II. 159 258	Artificial mound, ancient tombs.
el Fukkhari	G.	XIV. 087 079	Small mound with surface pottery.
Fûkin, Wadi	Jm.	IX. 160 124	Foundations of buildings, remains of chapel, vaulted rooms, rock-cut caves and cisterns.
el Fûl, Kh.	Re.	IX. 146 135	Foundations of two settlements connected by ancient road, rock-cut press, vats, cupmarks and channel, cistern and tombs.
el Fûl, Tell	Re.	IX. 132 137	Artificial mound.
el Fûl, Tell	Jm.	X. 172 137	Artificial mound, ruins of town and citadel, partly excavated.
el Fula	Nt.	V. 179 223	see Merhavia.
Fuleih, Kh.	Nt.	III. 186 240	Foundations of walls, cisterns, tombs, caves, wine-presses, heaps of stones.
Fûliya, Kh.	He.	XII. 137 114	Foundations, surface stones, marble columns.
Funeitir, Kh.	H.	IV. 158 215	Scattered stones.
Fuqeiqi'a, Kh.	J.	V. 188 212	Ruined towers. Maqâm esh Sheikh Barqân.
Fuqeiqis, Kh.	He.	XII. 148 100	Caves, remains of a Roman road, milestones.
el Furdeis (Jebel Fureidis, Kh.)	Jm.	XIII. 173 110	Fortress on hill-top, towers, walls, vaults. Remains of stairway. Ruined buildings on slopes, cisterns, terraces.
el Fureidis	H.	IV. 146 223	Tombs, traces of ancient settlement, well.
Fureidis, Kh.	He.	XII. 162 115	Walls, foundations, vaulted cisterns, pool.
Fureir, Kh.	H.	IV. 160 226	Foundations, caves, tombs, heaps of stones.
el Fura, Kh.	Re.	VIII. 127 147	Foundations, remains of rubble reservoirs, mosaic and marble floor.

Name of Site	Sub-District	Map Reference	Description
Furt, Kh.	G. Ba.	XII. 132 111	Cisterns, tessellated pavement, fallen masonry, ancient road, olive-press, well, ruined pool.
Fuseisiyât, Kh.	Bn.	V. 189 215	Ruined walls, foundations.
Futeis Kh.	Ba.	XI. 115 082	Extensive ruins, rubble cisterns.
Gan Hefer	TK.	VI. 141 194	Foundations, tessellated floor, surface pottery.
Gaza	G.	XI. 099 101	Artificial mound, remains of brick walls, ancient and medieval buildings and foundations in town, tombs.
Gerizim, Mt.	N.	VII. 176 179	see Jebel et Tur.
Geva'	Bn.	V. 187 219	see Qumiya, Kh.
Ghabbâtiya, Kh.	S.	III. 185 269	Foundations of walls, olive-press, pool, cisterns, caves, rock-cut tombs.
el Ghâbisiya	A.	II. 164 267	Rock-cuttings, sarcophagi.
Ghalghala	Jm.	X. 196 140	see en Nitla, Tulûl.
el Ghalta, Tell	H.	IV. 167 232	Artificial mound, traces of foundations.
el Ghanam	J.	V. 177 204	see Umm en Naml, Kh.
el Ghanâyim, Kh.	He.	XII. 163 095	see Umm el 'Amad, Kh.
Gharashliya, Kh.	A.	III. 181 271	Foundations, heaps of stones, surface pottery.
el Gharbâwi, Kh.	Re.	IX. 150 149	Cisterns, rock-cuttings and scattered stones round Sheikh el Gharbâwi.
el Gharbi, Tell	A.	II. 166 256	see Bir el Gharbi, Tell.
el Gharra, Kh.	Ba.	XV. 149 071	Remains of town, flint walls, glacis, foundations of buildings, caves, cisterns, pilaster cap, surface pottery, block-house to N N E.
Ghayâda	He.	XII. 138 112	Foundations of square building, enclosure wall.
Ghayâda, Kh.	G.	VIII. 119 127	Rubble foundations, cisterns, well, surface pottery.
Ghayâda, Kh. (en Nabi 'Arafât)	Re.	VIII. 127 138	Rubble foundations, cisterns, surface pottery.
Ghayâda, Kh.	G.	XI. 117 109	Traces of foundations, cisterns, potsherds.
Ghazâla, Kh.	S.	III. 205 261	Foundations, rough basalt enclosures, dolmens.
Ghazza, Tell	Re.	VIII. 140 150	Artificial mound, surface pottery, flints.
el Ghirur, Kh.	N.	VII. 201 180	Remains of rectangular enclosure and tower; tombs, cisterns, foundations. Roman road.
Ghor el Far'a	N.	VII. 196 171	see el Mazâr, Tell.
el Ghubaiya, Kh.	He.	XI. 136 111	Traces of ruins, caves.
el Ghunaiyima, Tell	N.	VI. 166 187	Artificial mound, partly excavated; flints, tombs.
Ghurâba, Kh.	RA.	VII. 173 161	Remains of buildings, foundations, rock-tombs.
Ghurâba, Kh.	He.	XII. 152 119	Foundations, heaps of fallen masonry, rock-cut caves and cisterns.
el Ghureib, Kh.	A.	II. 165 274	Foundations of cut-stones, olive-presses, cave, cisterns, lintels, broken columns.

Name of Site	Sub-District	Map Reference	Description
Ghuweina el Fauqa, Kh.	He.	XII. 158 085	Caves, cisterns, foundations.
Ghuweina et Tahta, Kh.	He.	XII. 156 084	Ruined walls, caves, arch.
Ginneigar	Nt.	V. 174 230	Caves, rock-cuttings, vaulted well, rock-cut tomb.
Giv'at Miller	Ja.	VI. 135 166	Pool with tessellated pavement, surface pottery, stones.
Giv'at Nu'ah (Ji'ara, Bannir)	H.	IV. 161 223	Tombs, layers of debris, wall, foundations, stones.
Giv'at ha-Po'alim	H.	IV. 144 214	Artificial mound, foundations, surface pottery, tomb.
Habaj ea Zir	N.	X. 193 159	Ruined aqueduct, tanks, foundations of buildings.
el Habay, Kh.	A.	II. 169 265	Heaps of stones, foundations, rock-cuttings.
el Habik, Kh. (el Hammâm, Kh.)	He.	IX. 154 121	Ruined walls, heaps of stones, rock-cut cisterns, remains of rock-cut mill.
el Habis	Re.	IX. 147 149	see el Haba.
el Habis	Re.	IX. 152 145	see el Burj.
el Habis	Jm.	IX. 162 131	Cave.
Habla	TK.	VI. 148 175	Ruined walls, tombs, cisterns, caves, quarries.
Hablata, Kh.	RA.	IX. 162 157	Ruined buildings of rough masonry. Rock-cut shaft-tombs, rock-cut press and tanks with mosaic floors.
Habra, Kh.	Re.	VIII. 128 139	Artificial mound, rubble foundations, well.
el Habs (el Habis)	Re.	IX. 147 149	Rock chamber, tombs, pool, rock-cuttings.
el Habs	He.	XII. 138 101	Cavern with several domed chambers.
el Habs	He.	XII. 159 103	Foundations.
el Habur, Kh. (esh Sheikh 'Abdallah)	Ba.	XII. 132 107	Buried walls, cisterns, surface pottery, caves.
el Hadab, Kh.	He.	XII. 150 096	Rock-cut cisterns, rock-cut tomb, caves.
el Hadaba, Kh.	Jm.	X. 175 131	Rock-cut and built pool. Foundations, cisterns, traces of press.
Hadatha	T.	V. 196 232	Vaulted building over spring, remains of press, ancient material in village.
el Hadatha, Kh.	Re.	IX. 151 143	Foundations of houses, heaps of building stones, cisterns, column fragments, rock-cut caves, tombs.
el Haddad, Kh.	Bn.	V. 192 223	Foundations, heaps of stones.
el Haddar	Ja.	VI. 134 168	Mills, dams, embankment walls.
el Hadid, Rujm	Ba.	150 900	Ruins of block-house.
el Haditha	Re.	IX. 146 152	Artificial mound, partly beneath village; foundations, column fragments, remains of mosaic, cistern, pool, tombs, caves.
el Hadra, Kh.	Ja.	VI. 134 169	Ancient cemetery, surface pottery.
el Hafi, Kh.	FA.	IX. 163 145	Heap of stones, surface pottery and glass.
el Hafna, Kh.	RA.	IX. 167 150	see 'Ein el Halfa.
el Hai, Kh.	Jm.	X. 177 142	Foundations, caves, cisterns.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Haifa	H.	II. 152 243/5	Tombs along Nazareth Road; prehistoric remains (Neve Sha'anana).
Haifa el 'Atiqa	H.	II. 149 245	Tombs, rock-cuttings.
Haiya, Kh.	N.	VII. 179 175	Traces of ruins.
Haiyân, Kh.	RA.	X. 176 146	Reservoirs, cisterns; north of site a stony tell.
Hajala, Kh.	H.	IV. 150 232	Foundations, dressed stones, rock-cuttings; rock-cut cisterns.
el Hajar, Kh.	G.	XI. 109 113	<i>see</i> er Rasm, Kh.
Hajar ed Dann	S.	III. 204 261	Dolmen.
Hajar 'Id	G.	VIII. 109 121	Tombs, well, reservoir, marble fragments, surface pottery.
Hajar Muneiqâ'	S.	III. 191 267	Dolmen.
el Haii 'Awwad, Kh.	Ba.	XI. 118 087	Scattered stones.
el Hajj Harb, Kh.	Ba.	XI. 120 101	Oil press, rubble masonry and vaulted construction, fragments of mosaic pavement, surface rubble and pottery, rubble cisterns.
el Hajj 'Isa, Kh.	He.	XII. 137 111	Foundations, heaps of stones.
el Hajj Mahmud, Kh.	Bn.	V. 203 207	Artificial mound, building materials, column shaft; to south-west shrine of esh Sheikh Muhammad.
el Hajj Rahhal, Kh.	J.	VII. 174 199	<i>see</i> en Nazla, Kh.
el Hajjaj Kh.	Ba.	XI. 094 089	Surface potsherds, rubble cisterns, tombs.
el Hakamiya, Kh.	Bn.	V. 201 215	<i>see</i> el Bawâti, Kh.
el Hâkûra (Hâkûrat 'Abd el Hamid)	G.	XI. 100 095	Potsherds, traces of ruins.
Hâkûra, Kh.	He.	XII. 157 105	Foundations, cisterns, rock-cuttings, caves.
Halhûl	He.	XII. 160 100	Ruins of a building with tessellated floor ('Aqd el Qîn), rock-cut tombs.
Hallâba, Kh.	RA.	IX. 158 145	Ruined walls, olive press, rock-cuttings.
Hamad Kh. (Dar el Hamad, Kh.)	N.	VI. 160 168	Ruined buildings, remains of square building with columns, cisterns, sarcophagus cut in the rock.
el Hamâm, Kh.	Re.	IX. 148 144	Rough stone walls and foundations, rock-cut cisterns.
el Hamâm, Kh. (Rasm el Hamâm, Kh.)	He.	XII. 146 106	Foundations of large buildings, ruined walls, rock-cut storage pits.
el Hamâm, Kh. Wadi	T.	III. 196 248	<i>see</i> el Wureidât, Kh.
Hamâma	G.	VIII. 111 122	Tomb with marble door-slab.
Hamda, Kh. (Ras Umm esh Shabâiyih)	He.	XII. 141 111	Ruined buildings, cisterns.
Hamdallah, Kh.	RA.	IX. 154 146	Extensive ruins, walls, cisterns, foundations.
Hamdân, Kh.	Jm.	IX. 161 125	Foundations, presses, column fragments, rock-cut tombs to west, ancient road.
Hâmid, Kh.	Re.	IX. 151 152	Ruined buildings, heaps of stones, rock-cut press.
Hamida, Kh.	Re.	IX. 149 137	Artificial mound, surface pottery.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
el Hamir, Kh.	Re.	IX. 146 135	Rock-cut cave dwelling, remains of tower.
el Hamir, Tell	Bn.	V. 203 210	Artificial mound, surface pottery, Roman milestones on way to Tell esh Sheikh Dawūd.
el Hamma	T.	V. 213 232	Ancient site, partly artificial mound, ruins of theatre, ruins of baths and of synagogue with mosaic pavement, buildings, tombs, column shafts, bases, capitals, aqueducts.
el Harama, Tell	N.	VII. 197 198	Artificial mound, traces of walls, rock-cut tombs.
Hammād, Kh.	N.	VI. 156 171	Ruined village, walls, cistern, cave watch-tower.
Hammād, Kh.	TK.	VI. 155 188	Ruined village.
(Ibn el Hajj Hammād, Kh.)			
Hammāda, Kh.	Jm.	IX. 152 131	Ruined walls and fallen masonry, to south-west barrel-vault; rock-cut caves and cisterns.
el Hammām, Kh.	Re.	IX. 146 149	Caves, cisterns cut in the rock, surface pottery.
el Hammām, Kh.	Re.	IX. 150 149	Foundations, press, cistern cut in the rock, quarries, tombs.
el Hammām, Kh.	He.	IX. 154 121	see el Habik, Kh.
el Hammām, Kh.	G.	XI. 119 104	Ruined rubble building, surface rubble.
(Umm-er Rujām, Kh.)			
el Hammām, Kh.	He.	XII. 147 115	Foundations of buildings and church, heaps of stones, caves with columbarium, cisterns.
Hammām Banāt	S.	III. 208 270	Pool enclosing spring.
Ya'qūb			
Hammām el Mālih	N.	VII. 195 193	Traces of buildings, aqueduct, channel.
el Hammūd Tell	Bn.	V. 202 214	Mound.
el Hamqa, Kh.	N.	VI. 155 163	Foundations, two cisterns.
el Hamra, Kh.	S.	III. 198 262	Foundations of walls.
(el Hamrāwi)			
el Hanbaliya, Kh.	A.	II. 168 266	Traces of foundations, heaps of ruins, well-dressed stones. Wine-presses, cistern.
Handhal, Kh.	Jm.	IX. 155 126	Foundations.
el Handhal, Rujām	He.	XII. 144 102	Foundations, piles of stones, ruined watch-tower, rock-cut press.
Handūs, Kh.	N.	VII. 186 193	Heaps of stones, caves, cisterns, rock-cuttings.
Haniya, Magharat	S.	III. 194 276	Cave with recesses and cisterns.
Hanna, Kh.	Jm.	IX. 157 125	Traces of buildings.
Hannāna, Kh.	H.	IV. 150 223	Walls, caves.
Hannānat el Qassis	T.	III. 201 245	Remains of tower, plastered tank.
Hannūna	TK.	VI. 140 192	see Beit Līd, Kh.
Hannūna, Kh.	Re.	IX. 153 155	Traces of foundations, rock-cut caves, cisterns, presses.
el Hannūna, Kh.	G.	XI. 107 104	Artificial mound, rubble vaulted chamber, building remains, architectural fragments, presses, cisterns.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Hânûta, Kh.	A.	II. 166 277	Upright stones, ornamented lintel, cisterns and tombs cut in the rock, mosaic floor.
Hânûta, Kh.	TK.	VI. 149 181	Accumulations with surface pottery and rubble. Rock-cut cisterns. To north rock-cut tombs and cisterns.
Harâbat el Beida	Ba.	XV. 163 059	Rectangular rock-cut and masonry cistern, runnel, stones. To north well with trough (Bir el Beida). Enclosure of rough stones.
Harâbat Ibn Sabâh	Ba.	XVI. 168 061	Rectangular cistern with rock-cut runnel. scattered blocks.
Harâbat Umm 'Ataba	Ba.	XV. 162 052	Rock-cut cistern, approach and steps; remains of two buildings.
Harâbat Umm Ghabit	Ba.	XVI. 154 048	Rock-cut cistern, runnel, dam.
Harâbat Umm Hamâta	Ba.	130 020	Rock-cut cistern with square pillar supporting roof.
Harâbat Umm Rukeiba	Ba.	XVI. 166 064	Three rock-cut cisterns, rock-cut steps, rough dam.
Haradhan, Kh.	Jm.	X. 176 127	Ruined walls.
Haraib el Bid	Jm.	XIII. 174 116	see Qa' Hujjar.
el Harâmis, Kh.	H.	IV. 156 227	Ruins of ancient village.
el Harasha, Tell	G.	XI. 085 091	see et Tabaqa.
el Harâyi, Kh.	He.	XII. 158 101	Ruined buildings, foundations, plastered vault, caves, cisterns, rock-cut pool, column shafts, bases, capitals.
el Harbaj, Kh.	H.	II. 159 241	Artificial mound partly excavated. Remains of fortifications, rock-cut tombs.
Harbiya, Kh.	G.	XI. 110 109	Traces of rubble buildings, cisterns, surface pottery, limestone font.
Harfûsh, Kh.	RA.	IX. 159 143	Remains of building, rock-cut cave, cistern, watch-tower between site and Beit 'Ur.
Hâris	N.	VI. 164 169	Watch-towers, tombs, cisterns, foundations.
Harmûsh, Kh.	Re.	IX. 148 151	Foundations, tombs, cisterns, pressing floors cut in the rock.
el Harrawi, Kh. (el Harra, Kh.)	S.	III. 203 277	Remains of walls, foundations, caves, rock-cut tombs, moulded stones, cisterns, Greek inscriptions, wine-press, tessellated floor.
Harsûs, Kh.	Jm.	IX. 152 136	Traces of watch-tower, caves, cisterns.
Hârûna, Kh.	A.	III. 177 275	Foundations of square building, heaps of stones.
Hasan, Kh.	Jm.	IX. 146 132	Ruined buildings, remains of tower, foundations, rock-cut cisterns, presses, treading floor, mill stone, tomb, ancient road.
el Hasi, Tell	Ba.	XII. 124 106	Artificial mound, partly excavated. Remains of dam in valley to east.
Hatta, Kh.	He.	XII. 152 114	Cisterns, caves, wine-press, well, ruins.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Haud er Rumiya, Kh.	He.	XII. 136 106	Traces of ruins, caves.
Haura, Kh.	Ba.	XV. 144 077	Ruins of town, with piles of fallen masonry and foundations. Five outlying forts, cisterns.
Haura, Wadi	He.	XII. 163 100	Rock-cut caves and tombs.
Hauran, Kh.	He.	XII. 142 099	Foundations, caves, rock-cut cisterns, presses.
Hauran, Kh.	He.	XII. 145 117	Ruined walls, heaps of stones, caves, cisterns.
el Haush, Kh.	N.	VI. 168 172	Ruined fort, rock-cut cisterns, traces of fosse.
el Haush, Kh.	Jm.	IX. 164 136	Foundations.
el Hawa, Kh.	N.	VII. 178 184	Traces of ruins.
el Hawa, Tell	G.	XI. 098 103	see Abu el Hawa, Tell
el Hawādī, Kh.	G.	XI. 101 097	Ruined cisterns, heaps of pottery, marble fragments.
Hawakir Bana	N.	VII. 174 180	Mound, foundations, pillar shafts, reservoir.
Hazzāna, Kh.	He.	XII. 141 103	Foundations of tower, door-posts, cisterns, caves, hewn stones.
Hazzāra, Kh.	Ba.	XII. 124 107	see Abu Zurei'i, Kh.
Hazzūr, Kh.	Jm.	IX. 168 138	Foundations, ruined tanks, cisterns, tombs.
Hebron	He.	XII. 160 104	Ancient site.
Hedera	H.	IV. 143 203	Artificial mound, rock-cut cistern south of esh Sheikh Hilu.
Hefsi-Bah	H.	IV. 141 208	Tombs. Abutments of destroyed bridge.
Heidara, Kh.	H.	IV. 144 225	Remains of buildings, tombs, quarries. To the east traces of rectangular building, mosaic fragments.
el Heik, Rujm	Re.	IX. 148 138	Dolmen with stone niche and cupmarks.
Herzliah III.	Ja.	VI. 135 175	Quarries, mosaic pavement, rock-cut tombs, reservoir, rock-cut tunnel, oil press, caves.
Hiba, Kh.	Re.	IX. 150 139	Foundations, cisterns.
Hibra, Kh.	He.	XII. 140 107	Foundations, heaps of stones.
el Hih, Kh.	He.	XII. 148 117	Building foundations and heaps of stones.
Hijārāt ed Duweiri	BA.	VII. 175 160	Remains of building with drafted masonry. Other ruined building in vicinity, cisterns.
Hilāl, Kh. (Khallat el Beida, Kh.)	Jm.	XIII. 168 119	Ruined walls, cisterns, cupmarks.
el Hilu, Kh. Tell (Karm el Hilu)	N.	VII. 198 192	Artificial mound, masonry foundations of tower, outer wall.
Hindāzi	Jm.	IX. 170 122	Caverns, tombs, rock-cuttings.
el Hira, Kh.	RA.	VI. 160 160	Rock-cut cisterns, tombs, surface pottery.
Hirbiya (esh Sh. Sa'id)	G.	XL 107 113	Foundations of tower (el Burj) at esh Sheikh Sa'id. Circular well. Architectural fragments and traces of pavement in village. To south-west foundations of rubble reservoirs.

Name of Site	Sub-District	Map Reference	Description
Hirsha, Kh.	Jm.	IX. 155 137	Walls of buildings, cisterns, fragments of mosaic floors, tombs, to south and east rock-cuttings.
el Hish-sha, Kh.	He.	XII. 139 113	Tomb, cave, rock-cut cisterns, loose masonry.
Hittin	T.	III. 193 246	Ancient foundations beneath village, rock-cut tombs, architectural remains.
Hizma	Jm.	X. 175 138	Traces of old buildings, granite columns and column fragments, foundations of walls, tombs, caves.
Huailân, Kh.	Jm.	X. 178 131	<i>see</i> Abu Huweilân, Kh.
el Hubeila, Kh.	He.	XII. 160 119	Ruined walls. Foundations, to west chapel paved with mosaics, two bases; north of chapel two bases and capital. Well at north-east corner, two broken columns. Square stones, rock-cut caves, reservoir.
el Hudeiba, Kh.	He.	XV. 165 078	Traces of ruins.
Hudeidûn, Kh	H.	IV. 145 212	Partly artificial mound, column shafts, capital, scattered masonry.
el Hudeithiya, Kh.	H.	IV. 145 220	Foundations, rock-cut tombs, wine-press (rock-cut), surface pottery.
Hôj, Kh. (en Nabi Hôj)	G.	XI. 115 102	Traces of settlement on rising ground, cisterns, surface pottery, marble fragments, rubbish mounds.
Humeidiya, Kh.	Jm.	XII. 164 119	<i>see</i> Ahmadliya, Kh.
el Humeira, Kh.	H.	II. 167 241	Ruined walls, cisterns, caves.
el Hummus, Rujm	He.	XII. 143 090	Ruined walls, cisterns, rock-cut wine-press.
el Humr, Tulûl (el Fâr, Tulûl)	G.	XI. 107 101	Three artificial mounds, rubble cisterns, surface pottery.
Humraiya	Re.	VIII. 126 149	Artificial mound, fragments of pottery, tombs.
Humsa, Kh.	N.	VII. 195 181	Foundations, ruined tank.
Humsîn, Kh.	A.	II. 164 272	Ruined remains of masonry column and pedestal, rock-cuttings, foundations, broken olive-presses. Rock-cut tombs to west.
Humûd, Tell (‘Ein el Jama’in)	Bn.	V. 192 212	Artificial mound, granite columns and column fragments, foundations of walls, caves, surface pottery, rock-cut water channel at ‘Ein el Jama’in with earthenware piping, quarries.
Hunin	S.	I. 201 292	<i>see</i> Oal’at Hunin.
el Hunûd, Tell (Mureibid, Tell)	T.	III. 200 252	Artificial mound covering ruin, ancient road to east, rough basalt stones.
Hurab Dhiyâb, Kh.	Ba.	XI. 112 094	Cisterns, traces of foundations, surface pottery.
Hurfeish	S.	III. 183 269	Foundations, cisterns, tombs, cut stones, shafts of columns.
Hûriya, Kh.	RA.	IX. 154 146	Foundations of buildings, remains of tower, pool with rock-cut steps, press, cistern.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
el Huseimiya, Kh.	He.	XII. 138 115	Foundations, two caves, cisterns cut in the rock.
el Husein (Mas-had Sidna el Husein)	G.	XI. 108 119	Ruined tower, two vaulted tombs.
Husein, Kh. (Masqûfa, Kh.)	TK.	VI. 156 193	Foundations and fallen masonry. Door posts, mill stones. Rock-cut cisterns. Threshold of gate at el Bawwâba.
el Huseinât, Kh. (Umm Râziq, Kh.)	He.	XII. 142 115	Heaps of stones, caves, cisterns.
Husha	H.	II. 164 244	Foundations of buildings and architectural remains in village, Maqâm of en Nabi Hushan. Circular well, plastered tank, rock-cut tombs in vicinity, mosaic floor.
el Husn	N.	VII. 163 170	see 'Aqraba.
el Husn, Tell	Bn.	V. 197 212	Artificial mound partly excavated. Gate, ruined buildings, foundations.
el Huwâra	H.	IV. 167 237	Ruins of large building with rude pillars.
Huzn Ya'qûb (Jami' el Khadra)	N.	VII. 174 181	Crusaders' building converted into mosque, minaret, Samaritan inscription, tank.
Ib'anna, Kh.	Re.	IX. 149 155	see B'inna, Kh.
'Ibdia	G.	VIII. 122 121	Rubble foundations and reservoirs, well, architectural fragments in village.
'Ibillin	H.	II. 108 247	Remains of castle with round towers and walls, rock-cut tombs, foundations, inscribed lintel, ornamented stones, rock-cut cisterns and stone heaps to north.
el Iblakhfiya	G.	XI. 098 106	Traces of ruined walls, surface pottery.
Ibn 'Awwâd, Kh.	RA.	IX. 156 145	see er Rujm, Kh.
Ibn Basma, Rujm	He.	XII. 161 084	see 'Arqûb Ibn Basma.
Ibn Haj Hammâd, Kh.	TK.	VI. 155 188	see Hammâd, Kh.
Ibn Nâsir, Kh. (edh Dhiyâb, Kh.)	N.	VII. 179 178	Foundations and heaps of stones within dry masonry enclosure, old quarry.
Ibn Zeid, Khurâb	He.	XII. 144 119	Ruined buildings in groups, caves, cisterns (rock-cut). To north ancient road.
Ibni Bârik, Kh.	RA.	X. 173 146	Foundations, rock-cut cisterns, ancient road to west.
Ibreika, Kh.	TK.	VI. 147 179	Mound, foundations of buildings, ruined cistern. Domed Maqâm.
Ibreiktas, Kh.	H.	IV. 140 204	Foundations, cisterns, rock-cut tombs, columbarium, traces of mosaic, quarries.
Ibziq, Kh.	N.	VII. 188 198	Traces of ruins, cisterns, caves.
'Id, Kh.	Jm.	IX. 167 140	Heaps of stones, rock-cut tombs, cisterns.
'Id el Minya, Kh. (Id el Miya)	He.	XII. 150 118	Ruined walls and vaults, columns, rock-cut caves, cisterns.
el 'Iddeisiya, Kh.	Re.	IX. 148 157	Heaps of stones, rock-cut caves, cisterns.
Idma, Kh.	Bn.	V. 201 227	Foundations, tombs, sarcophagus, scattered stones, architectural fragments.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Idmîta, Kh. (esh Sheikh el Mughâzi)	Ba.	XI. 091 092	Rubble cisterns, foundations and surface pottery on rising ground, fragments of marble shafts at esh Sheikh el Mughâzi.
Idmîth, Kh.	A.	II. 169 276	Foundations, cisterns cut in the rock.
Iqâs, Kh.	N.	VI. 167 176	Remains of building with substructures, rock-cuttings, carved lintel.
'Ifrein, Tell	TK.	IV. 149 205	Surface pottery on rising ground, rubble, tesserae.
el Ifshâr, Tell (el Afshâr, Tell)	TK.	VI. 141 198	Artificial mound.
el Ihlâl, Kh.	Jm.	XII. 160 118	Traces of foundations, cave, cistern cut in the rock.
Ihmeidân, Tell	Ja.	VI. 135 161	Surface pottery on rising ground, tombs.
Ijdûr, Kh.	He.	XII. 159 116	Ruined walls, niche and column, caves, cisterns, remains of an ancient road.
'Ijjis er Ras, Kh.	G.	XI. 118 118	Rubble, foundations, surface pottery, cisterns.
el 'Ijlîya, Kh.	A.	III. 178 278	Foundations, heaps of stones, cisterns and tombs cut in the rock, olive-press, base of column, stone sarcophagus with lid.
Ijzim	H.	IV. 149 229	Artificial mound beneath modern village.
el Ikhrein, Kh.	J.	IV. 160 203	Heaps of stones.
Ikhza', Kh.	G.	XIV. 090 080	Rubble foundations, cisterns, surface pottery.
Iklîl, Kh.	A.	II. 168 265	<i>see</i> Bir Iklîl, Kh.
Iksâl	Nt.	V. 181 232	Foundations, stone pavement, rock-sunk tombs, cemetery, cisterns.
Il'asa, Kh.	RA.	IX. 160 144	<i>see</i> el l'sa, Kh.
'Illîn, Kh.	He.	XII. 153 119	Walls, foundations, caves, cisterns.
'Ilma, Kh.	He.	XII. 140 115	Rock-cut cave with stairs and columbaria.
'Ilût	Nt.	V. 175 236	Rock-cut tombs, sarcophagi, traces of early settlement beneath village.
'Imwâs	Re.	IX. 149 138	Ruined basilica, baptistery, chapels, mosaics, tombs, traces of apsidal building in Maqâm esh Sheikh 'Ubeid, built and rock-cut conduit, remains of hypocaust, ancient masonry and architectural fragments reused in village.
Indur	Nt.	V. 186 227	Caves, silos, cisterns cut in the rock, tombs, ruins of houses.
Inseirât, Kh.	Ba.	XI. 094 091	<i>see</i> en Nuseirât.
Insîl, Kh.	He.	XII. 162 101	Foundations, large cistern.
Iqbala, Kh. (Deir el Banât)	Jm.	IX. 162 134	Ruined convent.
Iqrit	A.	III. 176 276	Village on artificial mound with ancient material, cisterns, mosaic pavements, wine press, rock-cut tombs, surface flints.
Iqteif, Magharat	Jm.	X. 192 134	Shaft with steps.

Name of Site	Sub-District	Map Reference	Description
'Irâq Abu Husein, Kh.	Ba.	XII. 130 105	Rock-hewn caverns.
'Irâq Abu Sirdâh	He.	XII. 141 112	Rock-hewn cavern, columbarium.
'Irâq Badr	N.	VII. 175 180	Rock-cut chambers, cistern and quarries in cliff.
'Irâq el Beida	Re.	IX. 138 139	Rock-hewn caverns.
'Irâq ed Deir	He.	IX. 139 120	Rock-hewn caverns, inscriptions, columbaria.
'Irâq el Fanash	He.	XII. 140 114	Caverns, rock-cut wine presses, cup-marks.
'Irâq el Kheil	He.	XII. 140 112	Cavern.
'Irâq el Manshiya	G.	XII. 130 113	see esh Sh. Ahmad el 'Areini, Tell.
'Irâq en Nu'man	Re.	IX. 138 129	see Deir en Nu'man, Kh.
'Irâq esh Shârat, Kh.	He.	XII. 142 113	Foundations, mosaic floor, caverns, rock-cut tombs and cisterns.
'Irâq Suleiman	He.	XII. 140 113	Cave cut in rock, halls, passage, chamber with cistern and manger, traces of graffiti and inscriptions.
'Irâq Suweidân	G.	XII. 121 117	Surface pottery and stones west of village, tombs, reservoir, group of caves, cut in the rock; mosaic pavement beside Majdal—el Falûja road.
'Irbada, Kh.	T.	V. 189 237	Rough basalt walls.
Irbid, Kh.	T.	III. 196 247	Extensive ruins, remains of synagogue, well, rock-cut tombs, wine-presses. Quarries, aqueduct.
Irdeiha, Kh.	Ba.	XV. 152 051	see Rudeiha, Kh.
Irba, Kh.	Jm.	X. 172 139	Foundations, cisterns, heaps of stones.
'Iribbin, Kh.	A.	III. 172 276	Ruins of ancient settlement, building stones, foundations, columns, cisterns.
'Irma, Kh.	Jm.	IX. 154 129	see er Ras, Kh.
Irmeilta, Kh.	G.	VIII. 126 122	see Rumeilta, Kh.
'Irq, Kh.	Ba.	XI. 106 086	Extensive ruin, heaps of stones, ruined cisterns, olive-presses.
'Irq el Ahmar	Jm.	XIII. 173 118	Cave, partly excavated, with prehistoric remains.
Irtah, Kh.	TK.	VI. 152 189	Maqâm en Nabi Ya'qûb with vault below, foundations, column fragments, capital, base. Press, cisterns, tanks, tombs. Masonry pool, rock-cuttings.
Irza, Kh.	G.	XI. 114 116	Rubble foundations, cisterns, well, pool, surface pottery and marble fragments.
Irziya, Kh.	Jm.	X. 171 141	Traces of walls and foundations, heaps of stones, press stone, column fragments.
el I'sa, Kh.	RA.	IX. 160 141	Ruined walls, foundations, scattered stones, rock-cut cisterns, fragments of columns, cave.
'Isawiya	Jm.	X. 174 134	Rock-cut cisterns, tombs and caves (with ossuaries), rectangular reservoir.
Isbeita (Subeita)	Ba.	110 030	Ruined town, churches, houses, cisterns, reservoirs, rubbish heaps, field walls in vicinity.
Isdeir, Kh.	A.	III. 185 263	Heaps of stones, rock-cut cistern.

Name of Site	Sub-District	Map Reference	Description
Isdūd	G.	VIII. 118 129	Artificial mound (er Ras). Maqām with inscriptions (esh Sheikh Ibrahim el Matbuli). Tessellated floor.
'Isfiya	H.	IV. 157 236	Tombs, cisterns.
Is-ha, Kh.	He.	XII. 159 109	Remains of walls, foundations, mosaics. To west wine-press, columns, rock-cut tombs, cisterns, caves.
el Is-haqiya	H.	IV. 162 232	see esh Sheikh Is-hāq, Kh.
Ishqaf, Tell	TK.	VI. 146 194	Artificial mound, surface stones and pottery, cistern, rubble wall, limestone capital.
Ishqāra, Kh.	RA.	X. 177 153	Foundations, heaps of building stones, uprights of press. To north wine press, cistern.
el 'Ish-sha, Kh.	Bn.	V. 200 217	see Zab'a, Kh.
Iahwa'	Jm.	IX. 151 132	Foundations.
Iakandar, Kh.	TK.	VI. 160 185	see Abu Bala, Kh.
Iam Allah, Kh.	Jm.	IX. 146 133	Foundations of walls, well.
Istabūl, Kh.	He.	XII. 163 097	Ruined walls, cisterns, caves, column shafts, rock-cut tomb, mosaic pavements, rock-cuttings.
Istās, Kh.	He.	IX. 132 125	Small ruin, ancient well.
Istūna, Kh. (Kafr Istūna, Kh.)	N.	X. 180 160	Remains of buildings (including el Habs) with large masonry, walls, vault, foundations, cisterns, tower, column shafts, capitals and bases, ancient road.
Jaba'	H.	IV. 147 220	Rock tombs, well, caves, ancient remains in village, mosaic fragments.
Jaba'	J.	VII. 171 192	Tomb, ancient remains beneath village.
Jaba'	Jm.	X. 175 140	Village on ancient site. Foundations, medieval tower (el Burj). Caves, cisterns cut in the rock, tombs.
Jabāliya	G.	XI. 101 104	Well, broken columns, rock-cut tomb, Masjid Abu Barjas.
el Ja'bari, Kh.	He.	XII. 142 087	Foundations, caves, cisterns.
Jabaris, Kh.	N.	VII. 192 196	Ruined walls of towers, foundations, pillar-shafts, mosaic pavement, broken sarcophagus, lintels, rock-cut tombs.
Jabbūl	Bn.	V. 198 219	Village on ancient site, tombs.
Jābir, Kh.	H.	IV. 146 218	Stone heaps, surface pottery on rising ground.
Jabjab, Kh.	J.	V. 175 205	Foundations of square building, surface pottery.
Jabr, Kh.	He.	XII. 147 113	Remains of building, foundations, door-posts, lintels, press, cisterns, caves.
el Jabn, Kh.	He.	XII. 133 110	Foundations, heaps of stones.
Jacob's Well	N.	VII. 177 180	see Bir Ya'qūb.
Jadira, Kh. (esh Sh. 'Alī Jidīr, Kh.)	Re.	IX. 146 137	Ruined tower and walls, cave cut in the rock with three arched cisterns, rock-cut tomb chamber.
Jadūr, Kh.	He.	XII. 159 116	see Ijdūr, Kh.
Jadūra, Kh.	J.	V. 175 213	Scattered stones, foundations, rock-cut cisterns and caves.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Ja'fâ, Kh.	S.	III. 190 270	Tumulus.
Jâfa, Kh.	J.	VII. 172 193	Ruined towers and walls of dry masonry, foundations, rock-cut cisterns and caves.
Jaffa	Ja.	VI. 127 162	Artificial mound beneath tower. Rock-cut tombs, medieval remains. Inscriptions at Qubbat esh Sheikh Murad. Sabil Abu Nabbât.
Jafrun, Kh.	N.	VI. 168 178	see Kafrûr, Kh.
Jahannam, Magharat	H.	IV. 162 234	see esh Sheikh Bureik.
el Jahms	H.	IV. 159 217	A mound with scattered stones.
el Jahûsh, Kh.	H.	II. 165 249	Heaps of stones, foundations, built spring.
el Jai, Magharat	Jm.	X. 179 139	Caves.
Jâlâ, Kh.	He.	XII. 157 114	Ruined walls, foundations of building, caves, cisterns, heaps of stones.
Jaladiya, Kh.	G.	VIII. 126 122	Traces of ancient building in the village, ruined cisterns.
el Jalakh, Kh.	He.	IX. 140 121	Foundations, door posts, scattered stones, cisterns and caves cut in the rock.
Jalama	J.	V. 160 213	Foundations, cisterns, rock-cuttings.
Jalama, Kh.	H.	II. 162 249	Artificial mound, remains of rough wall, surface pottery, cisterns, rock-cuttings.
el Jalama, Kh.	TK.	IV. 151 200	Foundations of walls, well, tombs.
el Jalama, Kh.	TK.	VI. 150 185	Foundations on rising ground, small pool, rock-cuttings, rock-cut tombs, column fragments, cistern.
Jalama, Kh.	G.	XI. 114 106	Rubble walls, foundations, cisterns, wells.
Jalamat en Nuhf	A.	III. 179 269	Traces of small settlement.
el Jalîl	Ja.	VI. 133 174	Rock-cuttings, foundations, caves, remains of tessellated pavements.
Jalîl, Kh.	A.	III. 173 273	Remains of church, vault, columns, capitals. Foundations of extensive buildings, tombs, caves, cisterns.
Jaljuliya	TK.	VI. 146 173	Artificial mound. Ruined mosque and khan, pool. Fragments of mosaics.
Jallûn, Kh.	A.	III. 172 257	Heaps of stones, foundations, cisterns.
el Jami', Kh. (en Nabi Danyâl)	Jm.	IX. 164 122	Remains of buildings and walls, rock-cut cave, remains of olive-crusher and press, vats, rock-cut cistern with steps, tomb and cave with columbarium, praying niche (Maqâm en Nabi Danyâl).
Jami' el Khadra	N.	VII. 174 181	see Huza Ya'qûb.
Jami' en Nuzailat	N.	VII. 197 165	Remains of square block house and foundations of circular building.
Jami' Tubrus	J.	IV. 165 201	Heaps of stones, well.
Jamiliya, Kh.	A.	III. 180 272	Small ruin.
Jammâ, Kh.	Ba.	XI. 097 088	Extensive ruins, mosaic pavement.
Jammâ, Tell	Ba.	XI. 097 069	Artificial mound, partly excavated.

Name of Site	Sub-District	Map Reference	Description
Jammain, Kh.	TK.	VI. 156 176	Extensive ruins, walls, three towers, cisterns, quarry, remains of enclosure walls.
Jammāla	Re.	IX. 159 153	Buried foundations of church.
Jammama, Kh.	Ba.	XII. 120 101	Cisterns, olive-press, fragment of tessellated pavement, tombs, capital and column drums, surface pottery and rubble; well.
Jamrīn, Kh.	He.	XII. 154 115	Cisterns, caves, foundations, heaps of stones.
Jamrura, Kh.	He.	XII. 148 110	Ruined walls, foundations, caves, cisterns.
el Jāniya	RA.	IX. 162 150	Remains of columns and capitals, tessellated pavement. To north ruined mosque and arched cistern, inscriptions.
Jannāba el Fauqa, Kh. (esh Sharqiya)	He.	IX. 147 121	Ruined walls of buildings, doorposts, rock-cut caves, cisterns.
Jannāba et Tahta, Kh. (el Gharbiya)	He.	IX. 145 121	Ruined walls, remains of press, cisterns.
Jannāta, Kh.	He.	XII. 139 102	Ruined walls, caves, cisterns.
el Janzur, Kh.	J.	V. 174 203	Foundations of walls, scattered stones, rock-cuttings.
Jarāba, Wadi	Ba.	XV. 162 058	Cave with graffiti and inscriptions.
el Jarādāt, Kh.	He.	XII. 164 106	Foundations of square building, cave, cisterns, ancient road.
Jarādāt, Kh.	He.	XII. 167 106	see Jarūn el Lauza, Kh.
Jarba	J.	VII. 174 199	Ruined buildings. Tomb caves, cisterns. To west inscription at esh Sh. Ibn Badriya.
Jarda, Kh.	Re.	IX. 155 150	Foundations, walls, cisterns.
el Jarīsha, Tell (Tell Napoleon)	Ja.	VI. 132 167	Artificial mound, partly excavated, ancient cemetery.
el Jarmaq, Kh.	A.	III. 188 266	Ruined walls, foundations, cisterns, olive press, pressing floors, rock-cuttings.
Jarrā'a, Kh.	N.	VI. 168 174	Ruined buildings, vaults, mosque, pool.
Jarrār, Kh.	J.	IV. 164 213	Scattered stones.
Jarwān, Kh. (Daqla, Kh.)	RA.	IX. 166 159	Foundations of buildings, remains of press, Maqām esh Sheikh 'Id.
Jaryūt, Kh.	RA.	IX. 163 144	Foundations.
Ja'thun, Kh.	A.	II. 168 268	Ruined walls, door-posts, domed Maqām, scattered dressed stones, tombs.
Jatt	A.	III. 172 264	Cisterns, built reservoir, cut stones, rock-cut tombs.
Jatt	TK.	IV. 154 200	Foundations, caves, cisterns, well.
el Jauf, Kh.	He.	XII. 155 097	Ruined buildings, remains of church to south-east, columns, bases, capitals, cisterns, caves, tombs.
el Jauq, Kh.	A.	III. 178 272	Ruined walls, foundations, cisterns, olive-presses.
el Jauza, Kh.	He.	XII. 144 107	Remains of building, well, steps cut in the rock, rock-cuttings.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Jauzariya, Kh.	A.	II. 168 274	Extensive ruined walls, remains of presses, cisterns.
Jazal el Khayâm, Kh.	Re.	VIII. 128 147	Traces of ruins.
Jazar, Tell	Re.	IX. 142 140	see Abu Shûsha.
Jazirat esh Shaddâdîn	H.	IV. 143 224	see Tantûra.
Jebel ed Deidaba	Nt.	III. 175 248	Dry-stone square wall, watch-tower, rock-cut tomb, remains of walls and enclosures.
Jebel Fureidis, Kh.	Jm.	XIII. 173 119	see el Furdeis.
Jebel Islamiya	N.	VII. 176 182	see Qabr en Nusrâni.
Jebel el Mukabbir	Jm.	X. 173 129	Foundations, fragments of columns.
Jebel el Qafza	Nt.	V. 178 232	Foundations and rock-cut apse of chapel. Rock-cut tombs, cisterns, remains of pool. Cave with prehistoric remains on east side of valley.
Jebel Quruntul	Jm.	X. 191 142	see Deir Quruntul.
Jebel Tannûriya	S.	III. 186 268	see Tannûriya, Kh.
Jebel et Tur (Mt. Tabor)	Nt.	V. 187 232	Ruins of fortress, monastic and other buildings, chapels, pool.
Jebel et Tur (Mt. Gerizim, Kh. esh Sheikh Ghânim)	N.	VII. 176 179	Ruins of church. Fortress, reservoir, cisterns. Ruined buildings.
Jebel 'Ubaid	S.	III. 187 272	Remains of tomb, rock-cut press.
Jebel Zuleiqa	Ba.	XV. 158 049	Enclosure of large undressed blocks, cave and cairns, ancient road.
Jeimar, Kh.	He.	XII. 140 097	Traces of ruins, caves, cisterns.
Jenin	J.	V. 179 207	Artificial mound, rock-cuttings, rock-cut tombs.
Jericho	Jm.	X. 195 141	Foundations of buildings, mosaic pavements. Architectural fragments in town. Artificial mound with remains of walls (Tell es Sultân). Tombs in vicinity.
Jerusalem	Jm.	X. 171 131	Ancient site.
Ji'ara	H.	IV. 161 223	see Giv'at Nu'ah.
el Jib	Jm.	IX. 168 139	Rock chamber, foundations. Crusaders' church, artificial mound; on hill to south rock-cut tombs, quarries, rock-cut press, well, cisterns, reservoir, rock-cuttings.
Jib'it, Kh.	N.	X. 185 160	Foundations, cisterns, rock-cut tombs, drafted stones.
Jibya	RA.	IX. 165 156	Cisterns, rock-cut pools, tomb, cave, rock-cuttings, foundations.
Jibyatha, Kh.	H.	II. 164 242	Artificial mound, scattered stones and ruined walls.
Jiddîn, Kh.	A.	III. 171 266	see Qal'at Jiddîn.
Jidru, Kh.	H.	II. 159 247	Artificial mound with ancient remains, vaulted well.
Jifât, Kh.	Nt.	III. 176 246	see Shifât, Kh.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Jifna	RA.	X. 171 152	Remains of two churches, foundations, fragments of sarcophagi, architectural fragments, tombs: "el Baubariya"; "el Burj"; cisterns, press to west.
Jifna, Kh.	Jm.	IX. 160 141	Ruined walls, olive press, caves, fragment of capital and of column shaft.
Jiftlik, Kh.	S.	III. 205 269	<i>see</i> Nijmat es Subh, Kh.
el Jihar, Wadi	He.	XIII. 174 104	<i>see</i> ed Deir, Kh.
Jiljiliya	RA.	X. 171 160	Foundations, remains of mosaic pavement.
el Jila, Kh.	G.	XII. 122 113	Surface pottery, scattered stones, cisterns, marble fragments.
Jilya	Re.	IX. 137 131	Foundations, rock-cut tombs, ancient well.
Jimzu	Re.	IX. 145 148	Well, cisterns.
Jinan, Tell	G.	XI. 080 086	Artificial mound, surface pottery.
Jinba, Kh.	He.	XII. 163 084	Foundations, heaps of stones, cut stones reused, caves, cisterns.
Jinjas, Kh.	Jm.	X. 180 127	Ruined walls, cisterns.
Jinna'ir, Kh.	Jm.	IX. 151 129	Ruined walls, rock-cut presses, cave and cisterns.
el Jirāba, Kh.	Jm.	IX. 156 135	Foundations, heaps of stones. Dressed masonry walls in ruins. Cistern, cave.
Jish	S.	III. 192 270	Ruins of two synagogues, sarcophagi, columns, tombs, cisterns, caves.
el Jisr (Dhahrat el Jisr)	Re.	VIII. 126 147	Tombs, cisterns, caves, rock-cut foundations of ancient bridge, surface pottery.
el Jisr, Tell	Bn.	V. 197 213	Artificial mound, with remains of buildings, architectural fragments, columns; paved ancient road, tombs. (<i>See also</i> el Qantara).
Jisr Banāt Ya'qūb	S.	III. 209 269	Flint implements, fossil bones in river bed.
Jisr Isdūd	G.	VIII. 119 132	Remains of bridge, cisterns. To north of bridge vaulted rubble tomb, traces of ancient settlement.
Jisr Jindās	Re.	IX. 141 153	Bridge with Arabic inscriptions and blazons.
Jisr el Majāmi'	Bn.	V. 203 225	Bridge. In its vicinity ruined khan, traces of vaults.
Jisr en Nuwā'ima	Jm.	X. 191 144	Bridge, aqueduct.
Jisr Saghir	T.	V. 204 228	Bridge.
Jisr es Sidd	T.	V. 203 233	Ruined bridge.
Jisr es Zarqa, Kh.	H.	IV. 142 217	Dam, bridge, rock-cuttings. Old quarries, rock-cut tomb.
el Jiya	G.	XI. 112 115	Ancient remains in village, architectural fragments, column.
Jiz, Rujm	Re.	IX. 144 135	Small mound with traces of foundations and hewn stones on surface.
el Jizl, Tell	Bn.	V. 203 206	<i>see</i> Makab el Jizl, Tell.
el Jubarat, Kh.	He.	XII. 133 100	Traces of settlement.
Jubb Rubeij, Kh.	A.	III. 175 268	Heaps of stones, rock-cut cisterns.

Name of Site	Sub-District	Map Reference	Description
Jubb er Rum, Kh.	Jm.	X. 176 128	Traces of settlement, cisterns.
el Jubbein, Kh.	Ba.	XV. 131 075	<i>see</i> Khashm Jubail, Kh.
el Jubei'a, Kh.	Jm.	IX. 159 139	Artificial mound, foundations. Ruined watch tower, heaps of stones, pottery. Ancient road to east.
el Jubei'a, Kh.	Jm.	IX. 164 133	Remains of buildings, press piers, cisterns.
el Judeida	A.	II. 165 259	Rock-cut cisterns, tombs, presses, caves.
	J.	VII. 179 194	Rock-cut tomb caves and cisterns in and near the village. Surface pottery.
el Judeida, Kh.	A.	II. 165 275	Heaps of stones, cisterns, rock-cut tombs, caves.
Judeida, Kh.	J.	V. 188 213	Foundations of buildings, heaps of stones.
Judeida, Kh.	G.	XII. 124 110	Cisterns, scattered stones, surface pottery.
Judeira, Kh.	Jm.	IX. 159 141	Foundations, column shafts and bases, mosaic floor.
el Judeiyida, Kh.	He.	XII. 141 115	Foundations, walls, heaps of stones, well, cisterns, caves. Roman milestones east of road.
el Judeiyida, Tell	He.	XII. 141 116	Artificial mound, remains of walls, gate, foundations of two towers, foundations of buildings, rock-cuttings.
Judrâya, Kh.	He.	IX. 150 122	Foundations, rock-cut cisterns, oil press with uprights.
Judur, Kh.	He.	XII. 159 116	Ruined walls, niche and column, caves, cisterns, remains of an ancient road.
Ju'eila, Kh.	A.	II. 170 273	Heaps of small stones, cisterns.
el Ju'eithini, Kh.	Ba.	XI. 117 093	Cisterns, heaps of stones, surface pottery.
Jufair, Kh.	Jm.	IX. 165 141	Ruined walls, foundations, cistern, remains of an old road.
Juhzum, Kh.	Jm.	X. 176 124	Ruined walls, cistern, rock-cut tomb.
Jul, Kh.	A.	III. 188 259	<i>see</i> Zeitun er Râma, Kh.
Julis	G.	VIII. 117 121	Village on ancient site. Incised lintel and press at the Maqâm. Well, rubble cisterns.
el Jundi, Kh.	Ba.	XI. 114 092	Heaps of stones, ruined cisterns, surface pottery.
el Juneid	N.	VII. 171 181	Ruins of fort. Arabic inscriptions.
Juneidiya, Kh.	N.	VII. 203 185	Two groups of foundations.
Junjâr	Nt.	V. 174 230	<i>see</i> Ginneigar.
Juraif el Ghazal, Wadi	Jm.	X. 195 133	Rock-cut cave.
Jurdeih, Kh.	A.	III. 171 278	Foundations, cisterns cut in the rock.
Jureibân, Kh.	J.	VI. 169 196	Foundations, cisterns, surface pottery.
Jureida, Rujm	He.	XII. 143 088	Walls, foundations, cisterns, rock-cut cave, ancient road.
el Jurfa, Kh.	He.	IX. 150 120	Foundations of buildings, column fragments, press, rock-cut cisterns and caves, well.
Jurish, Kh.	Jm.	IX. 158 125	Ruined buildings, cisterns, rock-cut tombs, caves, ancient road.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
el Jurn, Tell	Jm.	X. 193 142	Foundations, remains of synagogue with mosaic pavement.
Jurân el Lauza, Kh.	He.	XII. 167 106	Cisterns, heaps of stones.
Jûs, Kh.	A.	III. 180 266	Foundations of buildings and enclosure, heaps of stones.
Juseir	G.	XII. 128 118	Ruins of settlement, architectural fragments, rubble reservoirs. Remains of bridge, well.
Juweijsa, Kh.	He.	XII. 139 108	see el Mu'allagât, Kh.
Juweidira	J.	V. 175 213	see Jadûra, Kh.
Juweiyi, Kh.	He.	XII. 144 095	Foundations of buildings, press.
Kabâra, Kh. (Birkat Timsâh)	H.	IV. 144 216	Foundations of walls, tombs, masonry dam. Foundations of pool.
el Kabâra, Magharat	H.	IV. 144 218	Cave with prehistoric remains.
el Kabbush, Kh.	Jm.	IX. 161 138	Ruined walls and foundations of roughly cut stones, remains of olive mill, tunnel across valley to south.
el Kabri	A.	II. 164 269	Foundations of buildings, mosaic fragments, rock-cut tombs, ancient material in the village.
Kabshâni, Kh.	Nt.	V. 185 239	Foundations, stones, cistern.
Kâbûl	A.	III. 170 253	Ancient remains beneath village, foundations, tombs, cisterns, door posts, Roman road.
Kafa, Kh. (Kaffa)	TK.	VI. 155 189	Traces of buildings, wells, cisterns, mound.
el Kafira, Kh.	Jm.	IX. 160 137	Rectangular building on artificial hill top, foundations, walls with traces of towers of bossed masonry, cut stones, oil mill, rock-cut cistern, surface pottery.
el Kafr, Kh.	He.	XII. 152 117	Ruined walls, fallen masonry, press with uprights, rock-cut cistern, ancient road.
Kafr 'Ana	Ja.	IX. 138 159	Ancient site beneath village, foundations.
Kafr 'Ana, Kh.	Re.	IX. 139 134	Surface pottery, rock-cuttings, tombs, well.
Kafr 'Ana, Kh.	RA.	X. 174 153	Abandoned village with traces of earlier settlement.
Kafr 'Atiya	N.	VII. 181 168	Foundations.
Kafr Bara	N.	VI. 148 171	Foundations, cisterns and tombs, tessellated floor.
Kafr Bassa, Kh.	J.	IV. 152 205	Small artificial mound. Foundations, column, cistern, press.
Kafr Beita, Kh.	N.	VII. 181 177	Ruined walls, cisterns, rock-cut tomb, tessellated floor.
Kafr Bir'im	S.	III. 189 272	Remains of synagogue, tombs, olive presses, cave, cisterns, rock-cut tank.
Kafr Dâh	J.	V. 174 209	Rock-cut tombs, rock-cuttings and cisterns.
Kafr ed Dik	N.	VI. 158 164	Square tower, cisterns, pools, rock-cut tombs, decorated lintel, cupmarks.

Name of Site	Sub-District	Map Reference	Description
Kafr Dukk, Kh.	N.	VII. 184 193	see Fuk-ha, Kh.
Kafr Fār'āt, Kh. (Ein Kafr Fār'āt)	N.	VI. 169 185	Ruined walls of buildings, heaps of stones.
Kafr Fidiyā, Kh.	RA.	IX. 163 155	Ruined walls of buildings, door posts, rock-cut cave.
Kafr Gharib, Kh.	N.	VII. 183 169	Foundations, heaps of stones, cisterns.
Kafr Hāris	N.	VI. 163 169	Remains of a watch-tower. Maqām en Nabi Yusha' with inscription.
Kafr Hatta, Kh. (en Nabi Hatta, Kh.)	N.	VI. 147 170	Vaults (el Haba), ruined buildings, foundations, cisterns, well, pool, cave.
Kafr Inān	A.	III. 189 259	Foundations, rock-cut remains of building with column bases, architectural fragments, column shafts, pool, tombs; Maqām el Hajar el Azraq. Caves, rock-cuttings.
Kafr Insha, Kh.	Re.	VI. 149 161	Ruined village, vaulted buildings, cisterns, rock-cut tombs, rock-cut reservoir, quarries.
Kafr Istūna, Kh.	N.	X. 180 160	see Istūna, Kh.
Kafr Jaur, Kh.	He.	XII. 145 094	see Kafr Jūl, Kh.
Kafr Jinnis (el Kanisa)	Ja.	IX. 141 156	Remains of ruined tower on low mound, surface pottery.
Kafr Jūl, Kh.	He.	XII. 145 094	Foundations, caves, broken column shafts, architectural fragments, presses, cisterns, rock-cuttings.
Kafr Kama	T.	V. 192 236	Foundations, tessellated pavements, column fragments, lintel with Maltese cross, press, cisterns, tombs.
Kafr Kanna	Nt.	V. 182 239	Traces of medieval church, architectural fragments, column shafts, rock-cut tomb. To west remains of building at ed Deir.
Kafr el Labad	TK.	VI. 161 189	Ruins of buildings, cisterns cut in the rock. Tombs.
Kafr Lam	H.	IV. 144 227	Crusaders' fortress, quarries, tombs, rock-cuttings, cisterns.
Kafr Manda	Nt.	III. 175 246	Ancient remains, architectural fragments, sarcophagi at the spring, fragments of columns, capitals.
Kafr Misr	Bn.	V. 190 223	Foundations, built spring, broken sarcophagi.
Kafr Murr, Kh.	RA.	X. 172 149	Foundations of buildings.
Kafr Nāta, Kh.	RA.	X. 177 145	Ruined walls, vaults, cisterns, Maqām, caves.
Kafr Qari'	H.	IV. 155 212	Foundations, tombs, cisterns.
Kafr Qari', Kh. (el 'Uyūn, Kh.)	N.	VI. 158 174	Traces of ruins, two wells at foot of hill.
Kafr Qūs, Kh.	N.	VII. 173 182	Heaps of stones, building foundations, rock-cut cisterns.
Kafr Rut, Kh.	Re.	IX. 154 146	Extensive ruins. Foundations, ruined walls, caves, cisterns, buried building to south.
Kafr Sa	TK.	VI. 150 181	Foundations, cisterns, heaps of stones.

Name of Site	Sub-District	Map Reference	Description
Kafr Sabt (Umm el 'Alaq, Kh.)	T.	V. 192 239	Ruins of houses, fort and mosque, cisterns, presses, columns, architectural fragments.
Kafr es Samir, Kh.	H.	II. 148 244	Foundations, cisterns, caves, tombs, scattered masonry.
Kafr Shiyan, Kh.	RA.	IX. 165 146	Ruined buildings and tower, drafted masonry, pool, rough vault, cisterns, tombs, tessellated pavements.
Kafr Sibb	TK.	VI. 152 194	Ruined walls on mound, cisterns, caves, Maqām Jamāl ed Din with inscriptions.
Kafr Sām, Kh.	Jm.	IX. 159 126	Ruins of buildings and foundations, fragments of columns and base. Maqām esh Sheikh Musafer, ancient road.
Kafr Sumei'	A.	III. 179 265	Foundations, cisterns, tombs, mosaic fragments.
Kafr Tas, Kh.	Jm.	X. 172 142	Foundations.
Kafr Tāt, Kh.	RA.	VI. 161 160	Ruins of vaulted buildings.
Kafr Ya'rub	J.	V. 177 204	see Umm en Naml, Kh.
Kafr Yasif	A.	II. 166 262	Mosaic pavements, foundations, rock-cut cisterns and tombs, architectural and decorated fragments, press stones.
Kafra	Bn.	V. 196 222	Basalt trough, ancient site beneath village.
Kafrajân, Kh.	Ja.	IX. 138 160	Surface pottery and rubble. Column fragments.
el Kafrin	H.	IV. 162 220	Foundations, column shafts and capital, tombs, Maqām.
Kafrâr, Kh.	N.	VI. 163 178	Heaps of stones.
Kafruriya, Kh.	Re.	IX. 145 133	see Kefar Uriya.
Ka'kul, Kh.	Jm.	X. 174 136	Ruined walls, rock-cut cisterns, tombs.
el Kalbi, Kh.	H.	IV. 153 215	Traces of settlement.
el Kalkh, Kh.	Re.	IX. 148 148	Ruined walls, font with inscription, cisterns, moulded stones, rock-cut tombs.
Kammâna, Kh.	A.	III. 183 257	Ruined walls, cistern and cave, enclosure, circular pool.
Kammûniya, Kh.	N.	VII. 173 167	Traces of ruins, ruined watchtower, foundations, heaps of stones.
Kan'ân, Kh.	He.	XII. 157 102	Foundations, caves, tombs. Ruined watch tower to west.
el Kanâyis, Kh.	A.	III. 178 258	Ruined walls and remains of buildings, column shafts and bases, cisterns, rock-cuttings, marble fragments, to west tombs.
el Kanisa	Ja.	IX. 141 156	see Kafr Jinnis.
el Kanisa	He.	XII. 147 101	Foundations, capitals, shafts, lintel, font.
el Kanisa, Kh.	H.	II. 146 241	Artificial mound, traces of wall, rock-cuttings, vaulted cistern, rock-cut tombs, presses, old quarries.
Kanisat el 'Amari (Kh, Bir Kafr Nabid)	A.	II. 163 274	Extensive foundations, vaulted room, cisterns, olive-presses, well, architectural fragments, mosaic pavement.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Kanîsat er Ra'wât	Jm.	X. 172 123	Ruined church, crypt, remains of adjoining buildings to west.
Kanna, Kh.	Nt.	III. 181 240	Foundations, numerous cisterns cut in the rock.
Karâbin, Kh.	He.	XII. 154 117	Cistern, foundations, heap of stones.
el Karak, Kh.	H.	IV. 158 232	Remains of walls, foundations, tombs, fragments of mosaic pavement, rock-cut cisterns.
el Karak, Kh.	T.	V. 204 236	Artificial mound, remains of walls, aqueduct.
el Karak, Kh.	N.	VII. 180 165	<i>see</i> el Qariq, Kh.
Karâtiya	G.	XII. 124 117	Artificial mound, traces of ruined cisterns, architectural fragments.
Karâza, Kh.	S.	III. 203 257	Ruins of town, synagogue partly excavated, dolmen field to east and south-east.
Karkara, Kh.	A.	III. 171 275	Walls and foundations. Presses, tombs, cisterns. Column shaft, sarcophagus.
Karkash, Kh.	N.	VI. 161 166	<i>see</i> Kurqush, Kh.
Karkûr, Kh.	Ba.	XII. 127 081	Traces of extensive settlement. Cisterns and caves cut in the rock.
Karm Abu Tabaq, Kh.	Jm.	X. 187 128	Foundations, scattered stones, cave.
Karm el Ajaz	Jm.	X. 186 124	Scattered stones.
Karm 'Atrâd, Kh.	Jm.	X. 188 128	Remains of rectangular building, cave.
Karm el Hilu	N.	VII. 198 192	<i>see</i> el Hilu, Kh. Tell.
Karm 'Isa, Kh.	N.	VI. 158 168	Foundations, tomb.
Karm Salâma	Jm.	X. 171 135	<i>see</i> el Mughram, Kh.
Karm esh Shâmi	RA.	IX. 165 144	Remains of well-dressed masonry, surface pottery.
Karma, Kh.	He.	XII. 153 095	Foundations of walls, cisterns, presses.
el Karmil, Kh.	He.	XII. 163 092	Extensive ruins, two churches, castle, tower, masonry pool, rock-cut tunnel, rock-cut tombs, caves, architectural fragments.
Karmûl, Kh.	He.	XII. 149 111	Ruined walls and foundations of buildings, cisterns, caves, press to north.
el Karnûs, Kh.	TK.	VI. 157 191	Ruined buildings, rock-cut wine press, floors and vats, rock-cut tombs and cisterns, ancient roads to south-west, east and west.
Karza, Kh.	He.	XII. 150 094	Ruined buildings, foundations, column shafts, architectural fragments, vault, cisterns, well.
el Kasâ'ir, Kh.	Nt.	IV. 173 240	Foundations, scattered stones, rock-cut cisterns, tombs, rock-cuttings.
Kasfa, Kh.	N.	VI. 150 167	Ruined walls of squared masonry, pool, cisterns, press, rock-cut tombs, Roman road.
Kashda, Kh.	N.	VII. 153 191	Ruined buildings.
el Kasih, Kh.	Ba.	XII. 123 084	Scattered stones.
Kassâba, Kh.	Ba.	XII. 128 101	Traces of small ruin.

Name of Site	Sub-District	Map Reference	Description
Kaufakha	G.	XI. 118 098	Cisterns, marble capital, surface pottery, remains of a tessellated pavement, well.
el Kauka, Tell	Re.	IX. 152 139	see Yālū.
Kaukab el Hawa	Bn.	V. 199 222	Crusaders' fortress.
Kaukaba	G.	XI. 118 115	Pool, cisterns, foundations, column shafts and capital.
Kawakib, Kh.	J.	IV. 169 204	Ruins.
Kefar 'Esion	He.	XII. 163 117	Ruined megalithic building.
Kefar Shemaryahu	TK.	VI. 133 178	Rock-cut tombs.
Kefar Uriya	Re.	IX. 145 133	Foundations of buildings, to south-west rock-cut press with tessellated floor and niches, cisterns, tombs, columbaria.
Kefar Vitkin	TK.	VI. 139 199	Three areas with surface flints in sand dunes north and north east of settlement.
Keila, Kh.	Re.	IX. 149 133	Foundations, scattered dressed stones, door posts, rock-cut cisterns, tank and tombs.
Keisān, Tell	A.	II. 164 253	Artificial mound, wall foundations, glacis, well.
el Khadr (School of the Prophets)	H.	II. 147 248	Large cave, Greek inscription.
el Khadr	RA.	X. 179 151	Remains of church with forecourt and steps, rock-cut cistern, tomb, mosaics.
el Khadr, Kh.	He.	XII. 155 094	Ruins, heaps of well-cut stones, cistern.
el Khadra	G.	XI. 106 118	Rubble cistern and foundations.
el Khadra, Kh.	A.	III. 179 272	Foundations, of walls, cisterns, column, press with uprights.
el Khaladiya	T.	V. 189 236	Ruined wall.
Khalafitiya, Kh.	TK.	VI. 134 185	Scattered masonry, surface pottery.
el Khalasa	Ba.	XIV. 117 056	Ruined town, inscribed and architectural fragments, tombs, rubbish heaps.
el Khalil	He.	XII. 160 107	see Ramat el Khalil.
el Khālisa	S.	I. 294 290	Foundations of buildings, south of village. Surface pottery, rough mosaic. Dolmens (about 2 kms. to the east of Khālisa).
el Khalladiya, Kh.	Nt.	III. 172 240	Small artificial mound, remains of buildings, column fragments. To west: spring, aqueduct.
Khallat Abu Shāwir	Jm.	IX. 164 127	Foundations, tombs, conduit at spring ('Ein el Hadafa).
Khallat el 'Adas, Kh.	RA.	IX. 167 147	Traces of ruins.
Khallat el Beida, Kh.	Jm.	XIII. 163 119	see Hilāl, Kh.
Khallat el Burj	S.	III. 191 270	Rock-cut tombs with stone doors and traces of painting.
Khallat Hadaya	S.	III. 192 166	Dolmens.
Khallat el Hāma	Jm.	XIII. 171 118	Surface flints.
Kh.			
Khallat el Hamra,	Jm.	XIII. 172 111	see Sāhibā, Kh.
Kh.			
Khallat el Lauz	Jm.	XIII. 170 118	Flints.
Khallat el Meiya, Kh.	He.	XII. 164 095	Ruins, heaps of stones, cisterns.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Khallat Sam'a, Kh.	He.	XII. 147 093	Ruined walls, caves, rock-cut tombs.
Khallat el Wāwī, Kh.	A.	II. 166 273	Heaps of stones, cisterns.
el Khamīs, Kh.	Jm.	IX. 169 126	Caves, cisterns, tomb with stone door. Foundations, tessellated floor, remains of presses.
el Khan (Khan Lūbiya)	T.	III. 193 243	Foundations of a caravanserail, ruined birkeh, cisterns. Traces of megalithic structure on hillock.
el Khan, Kh.	T.	III. 201 253	see Khan Minya.
el Khan, Kh.	He.	IX. 148 121	Remains of building with colonnaded courtyard. Columns and bases, ancient road.
el Khan, Kh.	Jm.	IX. 155 124	Ruined khan with vaults, pool to west.
Khan Abu el Hajj Fāris	RA.	X. 174 155	Foundations and ruined walls, pool.
Khan el Ahmar	Bn.	V. 197 213	Ruins of a caravanserail; vaults, pool, inscribed lintel, sarcophagi, columns, tombs.
Khan el Ahmar, Kh. (Khan es Salāwina)	Jm.	X. 182 133	Ruins of monastery and church, mosaics, vaults, cisterns, remains of tower.
Khan el Hathrura	Jm.	X. 184 136	Remains of Crusaders' fortress with fosse, caves, cisterns. Mosaics and foundations in yard of modern building.
Khan Isdūd	G.	VIII. 117 129	Rubble foundations of caravanserail, sarcophagus.
Khan Jubb Yūsuf	S.	III. 200 258	Caravanserail, cistern with dome, pool.
Khan el Lajjūn	J.	IV. 167 220	Ruins of caravanserail.
Khan el Lubban	N.	VII. 174-163	Ruined caravanserail.
Khan Lūbiya	T.	III. 193 243	see el Khan.
Khan Minya (Kh. el Khan)	T.	III. 201 253	Remains of caravanserail, traces of ruins.
Khan er Ram	Jm.	X. 171 140	see er Ram, Kh.
Khan es Sahl	Jm.	X. 192 140	Foundations, scattered mosaics.
Khan es Salāwina	Jm.	X. 182 133	see Khan el Ahmar, Kh.
Khan es Sawiya	N.	VII. 175 166	Ruined rectangular building, rock-cut tombs.
Khan Yunis	G.	XI. 084 084	Caravanserail, Arabic inscriptions, architectural fragments.
el Khanazir, Kh.	He.	XII. 148 112	Cisterns, caves, ruined walls of buildings.
el Khanazir, Tell	G.	XI. 089 104	Mound with surface pottery, rubble and marble chips.
el Khaneizira, Kh.	H.	IV. 146 221	Foundations, well and ruined tank.
el Kharāb	Re.	IX. 142 157	Foundations of walls.
Kharab Abu Gharīb	N.	VII. 183 169	see Kfar Gharīb, Kh.
el Kharāba, Kh.	N.	VII. 180 180	Foundations, wall, rock-cut cisterns and pool, ancient road.
el Kharāba, Kh.	Jm.	X. 177 138	Heaps of stones, caves.
el Kharāba, Kh.	He.	XII. 159 096	Heaps of stones, caves, cisterns.
el Kharāyib	Bn.	V. 197 212	Foundations, walls, columns.
el Kharāyib, Kh.	Jm.	X. 177 130	Foundations, rock-cut cisterns, caves.
(Burj Qarrīt, Kh. Qarrīt)			Stone circle.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Kharazmiya, Rujm el Kharja, Kh.	He. J.	XIII. 170 082 VII. 171 197	Heaps of stones. Traces of settlement, cisterns cut in the rock.
Kharrûba, Kh.	J.	V. 180 210	Remains of tower with glacis, wall foundations, cisterns, caves, sarcophagus and tombs in vicinity.
Kharuf, Kh.	He.	XII. 148 113	Foundations, ruined walls, cisterns, caves, rock-sunk tomb, press.
el Kharwa', Kh.	He.	XII. 135 112	Foundations, cisterns.
el Khâshân	S.	III. 200 290	Terraces, stone circles, heaps of stones, pottery, tombs.
Khashm Jubeil, Kh.	Ba.	XV. 131 075	Cisterns, traces of ruins.
el Khashif, Kh. (Abu Ghalyân, Kh.)	Ba.	XIV. 112 075	Mounds with traces of buildings, rock-cut cisterns, caves, architectural fragments.
Khassa, Kh.	G.	VIII. 117 123	Extensive foundations, rubble cisterns, low mound, surface pottery.
Khâtûla, Kh.	Jm.	IX. 152 136	Foundations, walls of square building, rock-cut cisterns.
Khaur el Bak, Kh.	G.	VIII. 114 123	Vaulted cisterns and rubble tombs, surface pottery, rubble and tesserae over extensive site.
Khaur el Ballâwi	Jm.	X. 168 129	Ruined dry stone construction.
Khaur el Jummeiza, Kh.	G.	VIII. 122 128	Rubble chamber with domed roof (el Hammâm), rubble foundations.
el Khazna, Kh.	J.	IV. 169 222	Foundations of building, monolithic moulded pier, capital, architectural fragments.
Kheibar, Kh.	J.	VII. 176 195	Artificial mound, traces of circuit wall, buildings and foundations, rock-cuttings, tomb with sarcophagi, cisterns cut in the rock.
Kheir, Kh.	Jm.	IX. 154 133	Foundations of building, crushing stone, rock-cuttings, rock-cut cisterns.
el Kheishûm, Kh.	Jm.	IX. 146 126	Ruined walls of buildings, foundations, column fragments, remains of doors, rock-cut presses, cisterns, fragments of mosaic floor, rock-cuttings.
el Khirâqa, Tell	He.	XII. 134 104	Artificial mound.
el Khirba (Kh. Bureika, Kh. Sawawin)	H. Ja.	IV. 149 216 VI. 131 168	Foundations, surface pottery, tesserae, caves.
el Khirba	Ja.	VI. 131 168	Mound partly artificial, graves, surface pottery, rubble dressed stones, tesserae.
el Khirba (es Sallâqa, Tell)	Re.	IX. 130 147	Surface pottery, scattered masonry, sarcophagus, mosaic fragment, ancient rubbish heap.
el Khirba (Ni'ana)	Re.	IX. 138 142	Surface pottery, rubble, tesserae, stones.
el Khirba	Re.	IX. 143 152	see Ben Shemen.
el Khirba (Kh. Samwil)	Jm.	IX. 168 136	Foundations, traces of ruins, caves, cisterns, large mound.
el Khirba	G.	XI. 093 093	see er Rasm, Kh.
el Khirba, Tell	G.	XI. 104 106	Mounds with surface pottery in sand dunes, well.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Khisân	S.	I. 208 292	Tombs cut in the rock, rock-cuttings, stones.
Khisâs, Kh.	G.	XI. 108 117	Heaps of stones, wells, remains of pool, tombs.
el Khisâs, Kh.	Ba.	XII. 121 106	Surface pottery, well, rubble cisterns.
el Khiyâr, Tell	H.	II. 158 247	<i>see</i> es Subât, Tell.
Khubbaiza	H.	IV. 156 218	Traces of ancient remains.
el Khudeira, Kh.	H.	IV. 152 218	Walls, cave, cistern.
el Khudeira, Kh.	H.	IV. 169 236	Small artificial mound, foundations, scattered stones and pottery.
el Khudriya, Kh.	RA.	X. 177 146	Remains of buildings, columns, bases, font, mosaics, olive press, rock-cut cisterns.
Khulda	Re.	IX. 141 136	Village on ancient site.
el Khuljân, Kh.	J.	IV. 164 207	Square tower.
el Khuluf, Kh.	He.	XII. 139 117	Foundations, caves, cisterns.
el Khureiba	H.	II. 163 240	Caves, tombs, cisterns.
el Khureiba	A.	III. 176 276	Ruins of roughly built tower.
el Khureiba, Kh.	S.	III. 200 276	Ruined buildings, column fragments, rock-cut tombs, cisterns, oil and wine presses cut in the rock.
el Khureija, Kh.	TK.	VI. 147 177	Traces of ruins, caves, cisterns.
el Khureisa, Kh.	He.	XII. 143 109	Traces of settlement.
el Khureisa, Kh.	He.	XIII. 162 095	Foundations of buildings, remains of a small basilica, column shafts, architectural fragments, rock-cut cisterns, caves.
Khureish, Kh.	N.	VI. 147 172	<i>see</i> Qureish, Kh.
Khureitân, Kh.	Jm.	XIII. 173 117	Remains of monastery, ruined walls, tower, vaults, cisterns, masonry pool (Bir el 'Uneiziya).
Khureitân, Maghara	Jm.	XIII. 173 117	Cave with prehistoric remains.
Khursa, Kh.	He.	XII. 152 090	Foundations, ruined building with tomb, architectural fragments, dressed stones, well, cisterns.
el Khushsha, Kh.	T.	V. 202 234	Cisterns, heaps of stones.
Khutba, Kh.	RA.	IX. 154 146	Remains of buildings, foundations, pool, press, cisterns, column fragments, ancient road.
Khuweilifa, Kh.	Ba.	XII. 136 089	Ruined walls, column fragments, lintels, caves, cisterns, well.
Khuweilifa, Tell	Ba.	XII. 137 089	Artificial mound on natural hill.
el Kidish, Kh.	T.	V. 202 238	Ruined houses, heaps of stones, shaft of column.
Kidna	He.	XII. 140 117	Remains of a fort in village, foundations, caves, cisterns.
el Kiliya, Kh.	RA.	X. 183 149	Caves.
Kilûdiya	TK.	VI. 147 187	Foundations, rubble cisterns, scattered masonry and surface pottery.
Kisra	A.	III. 179 263	Foundations of walls, lintels, presses, cisterns, tombs.
Kufair	J.	VII. 182 198	Tombs, cisterns.
el Kufair, Kh.	He.	XII. 159 096	Ruined walls, caves, cisterns.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Kûfin, Kh.	He.	XII. 161 114	Ruined buildings, mosque, vaults, foundations, cisterns, press, reservoir, tombs.
Kûfiya, Kh.	G.	XI. 106 100	Heaps of stones, rubble cisterns, surface pottery and marble fragments.
el Kufîha, Kh.	G.	XI. 118 098	<i>see</i> Kaufakha.
Kufrat, Kh.	N.	VI. 169 185	<i>see</i> Kafr Fâr'ât, Kh.
Kufrata, Kh.	Re.	IX. 146 143	Vaulted rooms, ruined walls, rock-cut cisterns, rock-cuttings.
(<i>esh</i> Sheikh Suleimân, Kh.)			
Kufritta	H.	II. 160 245	Accumulated debris, foundations, well, rock-cuttings, mosaic pavement.
el Kufriya, Kh.	RA.	IX. 166 149	Ruined building, vault, tank.
Kuhla, Kh.	Ba.	XV. 155 078	Caves, cisterns cut in the rock.
el Kuleisa, Kh.	N.	VII. 177 182	Heaps of stones, press stone.
el Kuneisa, Kh.	S.	I. 204 293	Ancient cemetery, traces of built tomb.
el Kunnisa, Kh.	Re.	IX. 146 144	Foundations, fallen masonry, cisterns, rock-cut tombs.
Kur	TK.	VI. 159 182	Ruined watch-tower.
Kurdâna, Kh.	H.	II. 161 250	Ruins of rectangular building, to the north of it a large dam and mill.
Kurdâna, Tell	H.	II. 161 250	Artificial mound, traces of wall, quarries, tombs.
Kursikûr, Kh.	Re.	IX. 153 147	Ruins of two buildings, foundations, rock-cut cisterns.
Kurnub	Ba.	XV. 156 048	Ruins of town, churches, monasteries; fort, block-houses, architectural fragments, dams in wadi.
Kurqush, Kh.	N.	VI. 161 166	Ruined villages, rock-cut tombs, pool, quarries.
el Kurûm, Kh.	N.	VI. 167 186	Ruined walls, scattered dressed and decorated stones, architectural fragments, tombs, cisterns, caves.
Kurûm el Humeid, Kh.	A.	III. 179 273	<i>see</i> er Ruweisât, Kh.
Kusbur, Kh.	He.	XII. 157 112	Vaulted buildings, foundations, cisterns, rock-cut pool and spring.
Kuscifa, Kh.	Ba.	XV. 156 074	Ruins of three churches and town, caves, masonry well, cisterns.
Kuseiriya, Kh.	T.	III. 194 254	Heaps of stones, cisterns.
Kûsiya, Kh.	TK.	IV. 152 293	Artificial mound, foundations of undressed stones, surface pottery.
el Kuweib, Kh.	J.	VI. 166 196	<i>see</i> er Rama, Kh.
Kuweikat	A.	II. 164 264	Rock-cut tombs, well, vaulted building.
Kuweiziba, Kh.	He.	XII. 164 112	Ruined buildings, tower, drafted masonry, rock-cut caves.
el Lahm, Kh.	Jm.	IX. 159 138	<i>see</i> Abu Lahm, Kh.
el Lahm, Kh.	He.	XII. 140 109	Foundations, heaps of stones, wells, cisterns, caves.
Lajjân	J.	IV. 167 220	Artificial mound beneath village, remains of buildings and vaults, columns, tombs, cave with steps.
Laqiya, Kh.	Ba.	XII. 137 081	Foundations and caves, cisterns.

Name of Site	Sub-District	Map Reference	Description
Lasan, Kh.	G.	XI. 111 101	Surface pottery, marble fragments, scattered stones on rising ground, cisterns, traces of well.
Latatin, Kh.	RA.	IV. 166 142	Ruined buildings, cut stones, rock-cut tomb, ancient road.
Latrun	Re.	IX. 148 138	Ruins of castle, rock-cut tomb and water channel.
Lattun, Kh.	He.	IX. 136 126	Remains of square tower, foundations, scattered stones.
el Lauz, Kh.	N.	VI. 163 166	Heaps of stones, ruined walls, aqueduct, surface pottery.
el Lauz, Kh.	N.	VI. 163 166	Cisterns, tombs.
el Lauz, Kh.	Jm.	IX. 161 130	Tombs, ruined watch-tower, millstone.
el Lauza, Kh.	He.	IX. 144 125	Foundations, caves, cisterns, heaps of stones.
el Lauza, Kh	Jm.	IX. 166 136	Ruined khan and pool.
Lubiya	T.	III. 190 242	Rock-cut tombs, wine-presses, cisterns, architectural fragments reused in village, rock-cuttings.
Lubiya, Kh.	H.	IV. 150 233	Foundations of buildings, carved stones, fragments, cisterns, surface pottery.
Luqa, Kh.	Jm.	X. 172 125	Ruined building with stairs, cisterns; to north rock-cut and built pool.
Luqa, Kh.	He.	XII. 153 115	Foundations, cisterns, caves, column base.
Lydda	Re.	IX. 140 152	Partly rebuilt Crusaders' church, tombs, tessellated pavement.
Ma'abarot	TK.	VI. 141 197	<i>see</i> Madd ed Deir, Kh.
el Ma'bara	Bn.	V. 198 214	Quarry.
el Mabrûm, Tell (Suqûr, Kh.)	S.	I. 204 292	Foundations of walls, remains of olive mills and presses, surface pottery.
Madbasa, Kh.	Jm.	IX. 166 140	Walls, foundations, caves, cistern.
Madd ed Deir, Kh. (Ma'abarot)	TK.	VI. 141 197	Vaults, cistern, reservoir, rock-cut tombs.
el Madfa, Rujm	He.	XII. 156 087	Ruined watch-tower.
Ma'dhar	T.	V. 194 233	Vaults, foundations of church, reused lintels and architectural fragments, tombs.
el Madhbah, Kh.	Ba.	XV. 144 066	Foundations of building and surface pottery on hill. To north caves and cisterns (<i>see also</i> Abu Tulal, Kh.)
el Madrasa, Kh.	A.	III. 176 258	Traces of settlement.
el Madrasa, Tell (Ma'oz)	Bn.	V. 202 211	Artificial mound.
Madyan, Kh. (Qarn Hattin)	T.	III. 193 245	Circular enclosure of rough stones. Stone heaps, dry walls and surface pottery. Remains of square room and vaulted cisterns on southern peak.
el Mafjar, Kh.	Jm.	X. 194 143	Ruins of two palaces and other buildings, forecourt, pool, garden, enclosure wall, aqueduct; remains of bridge.
el Maghar	S.	III. 201 266	<i>see</i> Mughr el Kheit.
el Maghar	Re.	VIII. 130 139	Artificial mound, surface pottery, wells, rock-cut tombs.
el Maghâra, (el Ma'lawiya)	Re.	IX. 134 134	Surface rubble and pottery, foundations of reservoir.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
el Maghâra, Kh.	J.	VII. 171 198	Maqâm esh Sheikh 'Ali, 'Uqd Abu Zam-mûqa, Maqâm esh Sheikh Sarrar, re-mains of buildings, foundations, rock-cut caves and cisterns, rock-cuttings, cupmarks.
el Mahafir, Kh.	S.	I. 198 280	Ruined village on low mound.
el Mahami, Kh. (esh Shâdarwân, Kh.)	He.	XII. 145 101	Remains of church, font, column shafts. Ruined walls of drafted masonry.
Mahbûz, Kh.	A.	III. 175 282	Ruins of small town; remains of church with mosaics, foundations, vaults (Qasr el 'Ashiq), cisterns, rock-cut pool, tombs.
el Mahjar, Kh. (Umm esh Shuqaf, Kh.)	G.	VIII. 115 121	Rubble foundations, surface pottery and marble fragments.
el Mahma, Kh.	RA.	IX. 163 143	Ruined buildings, rock-cut cisterns.
el Mahrûna	J.	V. 174 202	see Qasr Mahrûn.
el Mahshûra	H.	IV. 161 228	Caves, tombs, rock-cut tunnel and chamber at spring. To east traces of ancient settlement.
el Mahzûq, Kh.	G.	XI. 117 111	Rubble foundations of extensive settle-ment.
Ma'in	G.	XI. 085 083	Mound, foundations, rubble cisterns fragments of columns, surface pottery.
el Ma'in, Kh.	Ba.	XI. 093 082	Traces of buildings, surface pottery, rubble cisterns.
Ma'in, Kh.	He.	XII. 163 091	Foundations of square tower, ruined buildings, cisterns, well, presses, shaft tombs, caves, surface pottery.
Maiyat 'Awad	Ba.	160 990	Square fort, ruined buildings of rough masonry, to north-west, north-east, east and north, three small mounds, terrace walls, surface pottery.
Majâdil, Kh.	He.	XII. 135 092	Ruins of buildings, column shafts, marble bases, rock-cut cisterns, caves.
Majâdil, Tell	He.	XII. 134 092	see Tabakhâna, Kh.
Majâhid Sheikhâ	TK.	VI. 139 196	Surface pottery and rubble, scattered tesserae.
el Majalis, Magharat	S.	III. 197 276	Cave with recessed chambers, cisterns, rock-cut tombs above and remains of stairs.
el Majd, Kh.	He.	XII. 145 099	Caves, cisterns, pillar-shafts.
Majd el Bâ', Kh.	He.	XII. 156 092	Walls, a reservoir, caves, tombs, ancient road.
Majd el Kurum	A.	III. 174 258	Ancient remains in village, built spring.
Majdal	T.	III. 199 248	Remains of walls and vaults, column fragments, foundations, ancient ceme-tery (300 m. south of site).
el Majdal	TK.	VI. 151 183	Terrace walls, surface pottery, columns
el Majdal	G.	XI. 111 120	Foundations of walls beneath village, Mosque of Saif ed Din Sular, Maqâm esh Sheikh et Tamîmi.
el Majdal, Kh.	H.	II. 161 244	Rock-cut tombs and cisterns, built well.
el Majdal, Kh.	TK.	IV. 150 202	Traces of buildings, surface pottery.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Majdal Bani Fadil	N.	VII. 184 166	Cisterns, caves, rock-cut tombs, columns.
Majdal Yaba	Re.	VI. 146 165	Medieval castle with tower (el Burj), remains of font, inscribed lintel, tombs, ancient road.
el Majdala, Kh.	He.	XII. 141 105	Foundations, remains of square tower, drafted masonry. Columns. Caves with niches. Two wells.
Makab el Jizi, Tell	Bn.	V. 203 206	Two artificial mounds and terrace, surface pottery and flints.
Makhādat el Burduḡāni	Bn.	V. 204 212	Remains of settlement.
el Makhbiya, Kh.	He.	XII. 146 116	<i>see</i> el Wāwiya, Kh.
Makhrash	RA	X. 178 147	Rock-cut cisterns, oil press.
Makhrum, Kh.	Jm.	X. 176 123	Foundations, caves, cisterns.
el Makhrūq	N.	VII. 198 170	Foundations, rock-cut channel, rock-cut chambers.
Makkus, Kh.	G.	VIII. 115 122	Foundations, ruined cisterns, surface pottery.
Makmish (Dhahrat Makmish, Tell el Qantār)	Ja.	VI. 131 174	Artificial mounds (including Tell el Qantār), foundations of buildings, surface pottery and marble fragments.
el Makr	A.	II. 163 260	Foundations, caves, rock-cut tombs, some cut stones.
el Mālāt, Tell	H.	IV. 141 216	Mound with remains of squared masonry wall. Surface stones, marble and pottery fragments. Ruined pool to east.
Mālāt, Tell	Re.	IX. 137 140	Artificial mound, surface pottery, remains of pool.
el M'alawiya	Re.	IX. 134 134	<i>see</i> el Maghāra.
el Malih, Kh.	N.	VII. 195 193	Ruined walls, surface pottery and tesserae.
el Māliha	Jm.	IX. 167 129	Ruined tower, caves, tombs.
Māliha, Kh. (including ash Sbeikh Bureik)	H.	IV. 145 231	Foundations, rock-cuttings, tombs, caves, quarries, cisterns, presses.
el Māliha, Tell	Bn.	V. 199 211	Artificial mound, surface pottery, flints.
Māliha, Tell (el Muleiha, Tell)	Ba.	XII. 129 097	Artificial mound, foundations, surface pottery.
Mallta, Kh.	G.	XII. 120 114	Rubble foundations, pool, surface pottery, marble fragments.
Māliyāt el Fanash	He.	XII. 142 113	Boundary wall enclosing tract east and north-east of Beit Jibrin.
Malkat-ha, Kh.	He.	IX. 152 121	Ruined walls of buildings, drafted masonry, font with inscription, oil-press, architectural fragments, caves, cisterns.
Mallāha	S.	III. 205 277	Artificial mound, traces of masonry.
el Mallāha	H.	IV. 143 215	Foundations of square building, rock-cuttings, columbarium.
Mallāha, Kh.	A.	II. 158 266	Debris of settlement, rock-cut tombs, mosaic pavement, cisterns, marble fragments, surface pottery.
el Malta'a, Kh.	Ba.	XI. 106 081	Traces of buildings, cisterns, scattered stones, water channel.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Malûf, Kh.	Nt.	V. 186 225	Rock-cut tombs and cistern, heaps of stones, quarries.
Ma'lûl	Nt.	V. 173 234	Traces of foundations, tombs.
Mâmâs, Kh.	He.	XII. 159 111	Foundations, heaps of stones, tombs, cisterns, ancient road.
Mâmilya, Kh.	T.	III. 191 251	Traces of ruins, heaps of stones, cisterns.
Manâ'ya, Wadi	Ba.	140 900	Ruined walls and enclosures, ancient copper mines.
el Manâra	T.	III. 201 240	Ruined houses.
el Manâra, Kh. (Adathîr)	S.	III. 185 271	Foundations, rock-cut cisterns, wine press.
Manâsîf, Tell	TK.	VI. 152 176	see Dhahr el Manâsîf.
el Manatîr	RA.	X. 181 153	Cave, watch-tower.
(Ras ed Deir)			
el Manatîr, Kh.	H.	IV. 169 224	Traces of settlement, scattered stones, granite column, surface pottery.
el Manawât, Kh.	A.	II. 164 272	Ruined building (el Baubariya), cisterns, heaps of stones.
el Mandûr	Ba.	XI. 100 091	Ruined rubble cisterns, tombs, scattered pottery, stones.
el Manhata, Kh.	A.	III. 172 272	Ruined walls, cisterns, remains of a portal, pool, quarries, rock tower with cistern.
Man'in, Kh.	He.	XII. 158 110	Beneath modern ruined village: foundations and cisterns, rock-cut caves.
Manna', Kh. (Abu Suqeir, Kh.)	RA.	IX. 156 145	Rock-cut tombs and remains of peristyle building, rock-cut steps.
el Manshiya, Tell	Bn.	V. 199 210	Artificial mound.
el Mansi, Kh.	Re.	IX. 146 148	Cisterns cut in the rock, surface pottery.
el Mansiya, Kh.	Re.	IX. 136 127	Ruins of buildings, caves, wine-press cut in the rock, lintel-stones, traces of terracing to east.
Mansûr el 'Aqqâb, Kh.	H.	IV. 144 217	see esh Sheikh Mansûr el 'Aqqâb, Kh.
el Mansûra, Kh.	H.	IV. 158 230	Foundations, fallen masonry, cistern, well, rock-cut tombs.
el Mansûra, Kh.	T.	V. 202 234	see el Khushsha, Kh.
el Mansûra, Kh.	G.	XI. 100 096	Heaps of stones, ruined cisterns, surface pottery.
Mantarat el Quta	S.	III. 191 268	Ruined watch tower.
Ma'oz	Bn.	V. 202 211	see el Madrasa, Tell.
Maqâm el Arba'in	He.	XII. 159 104	see er Rumeidî.
Maqâm el Imam	Jm.	X. 191 144	Maqâm, three column shafts, foundations of buildings with surface pottery.
'Ali ibn Abu Tâlib			
Maqâm en Nabi Yahya	Re.	VI. 145 162	Rectangular building with portico, foundations of enclosing wall, rock-cut tombs, cisterns.
Maqâti' 'Âbûd	RA.	IX. 156 159	Rock-cut tombs, some with carved ornament, painted plaster, quarries.
el Maqâtîr, Kh.	RA.	X. 173 147	Ruins of basilical church, lintels, fallen column, bases.
Maqbarat el Bureij	H.	IV. 146 214	see Benyamina.
el Maq haz, Kh.	He.	XII. 131 102	Cut stones.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Maqhuẓ, Tell	N.	V. 197 201	Small artificial mound by spring.
Maqīqa, Kh.	Jm.	IX. 169 135	see Beit Kika, Kh.
Mar 'Abādi	RA.	IX. 157 158	see 'Abūd.
Mar Eliās	H.	II. 148 248	Stone enclosure with architectural fragments, remains of rock-cut chapel.
Mar Eliās	Jm.	X. 170 127	Monastery, partly medieval.
Mar Sābā	Jm.	X. 182 123	see Deir Mar Sābā.
Mar Theodros	RA.	IX. 157 158	see 'Abūd.
Mar Yuhanna	Jm.	X. 201 138	see Qasr el Yahūd.
Ma'raba, Kh.	G.	XI. 107 111	Remains of rubble reservoirs, rubble foundations, surface pottery.
el Maraghib, Kh.	Jm.	X. 171 135	see el Mughram, Kh.
Marāh el Maut	N.	VII. 189 195	Remains of square building, traces of Roman road, cistern.
el Marājim, Kh.	N.	VII. 194 162	Foundations, heaps of stones.
el Marājim, Kh.	He.	XII. 152 100	Ruined walls, foundations of large rough stones.
el Marasān, Tell	A.	III. 179 251	Artificial mound.
Mar'ash, Kh.	He.	XII. 139 112	Foundations, cisterns, caves, pressing floor, traces of ancient road to east.
el Marashān, Kh. (Sawabta, Kh.)	G.	XI. 118 105	Foundations, surface pottery and glass, marble fragments at well.
Marda	N.	VI. 169 169	Three ruined mosques, cisterns, pool.
Marj el Baina, Kh.	A.	II. 170 273	see Ju'eila, Kh.
Marj el Fikya	Jm.	IX. 156 135	see el Jirāba, Kh.
el Markaz, Kh.	He.	XII. 164 096	Traces of foundations, heaps of stones, cisterns, caves.
Marmita, Kh.	Jm.	IX. 151 130	Ruined walls, caves, cisterns, rock-cuttings, stone with cupmarks.
el Marqab, Rujm	Ba.	XVI. 168 050	Remains of two-roomed building, cairns, graves.
Marrina, Kh.	He.	XII. 161 116	Ruins of buildings, vaults, well, caves.
Marsī, Kh.	Jm.	XIII. 163 119	Foundations of buildings, heaps of stones, cisterns, white tesserae on surface.
Martina, Kh.	He.	XII. 140 093	Traces of buildings.
Mārūs, Kh.	S.	III. 200 270	Foundations, rock-cut tombs and presses, cave with stone door.
el Ma'sa, Magharat	Jm.	XIII. 172 117	Cave.
Manada (Sabba)	He.	XIII. 184 090	Fortress with ruined buildings. Roman camps and siege works.
el Mas'ada, Kh.	He.	XII. 137 104	Traces of buildings, caves.
Masā'id, Kh.	TK.	IV. 149 200	Rubble, tesserae, surface pottery, stones.
el Masā'id, Kh.	G.	XI. 103 099	Cisterns, granite column, surface pottery.
el Masāni', Kh.	Jm.	X. 171 135	Church cut partly in the rock, cisterns, rock-cut pool, surface pottery and tesserae. To east (in Wadi Masāni') rock-cut tomb with frieze and imitation masonry. Other tombs and rock-cuttings.
el Masarra, Kh.	He.	XII. 134 111	Traces of foundations.
Mas-ha, Kh.	Nt.	V. 191 233	Foundations, vaults, cisterns, mill stones, architectural fragments.

Name of Site	Sub-District	Map Reference	Description
el Masha'ala, Rujūm	He.	XII. 136 115	Foundations, scattered stones, surface pottery.
Mash-had	Nt.	V. 181 238	Artificial mound, rock-cut tombs, rock-cuttings.
Mash-had Sidna el Husein	G.	XI. 108 119	see el Husein.
el Mashnaqa, Tell	G.	XI. 115 108	Traces of foundations, surface pottery and rubble.
el Mashrāb, Kh.	Jm.	X. 187 137	Remains of building with mosaic pavement; rock-cut cave.
el Mashrafa, Kh.	Ba.	XI. 102 093	Heaps of stones, rubble cisterns, surface pottery, marble fragments and capital.
Ma'sidi, Wadi	H.	IV. 145 225	Tombs, caves.
el Masiya, Kh.	A.	III. 182 272	Scattered stones, tombs.
Maskana, Kh.	Nt.	III. 189 243	Extensive ruins, rough stone enclosures, foundations of walls, rock-cut cisterns, tombs, pool, fragment of Roman milestone, caves and wine-presses cut in the rock.
Maslakhīt, Kh.	A.	III. 183 248	Foundations, remains of tower, cisterns, heaps of stones.
Masmar, Kh.	Jm.	IX. 157 136	Remains of enclosure.
el Masmiya el Kabira	G.	VIII. 130 129	Old foundations and rubbish heaps, well.
Masqūfa, Kh.	TK.	VI. 156 193	see Husein, Kh.
Massin, Kh.	J.	VI. 161 196	Ruins, well.
el Mastaba, Tell (including Dabāyib Jurat el Fijil)	Bn.	V. 197 213	Artificial mound, tombs, late Roman wall and tower, remains of monastery and church with mosaic pavements, ancient cemetery, sculpture fragments, reservoir.
el Ma'sub, Kh.	A.	II. 165 276	Foundations of houses, olive presses, tombs, cisterns.
el Mas'ud, Kh. (el Bustān, Kh.)	He.	IX. 147 121	Masonry pool.
Mas'ud, Tulūl	TK.	IV. 143 202	Surface pottery on sand dunes.
el Matābin, Wadi	H.	IV. 153 227	Cave, cairns and dry stone structures on ridge to east.
Mat-huma, Maghārat	Nt.	V. 181 233	Cave.
el Matlab, Tell	Jm.	X. 194 142	Foundations, surface pottery.
Matwi, Kh.	N.	VI. 162 165	Ruined village.
el Mazaqqa, Kh.	T.	III. 193 248	Foundations, heaps of stones, a cave, rock-cut well, a trough cut in the rock.
el Mazār (esh Sheikh Yahya)	H.	IV. 147 232	Surface pottery, heaps of stones and accumulated debris, rock-cut tombs, rock-cuttings.
el Mazār, Tell (Ghor el Far'a)	N.	VII. 196 171	Artificial mound, surface pottery.
Mazār esh Sheikh Muhammad	Nt.	V. 189 234	see esh Sheikh Muhammad, Kh.
el Mazāri', Kh.	RA.	X. 176 151	Ruined walls of houses, large rock-cut cistern, well to south-east.
Mazāri' en Nubāni	RA.	VI. 166 162	Foundations, caves, watch-tower, rock-cut tombs.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Mazmûriya, Kh.	Jm.	X. 173 125	Foundations, cisterns, cave.
el Mazra'a	A.	II. 160 265	Remains of medieval fort in village, olive presses, cisterns, tombs, bridge across valley to north.
el Mazra'a, Kh.	H.	IV. 143 222	Ruins of square vaulted tower, caves to south.
el Mazra'a, Kh.	Nt.	V. 179 223	Ruins, broken sarcophagi, mosaic fragment, wells.
el Mazra'a, Kh.	RA.	VI. 166 162	see Mazâri' en Nubâni.
Megiddo	J.	IV. 168 221	see el Mutasallim, Tell.
Meirun	S.	III. 191 265	Remains of synagogue, walls of drafted masonry in village, rock-cut tombs, sarcophagi, cisterns, olive presses, architectural remains. To east dolmens by road to Sufsaf.
Meirun, Wadi	S.	III. 192 265	Tombs and caves cut in the rock.
el Meisiya, Kh.	Re.	IX. 142 138	Foundations, surface pottery and stones.
el Meita, Kh.	RA.	IX. 162 144	Remains of church, columns and bases, foundations of other buildings, caves, rock-cut tombs.
Meithalun	J.	VII. 176 193	Traces of old remains in village.
Merhavia	Nt.	V. 179 223	Remains of fort on artificial mound with moat.
(el Fula)			
Messilot	Bn.	V. 165 211	Site of ancient cemetery, sarcophagi, scattered stones.
Mi'ar	A.	III. 174 253	Rock-cuttings, traces of ancient masonry, column fragments, olive presses, cisterns.
Mibilya, Kh.	A.	III. 173 260	Foundations, walls, cisterns, column bases.
el Midân, Kh.	RA.	IX. 159 152	Ruined walls and foundations, rock-cut cisterns, tower.
Midân Abu Zeid	G.	XI. 102 100	Two granite columns.
Midya, Kh.	Re.	X. 150 149	Foundations, rock-cut tombs, cisterns, wine presses.
Mi'ilya	A.	III. 175 270	Remains of Crusaders' fortress, rock-cuttings, tombs, mosaics, cisterns, architectural fragments.
el Milh, Kh. Tell	Ba.	XV. 152 070	Artificial mound with traces of rectangular building and walls. Extensive site with ruins of houses. Surface pottery and ancient rubbish heaps. Isolated ruined buildings and cisterns in vicinity.
Mimâs, Tell	A.	A. 165 263	Artificial mound, cisterns, winepress, tombs, built reservoir at well.
el Mina	G.	XI. 097 104	Extensive traces of settlement beneath sand-dunes, surface pottery, traces of foundations, marble fragments, fallen column in sea.
el Mina, Kh.	N.	VI. 165 189	Foundations, heaps of dressed stones, cisterns, rock-cuttings, surface pottery and tesserae.

Name of Site	Sub-District	Map Reference	Description
Minat Abu Zabâra	TK.	IV. 138 201	Traces of settlement, surface pottery and tesserae, rock-cut tombs to north.
Minat Isdûd (Minat el Qal'a)	G.	VIII. 114 132	Remains of fort with round towers, ruined buildings, domed and vaulted rooms, rubble foundations, architectural fragments, surface pottery.
Minat Rubin (including ed Dakâkin)	Re.	VIII. 121 148	Remains of harbour and town, surface rubble and walls beneath dunes. Rock-cut tombs, cisterns, graves, tiled floor.
el Mintara, Kh.	N.	VII. 175 176	Foundations, rock-cuttings, cup-marks, rock-cut tomb-caves, ruined watch-tower.
Minya, Kh.	T.	III. 201 252	Ruined palace.
el Minya, Kh.	He.	XIII. 171 114	Foundations, ruined walls, caves.
Miras ed Dîn, Kh.	N.	VII. 186 167	Foundations, cisterns, caves.
el Mird	Jm.	X. 185 125	Remains of chapel with mosaic floor and chancel posts, foundations, caves, marble fragments, mosaics, font, cisterns, tombs, rock-cut ditch and reservoirs, aqueduct and bridge.
Miryam, Kh. (Kh. Burhan)	N.	VI. 148 172	Foundations, heaps of stones, cistern, rock-cut tomb, wine press.
Miryam, Tell	Jm.	X. 175 141	Cave, enclosure wall, rock-cut pool to north.
Mi'saba, Kh.	G.	VIII. 116 124	Traces of settlement, remains of rubble constructions, surface pottery.
el Misbah, Kh.	RA.	IX. 157 143	Rock-cuttings rock-cut tombs, mosaic pavements, presses and cisterns, foundations.
el Mishash, Kh.	Ba.	XV. 147 069	Artificial mound with foundations of building in rough-hewn flint masonry. Ruined block-house 2 km. to east. To north-east traces of buildings, scattered stones and surface pottery over extensive area.
Mishmish, Kh.	A.	III. 174 275	Ruins of small town, houses with doors and windows in situ, olive press, tombs, rock-cut cisterns with masonry shafts.
Mishmish, Kh.	Jm.	X. 175 127	see Deir es Sûq.
el Mishqafa, Tell	G.	VIII. 111 122	Remains of brick walls, surface pottery, tombs.
Miska	TK.	VI. 143 180	Traces of earlier settlement in and around the village; architectural fragments.
Miska, Tell	N.	VII. 187 182	Artificial mound, surface pottery and glass. Remains of rough stone building, scattered stones.
Mithilya, Kh.	H.	IV. 147 239	Foundations of buildings, scattered masonry, well, cisterns, tombs, wine press.
el Mitraz, Kh. (es Sukkar, Kh.)	Jm.	IX. 155 131	Traces of settlement, caves, cisterns, presses.
el Miya, Kh.	He.	XII. 164 095	see Khallat el Meiya, Kh.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Miyamas (Ras el 'Ein, Ras el Ma, Umm el Yamas)	H.	IV. 146 216	Three small mounds, remains of masonry, sarcophagus, aqueduct, tombs.
Montfort	A.	III. 171 272	<i>see</i> Qal'at el Qurein.
el Mu'allaqât, Kh.	He.	XII. 139 108	Foundations, cisterns.
Mu'arrash Ba'ra, Kh.	He.	XII. 145 111	Ruined walls of rectangular buildings, cisterns, scattered lintels and door-posts, oil and wine presses.
Mu'âwiya	J.	IV. 160 215	Ruined caravanserail.
Mubarak, Tell	H.	IV. 143 215	Artificial mound partly excavated, remains of Roman mausoleum.
el Muda'dir	N.	VI. 159 174	Ruined village.
el Mudahdara, Kh.	TK.	VI. 151 183	Ruins of fort, rock-cut wine presses, tombs.
el Mudeira	S.	I. 204 296	<i>see</i> Abil, Tell.
el Mu'eisara, Kh.	S.	III. 208 274	Traces of foundations on small artificial mound.
Mu'eyid, Kh.	He.	XII. 161 085	<i>see</i> Umm el Qaryatein, Kh.
Mûfiya, Kh.	N.	VII. 199 184	Ruined walls and cisterns, watch tower to north.
el Mughaiyir	N.	X. 183 158	Cisterns, rock-cut wine-press, ancient material in village.
el Mughaiyir, Kh.	J.	V. 189 203	<i>see</i> el Mutilla, Kh.
el Mugheifir, Kh.	Jm.	X. 195 139	Remains of square building with pool.
el Mugheifir, Rujm	Jm.	X. 195 138	Ruins of large building, cisterns, vaults, pool.
Mugheisil, Kh.	Ba.	XII. 131 097	Remains of square building with pool. Traces of settlement.
Mugheisil el 'Idda, Magharat	Jm.	XIII. 180 110	Cave.
Mughr el 'Ababisha	TK.	VI. 133 178	<i>see</i> Kefar Shemaryahu.
Mughr el Kheit	S.	III. 201 296	Remains of building, doorposts, caves, rock-cut tombs, columns, a pedestal, oil mill, cisterns.
Mughr esh Shab'ân	He.	XII. 145 089	Ruined buildings, foundations, cisterns, tombs, rock-cut cave with steps.
Mughr 'Uba	S.	III. 195 276	Tombs, olive and wine presses, caves, cisterns, rock-cuttings, rock-cut steps.
el Mughrabi, Tell	Ba.	XI. 101 088	Traces of settlement, surface pottery over extensive area.
el Mughrâm, Kh. (Karm Salâma, el Maraghib, Kh.)	Jm.	X. 171 135	Foundations, old walls, watch-tower.
el Muhaffar, Tell	J.	V. 171 205	Artificial mound, with surface stones and pottery. To north heaps of stones (Kh. el Muhaffar).
Muhammad es Sâlih, Kh.	H.	IV. 160 210	<i>see</i> el Muntar.
el Muharraqa	Ba.	XI. 113 097	Remains of mosaic floors, cisterns, marble fragments, surface pottery.
el Mujadda'a, Kh.	J.	V. 193 203	Low artificial mound, shaft graves, surface pottery.

Name of Site	Sub-District	Map Reference	Description
el Mujeidil	Nt.	V. 173 232	Roman road.
Mujeidilât, Kh.	Ba.	XII. 135 091	Ruined cisterns, scattered stones, caves.
Mukeiman, Kh.	Ba.	XII. 132 092	see Umm 'Uleiyân.
Mukeimin	G.	XIV. 084 079	see el Mukheimil.
el Mukhabbi	N.	VIII. 189 196	see Qasr esh Sheikh Ghazâl.
Mukhalid	TK.	VI. 138 193	see Umm Khâlid.
el Mukheimil	G.	XIV. 084 079	Rubble cisterns, surface pottery.
el Mukheizin, Kh.	Re.	IX. 132 134	Well, pool, cisterns, scattered stones and pottery.
el Mukhmar, Tell	Ja.	VI. 140 171	Artificial mound, graves in vicinity.
Mukhmâs	Jm.	X. 176 142	Traces of ancient settlement, tombs, mosaic pavement.
Mulabbis	Ja.	VI. 139 167	Artificial mound, tessellated floor, surface pottery.
el Muleiha, Tell	Ba.	XII. 129 097	see el Mâliha, Tell.
el Muna, Kh.	A.	II. 167 265	Foundations, rock-cut cisterns, presses, tombs, rock-cuttings.
el Muneizil, Kh.	He.	XII. 164 099	Traces of settlement, caves, tombs, rock-cuttings.
el Muntar	T.	III. 193 245	see el 'Eika, Kh.
el Muntar (Muhammad es Sâlih, Kh.)	H.	IV. 160 210	Cairn of fallen stones, ruined towers.
el Muntar	N.	VI. 154 174	see el Quseir, Kh.
el Muntar, Kh.	S.	III. 205 265	Foundations, square stones, column shaft and base.
el Muntar, Kh.	J.	IV. 163 207	see Umm Dar, Kh.
el Muntar, Kh.	J.	IV. 164 207	see el Khuljân, Kh.
el Muntar, Kh.	Ja.	VI. 134 173	see Rishpon.
el Muntar, Kh.	Re.	VI. 148 160	Ruined watch-tower, rock-cut cave.
el Muntar, Kh.	N.	VII. 185 162	Foundations, heaps of stones.
el Muntar, Kh.	He.	IX. 151 124	Small ruined building.
el Muntar, Kh.	Jm.	X. 183 127	Foundations of squared stones, rubble cisterns, well in valley.
el Muntar, Kh. (Shi'b Abu Rijâm)	He.	XII. 157 094	Remains of building with columns. Foundations, caves, tombs, cisterns. Remains of building and wall at Shi'b Abu Rijâm.
Muntar el Abyad	Bn.	V. 197 211	Mound with surface pottery, stone sarcophagus near by.
Muntar el Azraq	Bn.	V. 195 211	Low mound with traces of building and surface pottery.
Muntar el Banik	N.	VII. 191 175	Watch-tower, cairn of rough stones.
Muntar Mâfiya	N.	VII. 199 184	Ruined watch tower.
Muntar esh Shaqq	N.	VII. 197 195	see esh Shaqq, Kh.
el Muqanna', Kh.	Re.	IX. 136 132	Mound with surface pottery, foundations of walls over extensive area.
Muqeisima, Kh.	N.	VII. 193 183	Foundations, cisterns.
el Murâba'a, Kh.	RA.	X. 177 148	Remains of rock-cut foundations, traces of a wall, rock-cut cisterns, columns.
el Mûraq, Kh.	He.	XII. 147 104	Ruined buildings; cisterns with steps, caves, wall with arch at el Qal'a to east.
Murara, Kh.	RA.	X. 172 149	see Kafr Murr, Kh.
Murashrash	Ba.	140 880	Heaps of copper slag.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
el Murassas, Kh.	Jm.	X. 179 132	Ruined monastery with walls, tower, pavements, remains of church, vaulted and rock-cut cisterns. To west cistern with octagonal well-head, conduit and reservoir. To east and south-east ruined buildings and cisterns. Ancient road to north-east.
Mureibid, Tell	T.	III. 200 252	<i>see</i> el Hunûd, Tell.
Murra, Tell (el Akheidir, Tell)	G.	VIII. 118 137	Artificial mound.
el Murrân, Kh.	Jm.	IX. 163 136	Ruined walls of rough stone, ancient road. Rock-cut tomb.
Murrân, Kh.	He.	XII. 138 094	Remains of buildings, dressed masonry, caves, cisterns.
Murt es Seil, Kh.	He.	XII. 133 112	Foundations, cisterns, reservoirs, caves.
el Murtaf'a	J.	IV. 167 217	Ruined vault.
Mûsa, Tell	Ba.	V. 204 222	Artificial mound.
Mûsa Shabin, Kh.	Re.	VIII. 128 145	Ancient site, surface pottery.
Musabbih, Tell	G.	XIV. 081 080	Surface pottery on mound.
el Musalla, Kh.	G.	VIII. 116 124	<i>see</i> Balâs, Kh.
el Musâyât, Kh.	RA.	X. 172 149	Foundations, vault.
el Musajjid, Kh.	He.	XII. 136 116	Traces of ruined settlement.
Musheibish, Kh.	N.	VII. 194 187	Heaps of stones, cisterns.
Musheirifa	Ba.	110 030	Ruins of small fortified town with church and monastery, rock-cut chambers.
Musheirifa, Kh.	A.	II. 160 276	<i>see</i> et Tabayiq, Kh.
el Musheirifa, Kh.	Nt.	IV. 170 239	Square enclosure, tower, chambers.
el Musheirifa, Kh.	Jm.	IX. 145 132	Foundations, walls, caves.
el Mushta, Kh.	A.	III. 180 251	Heaps of stones, cisterns.
Musmâr, Kh.	Re.	VI. 151 162	Ruins of house, to south foundations of enclosure, rock-cut cisterns.
el Mutaiyan, Kh.	N.	VI. 156 171	Ruined walls.
el Mutasallim, Tell (Megiddo)	J.	IV. 168 221	Artificial mound partly excavated. Remains of walls, gate, buildings.
Mutâyl edh Dhîb	N.	VII. 196 164	Traces of ruins, scattered stones, caves, circular enclosure.
el Mutilla, Kh.	J.	V. 189 203	Traces of settlement, rock-cut cistern.
el Muwajih, Tell	H.	IV. 165 234	<i>see</i> er Rish, Tell.
Muweilih, Kh.	Ba.	XV. 127 078	Traces of settlement, rubble cisterns, scattered stones.
en Na'am, Tell	T.	V. 198 236	Artificial mound, heaps of stones and traces of foundations.
Nabhân, Kh.	Jm.	IX. 155 129	Ruined walls, fragments of columns, lintel, presses, caves.
en Nabi 'Arafât	Re.	VIII. 127 138	<i>see</i> Ghayâda, Kh.
en Nabi Bâlus, Kh.	He.	IX. 148 125	Ruined buildings, foundations, pool. To south remains of church, Maqâm with dome and vaults.
en Nabi Danyâl	Jm.	IX. 164 122	<i>see</i> el Jami', Kh.
en Nabi Haidar	A.	III. 185 262	Traces of dry stone wall round summit, presses, surface pottery.
en Nabi Hatta, Kh.	N.	VI. 147 170	<i>see</i> Kafr Hatta, Kh.
en Nabi Hûj	G.	XI. 115 102	<i>see</i> Hûj, Kh.

Name of Site	Sub-District	Map Reference	Description
en Nabi Ilyas	TK.	VI. 152 177	Ruined walls, wells, cisterns, tomb with Arabic inscriptions.
en Nabi Kifl	Re.	IX. 143 157	Fallen masonry, two wells, columns, capitals and bases.
en Nabi Lâwin	J.	VI. 167 183	Foundations of walls, columns and architectural fragments at the Maqâm.
en Nabi Mûsa	Jm.	X. 191 133	Maqâm with inscriptions.
en Nabi Samwil	Jm.	IX. 167 138	Mosque (originally Crusaders' church). Remains of fortified enclosure, rock-cut reservoirs, cisterns, foundations, tombs.
en Nabi Shu'eib	T.	III. 192 245	Ruined Maqâm.
en Nabi Thâri	Re.	VI. 143 164	Maqâm en Nabi Thâri, foundations of buildings, heaps of stones, reservoirs, vaulted tomb.
en Nabi 'Uzeir	N.	VII. 177 174	Maqâm with inscriptions.
en Nabi Yamîn	TK.	VI. 145 176	Vaulted Maqâm with medieval masonry and Arabic inscriptions.
en Nabi Yaqln	He.	XIII. 165 101	Maqâm with Arabic inscriptions.
Nablus	N.	VII. 175 181	Roman, Byzantine and medieval remains in town, springs, aqueducts. 'Ein Qaryûn, tombs. <i>See also</i> Huẓn Ya'qûb.
(‘Ein Qaryûn, Ras el ‘Ein)			
en Nabra, Kh.	S.	III. 198 268	Scattered masonry and column fragments.
en Nabratein, Kh.	S.	III. 198 268	Remains of synagogue, architectural fragments, carved stones.
Nada, Kh.	Jm.	IX. 165 139	<i>see</i> el ‘Adas, Kh.
Naghnaghiya	H.	IV. 165 223	Artificial mound, foundations, caves.
(el Aqbiya, Tell)			
Nahalin, Kh.	J.	IV. 159 203	Traces of settlement, small mound with tombs and surface pottery on the shore.
Nahariya	A.	II. 159 268	Part of Roman road. To north rock-cut steps and presses.
Nahf	A.	III. 180 260	Remains of medieval building and architectural fragments in village. Traces of mausoleum with sacrophagus, caves, tombs, rock-cuttings, mosaic.
en Nahl, Kh.	Jm.	IX. 168 131	Ruined house.
en Nahl, Tell	H.	II. 157 245	Artificial mound, surface pottery and stones.
en Nahm, Kh.	J.	V. 180 201	<i>see</i> ‘Anâhum, Kh.
en Nahr (et Tell)	A.	II. 164 268	Artificial mound beneath village with traces of ancient remains.
Nâ‘ima	S.	I. 206 288	Small basalt mounds (artificial?), covered by Moslem graves.
en Nâ‘ima, Kh. Tell	S.	I. 206 287	Artificial mound, traces of causeway. To west ancient road.
Najd, Kh.	G.	XI. 112 105	Rubble foundations, vaulted substructures, cisterns, reservoirs, tombs.
en Najlla, Tell	Ba.	XII. 127 101	Artificial mound, with traces of town wall and foundations of square building. Remains of dam in valley.
en Najjâr, Kh.	J.	V. 178 206	Tombs cut in the rock.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
en Najjār, Kh.	Jm.	IX. 167 125	Remains of buildings, rubble wall, terrace walls, rock-cuttings and tomb, mosaic pavement.
en Najjāra, Kh.	N.	VI. 151 170	Ruined buildings and houses, olive press, cisterns and tombs.
en Najma, Kh.	N.	VII. 183 167	Ruined walls.
en Nakhābir	Ba.	XI. 098 093	Gullies with prehistoric worked flints.
en Nāmūs	G.	VIII. 116 123	Surface pottery, rubble foundations.
(en Nawāmīs)			
en Nāmūs, Kh.	G.	XI. 101 098	Ruined cisterns, surface pottery, marble fragments.
en Nāmūs, Kh.	G.	XI. 118 102	Ruined buildings, vaulted rooms on mound, cisterns, marble column shaft, rubble pool.
Napoleon, Tell	Ja.	VI. 132 167	<i>see</i> el Jarisha, Tell.
en Nāqa, Kh.	He.	XII. 146 107	Remains of three enclosures, foundations of houses, caves.
en Naqaqr, Kh.	A.	III. 185 259	Heaps of stones, foundations, shafts of columns, rock-cut tombs, olive-press.
Naqb el 'Arāyis, Tell	N.	VII. 190 182	Artificial mound, remains of rough stone building, surface pottery.
Naqb el Ghārib	Ba.	130 020	Ruined rectangular building of rough masonry.
Naqb el Mahamla	Ba.	140 010	Old road, buildings of square and rough masonry. 2 hrs. to north-west rough stone buildings.
Naqb Zuweira	Ba.	XVI. 182 062	Small ruined tower.
en Nāqiya	G.	XI. 102 109	Surface pottery on high sand dunes, marble fragments.
Nāqūra, Kh.	Jm.	IX. 150 129	Traces of foundations, rock-cuttings, cistern.
Nasar, Kh. Wadi	N.	VII. 182 166	Traces of ruins.
en Nasāra, Kh.	He.	XII. 159 106	Ruined buildings, foundations, vaults, cisterns.
en Nasba, Tell	RA.	X. 171 143	Artificial mound with remains of town wall and gate, rock-tombs in vicinity.
Nashā, Kh.	N.	VI. 148 169	<i>see</i> ed Deir, Kh.
Nashā, Kh.	TK.	VI. 150 181	Traces of settlement, cisterns.
en Nāsira, Tell	G.	XI. 095 096	Traces of settlement, surface pottery and marble fragments.
Nasus, Kh.	H.	IV. 150 230	Surface pottery and building debris. Rock-cuttings and tombs.
Nathanya	TK.	VI. 136 193	Roman necropolis with rock-cut tombs and sarcophagi.
en Natif	H.	IV. 145 236	<i>see</i> Fallāh, Magharat Wadi.
Natif, Kh.	A.	III. 186 249	Foundations, heaps of stones, cisterns, rock-cut tomb.
en Natsh, Kh.	Jm.	X. 171 120	Ruined walls.
Na'ura	Nt.	V. 187 225	Traces of settlement beneath village, surface pottery, foundations and broken sarcophagi to south, cemetery.
en Nawāmīs	G.	VIII. 116 123	<i>see</i> en Nāmūs.

Name of Site	Sub-District	Map Reference	Description
Nazareth	Nt.	V. 178 235	Remains of medieval and Byzantine buildings. Rock-cut tombs, cisterns, vaulted tunnel, spring.
en Nazla, Kh.	H.	IV. 146 221	Low mound with foundation and stones, tomb, caves.
en Nazla, Kh.	J.	VII. 174 189	Traces of settlement.
Nazlat 'Isa (Nazlat el Ma'asfi)	TK.	IV. 155 202	Cisterns, tombs.
Nein	Nt.	V. 183 226	Village on ancient site, foundations, oil press, sarcophagus, rock-cut tombs.
Neiraba, Kh.	TK.	VI. 159 191	Remains of settlement with surrounding wall on hill. Caves, cisterns, tombs.
Nes Ziona	Re.	IX. 131 148	Rubble foundations, surface pottery and tombs north-west of settlement.
Neve Sha'anana	H.	II. 152 243	see Haifa.
Ni'ana	Re.	IX. 138 142	see el Khirba.
Nib, Kh.	N.	VII. 175 186	Traces of ruins.
Niha, Kh.	S.	I. 203 295	Foundations of walls, scattered stones, surface pottery.
Ni'ilya	G.	XI. 109 117	Mosque to south of village with inscriptions, drinking fountain and architectural fragments, tombs.
Nijm, Kh.	Jm.	IX. 163 137	Ruins of watch-tower, rock-cut cistern.
Nijmat el Haudali, Kh. (Fa'ûah, Kh.)	RA.	IX. 155 145	Ruined square buildings, orientated: ruined walls, arch, cisterns, rock-cuttings.
Nijmat es Subh, Kh.	S.	III. 205 269	Extensive site, foundations, columns, walls, cisterns.
Ni'lân, Kh.	RA.	IX. 164 152	Barrel vaulted rooms, ruined building (el Kanisa). To south rock-cut chamber, tomb caves, cisterns.
Nimrin	T.	III. 190 245	Cisterns, olive-presses, caves, traces of tombs, wine-press cut in the rock.
Nimrûd, Tell	Bn.	V. 202 210	Two mounds, traces of walls, surface pottery.
Nina, Kh.	Re.	IX. 134 136	Foundations, surface pottery and rubble, cisterns.
Nisya, Kh.	RA.	X. 173 145	Traces of ruins.
en Nitla, Tulûl (Ghalghala, Birkat Jiljuliya)	Jm.	X. 196 140	Rectangular pool, foundations, fallen sundried bricks.
en Niyâs, Rujm.	He.	XII. 156 087	see el Madfa', Rujm.
en Niyâta, Kh.	Jm.	IX. 151 127	Foundations, door posts, cisterns, olive presses and mills, plastered tanks.
Nu'eila, Kh.	A.	III. 173 274	see Din'ila, Kh.
Nûh, Kh.	Jm.	IX. 155 125	see Bint Nûh, Kh.
Nujeimiya, Kh.	A.	III. 185 251	Traces of buildings; cisterns, scattered stones by spring.
en Nuqeid, Tell	G.	XI. 092 097	see es Sanam, Tell.
en Nuqta, Magharat	Re.	IX. 147 157	Natural cave with deposits containing potsherds and worked flints.
Nuris	J.	V. 184 216	Rock-cut caves, sarcophagus, ruins of ancient building.
en Nûriya, Magharat	A.	III. 189 264	Wine press.
Nusib 'Uweishira	Jm.	X. 190 140	Traces of ruins.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Nuseibah, Kh.	S.	III. 194 271	Fallen walls, foundations, cisterns.
en Nuseirât	Ba.	XI. 094 091	Traces of settlement, ruined cisterns, surface pottery and marble fragments.
Nusf Jubeil	N.	VII. 171 188	Foundations. To north-west arch and tunnel at spring.
en Nusrâni, Kh.	He.	XII. 142 096	Traces of ruined buildings, cisterns, olive-press, caves.
en Nuweiriya, Kh.	S.	III. 198 258	Heaps of drafted masonry, rock-cut wall, rock-cut wine presses.
(esh Sheikh er Rumi)			
en Nuweitif, Kh.	He.	IX. 144 121	Traces of foundations and of an ancient road, rock-cut cisterns, caves.
Peqi'in	A.	III. 182 264	<i>see</i> el Bugei'a.
Qa' Hujjâr	Jm.	XIII. 174 116	Square dry stone enclosure, surface pottery. Cisterns to east (Harâib el Bîd).
Qa' el Kharâba	G.	XI. 083 080	Rubble cisterns, surface sherds.
Qa' Wadi es Sana'	He.	IX. 153 124	<i>see</i> Shallâlat Umm el 'Umdân.
Qabbâ'a	S.	III. 201 267	Caves, wells, cisterns, tombs, rock-cuttings.
Qabr Dafur	Ja.	IX. 133 156	Bronze Age remains.
Qabr en Nusrâni	N.	VII. 176 182	Large dry stone buildings, walls, terraces, enclosures, rock-cut tombs.
el Qabra, Kh.	A.	III. 176 258	Ruined walls, cut stones, cisterns, tombs.
el Qabra, Kh.	He.	XII. 155 108	Foundations, cisterns.
el Qabu	Jm.	IX. 161 126	Remains of a vaulted church, vaulted tank and conduit.
el Qabu	G.	XI. 105 117	Foundations, surface pottery and marble fragments, well.
el Qabu, Kh.	A.	III. 177 257	Ruined walls, cisterns, remains of vaults and apsidal building.
el Qâbûba, Kh.	N.	VI. 166 186	Ruined walls and foundations, circular pool, cisterns, caves.
el Qadah	S.	III. 203 269	<i>see</i> Waqqâs, Kh.
Qadas, Kh.	S.	III. 200 280	Artificial mound, remains of temple, built tombs, foundations, architectural fragments, ornamented sacrophagi, rock-cut tombs.
el Qâdi, Kh.	Ba.	XI. 119 092	Cisterns, column fragments, capitals, surface pottery and marble fragments, press stones.
el Qâdi, Kh.	Ba.	XIV. 097 073	<i>see</i> Umm 'Ajwa.
el Qâdi, Tell	S.	I. 211 295	Artificial mound, traces of surrounding wall.
el Qahwa, Tell	A.	II. 164 268	<i>see</i> en Nahr.
Qalandiya	Jm.	IX. 170 141	Remains of building with paved floors, tanks and niches, rock-cut tombs, pool to north.
Qalansuwa	TK.	VI. 148 188	Remains of Crusaders' tower (el Burj) and two-storeyed vaulted building. Domed mausoleum to west, and grave with Arabic inscription.
Qalâsûn	RA.	X. 182 159	Ruined walls of buildings, two streets, rock-cut caves, cisterns.
Qal'at el Burak	Jm.	IX. 166 122	Square castle with corner towers.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Qal'at el Burj	He.	XII. 141 095	<i>see</i> el Burj, Kh.
Qal'at el Fanash	G.	XII. 124 117	<i>see</i> Karātiya.
Qal'at el Hiss	T.	III. 212 242	Ruins of walled town, streets, remains of gate, basilica and other buildings, street, vaults, cisterns, architectural fragments, stone pipe aqueduct, ancient road, tombs.
Qal'at Hunin	S.	I. 201 292	Crusaders' castle, rock-cut fosse, ruined mosque.
Qal'at Ibn Ma'an	T.	III. 197 248	Fortress in cliff with walls, vaults, caves, stair cases.
Qal'at Jiddin	A.	III. 171 266	Castle, rock-cuttings and fosse, foundations of earlier walls, mosaic fragments.
Qal'at el Qumeiqama	N.	VI. 161 171	Watch-tower.
Qal'at el Qurein (Montfort)	A.	III. 171 272	Ruined Crusaders' castle, vaulted building and remains of dam in Wadi el Qurn. Tombs.
Qal'at Ras el 'Ein	Re.	VI. 144 168	<i>see</i> Ras el 'Ein.
Qal'at esh Shūna	S.	III. 196 257	<i>see</i> esh Shūna, Kh.
Qal'at Tantūra	Re.	IX. 152 145	<i>see</i> el Burj.
Qal'at el Tufāniya	A.	III. 174 262	<i>see</i> el Tufāniya, Kh.
Qallus, Kh.	He.	IX. 137 125	Foundations, caves, cisterns, scattered stones.
Qalūnya	Jm.	IX. 166 134	Ruins of vaulted building.
Qamha, Kh.	He.	XII. 140 119	Ruined houses, foundations, cisterns, columbarium.
Qamsa, Kh.	G.	XI. 114 105	Rubble cisterns, well, surface pottery.
Qana, Kh.	A.	III. 179 248	Artificial plateau, traces of walls, cisterns, surface pottery.
Qanāt Bint el Kāfir	Re.	IX. 137 149 to 142 149	Traces of aqueduct.
Qanāt el Manyal	Jm.	X. 190 150	Ruined aqueduct.
Qanāt Musa	Jm.	X. 188 148	Aqueducts.
Qanāt Qasr el Banāt	He.	XII. 141 113-4	Aqueducts between Qasr el Banāt and Bir el Mafahim.
Qanāt Umm Heil	Bn.	V. 200 215	Aqueduct, Roman road, tombs, building.
el Qandul, Rujm	He.	XII. 143 115	<i>see</i> Shu'b eth Thaur, Rujm.
el Qantara	Bn.	V. 196 213	Traces of foundations, bridge of aqueduct; <i>see also</i> el Jisr, Tell.
el Qantūr, Tell	Ja.	VI. 131 174	<i>see</i> Maknishi.
Qanya, Kh.	He.	XII. 147 119	Foundations, ruined walls, caves, cisterns.
Qa'qa'iya	T.	III. 201 242	<i>see</i> Qasr Bint el Malik, Kh.
Qāqūn	TK.	VI. 150 196	Remains of tower with vaults, architectural fragments in village, two wells, inscription at mosque.
Qāra, Kh.	Nt.	V. 185 222	Ruined walls, tombs, cisterns.
Qaraja, Kh.	He.	XII. 142 119	Foundations, caves, cisterns cut in the rock.
Qarāwa el Mas'ūdi	N.	VII. 197 172	Ruins, cisterns, tombs.

Name of Site	Sub-District	Map Reference	Description
Qarāwat Bani Hassan	N.	VI. 169 171	Ruined mosque (Jami' el 'Umari), masonry pool with pilasters, ruined tower (el Burj). To west vaulted building (Badd Bunduq). To south watch towers (Qasr Abu Jāliya, et Tirbi'a and others). Ruins of buildings, cisterns, presses, tombs, quarries.
Qarhata, Kh.	A.	III. 179 270	Remains of tower with drafted masonry, oil press, rock-cut tombs, cisterns.
el Qariq, Kh.	N.	VII. 180 165	Ruined walls, piles of stones, rock-cut cisterns.
Qarn Hattin	T.	III. 193 245	<i>see</i> Madyan, Kh.
Qarn Sartaba	N.	VII. 194 167	Ruins of fortress on hill top, aqueduct, cisterns, road, well, quarry, caves in east slope.
Qarqaf, Kh.	TK.	VI. 164 186	Foundations, scattered stones on hill.
Qarqafa, Kh.	N.	VII. 180 167	Traces of settlement.
Qarqafa, Kh.	G.	VIII. 124 122	<i>see</i> Ahmad el Qarqafawi.
Qarqara, Kh.	Ba.	XII. 132 105	Traces of foundations, scattered stones, cisterns cut in the rock and built.
Qarqara, Kh.	He.	XII. 138 108	Foundations, heaps of stones.
Qarrit, Kh.	Jm.	X. 177 130	<i>see</i> el Kharāyib, Kh.
Qaryat Hajja	N.	VI. 163 179	Mosque and minaret with ancient material and inscriptions.
Qaryat el 'Inab (Abu Ghosh)	Jm.	IX. 160 135	Crusaders' church, vaults, cisterns, rock-cut tombs.
Qaryat Jit	N.	VI. 166 180	Traces of ancient buildings, well, surface pottery, 'Umari mosque.
Qaryat Sa'ida	Jm.	IX. 162 129	<i>see</i> Su'eida, Kh.
el Qaryatein, Kh.	He.	XII. 162 084	Ruins of buildings, broken column shaft, cisterns, caves.
el Qas'a	Re.	IX. 144 141	Rock-cut tombs, circular vat.
el Qas'a, Kh.	He.	XII. 146 102	Caves, foundations, cisterns, heaps of stones, ancient road.
el Qasab, Kh.	H.	IV. 159 218	Traces of ruined buildings, heaps of stones.
el Qasab, Tell	S.	III. 203 204	Artificial mound, surface basalt stones, pottery and flints, built well to west.
el Qasaba, Kh.	Ba.	XII. 128 101	<i>see</i> Kassāba, Kh.
el Qasr	N.	VII. 187 194	Remains of built tomb, oil press, rock-cuttings, cisterns.
el Qasr, Kh. (Sārin, Kh.)	N.	VII. 176 179	Foundations of walls, ruined vaults, built spring, canal and basin, rock-cut tombs.
el Qasr, Kh.	Re.	VI. 147 161	Remains of tower, cistern cut in rock.
el Qasr, Kh.	Jm.	IX. 155 136	Foundations, rock-cut cistern, vault, cave.
el Qasr, Kh.	He.	XII. 143 105	Ruined fort with glacis, cistern, caves.
el Qasr, Kh.	He.	XIII. 198 160	Ruined buildings, foundations, cisterns.
Qasr el 'Abd	Ba.	160 990	Ruined fort, Nabataean surface pottery.
Qasr Abu Jāliya	N.	VI. 160 171	<i>see</i> Qarāwat Bani Hassan.
Qasr 'Ali	Jm.	X. 176 135	Foundations, cisterns.
Qasr 'Antar	Jm.	XIII. 172 115	Foundations, heaps of stones.
Qasr el 'Areija	Jm.	XIII. 187 093	Tower, aqueduct, rock-cut tombs.

Name of Site	Sub-District	Map Reference	Description
Qasr 'Atra	S.	III. 209 268	Remains of Crusaders' castle on artificial mound, rock-cut tombs.
Qasr el Badawiya	Jm.	IX. 170 131	Ruined vaulted building.
Qasr Bint el Malik, Kh. (Qa'qa'iya)	T.	III. 201 242	Ruined tower, traces of walls, pool, caves, on slopes, reservoir.
Qasr el Bustân (Qasr el Khadr)	Jm.	IX. 168 134	Watch-tower.
Qasr 'Ein Kharûf	Ba.	170 010	Ruined fort, pottery on hill slopes.
Qasr 'Ein Shari'a	J.	IV. 163 212	see Qasr Sharayi.
Qasr 'Ein Yarqa	Ba.	150 030	see 'Ein Yarqa.
Qasr Fakkia	H.	IV. 153 217	Traces of ruins.
Qasr Hajla	Jm.	X. 198 136	see Deir Hajla.
Qasr el Harâmiya	N.	VI. 157 175	Remains of watch tower; to north-east, rock-cut press, rough towers to south and east, quarry.
Qasr Islayin	He.	XII. 160 110	see 'Ein edh Dhirwa.
Qasr el Jubeiniya	Ba.	XVI. 173 048	Square fort with towers.
Qasr el Jubeiniya	Ba.	XVI. 179 070	Fort with corner towers, arched doorways, three reservoirs; rectangular building to east, cemeteries in vicinity, to west dam in Wadi Dhâna.
Qasr el Khadr	Jm.	IX. 168 134	see Qasr el Bustân.
Qasr Khallat el Mardun	He.	XII. 147 091	see Bir el Qasr, Rujûm.
Qasr el Mahalla	Ba.	150 000	Ruined square building, surface pottery.
Qasr Mabrun	J.	V. 174 202	Ruined beacon station.
Qasr Sabbah	N.	VI. 160 170	Watch-tower.
Qasr Sharayi	J.	IV. 163 212	Remains of buildings, well.
Qasr esh Sheikh Ghazâl (el Mukhabbi)	N.	VII. 189 196	Ruins of fallen tower beside the Roman road.
Qasr esh Sheikh Rabs	J.	VII. 186 199	Ruined tower.
Qasr es Siq	Ba.	150 000	Building of roughly squared masonry, cisterns roofed on arches, cairns.
Qasr es Sirr	Ba.	XV. 149 034	see es Sirr, Kh.
Qasr Thughrat Rusheidfiya	Jm.	XIII. 173 108	Heaps of flints.
Qasr Umm Baghiq	Ba.	XVI. 184 068	Ruins of fort with corner towers, reservoirs, aqueduct.
Qasr Umm el Leimun	Jm.	XIII. 171 115	Vaults, foundations, rock cut cisterns, caves.
Qasr 'Uweis	Jm.	IX. 169 127	Watch-tower, ruined walls, fragment of mosaic pavement, rock-cut tombs and presses.
Qasr el Yahûd (Mar Yuhanna)	Jm.	X. 201 138	Modern monastery and church on ancient foundations.
Qasr es Zuweira	Ba.	XVI. 183 062	Castle and enclosure, two reservoirs, masonry dams.
el Qasrein	He.	XIII. 167 103	Ruined towers, rough stone masonry, cave, cliff shelter.
el Qassis, Kh.	Jm.	X. 174 124	see Biyar el Qasala.
el Qassis, Tell	H.	IV. 161 232	Surface pottery on mound.
Qasta, Kh.	T.	V. 159 237	Heaps of stones, cisterns, caves, tombs.
Qastina, Kh.	N.	VI. 165 178	Ruins of small settlement.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Qaswal, Kh. (et Teira, Kh.)	RA.	X. 180 149	Watch-tower, heaps of stones.
Qasyûn, Kh.	S.	III. 200 272	Remains of temple and other buildings, ruined pool, cisterns, olive-press, rock-cut tombs, columns, bases, sculptured fragments.
Qatana, Kh.	S.	III. 204 266	Ruined Arab houses.
el Qatifa, Tell	G.	XI. 084 090	Artificial mound, brick foundations, surface sherds, traces of necropolis.
Qatlâna, Kh.	Re.	IX. 140 139	Cisterns cut in the rock, scattered stones, surface pottery.
Qatra	Re.	VIII. 129 137	Artificial mound (es Sakhra), rubble foundations, traces of tessellated floors.
el Qatt, Kh.	He.	XII. 160 113	Heaps of stones, foundations, cisterns.
Qa'un, Kh.	N.	V. 195 201	Two ruins east and south-west of spring; c. 2 kms. south-west traces of building.
el Qauqa'a, Tell	Re.	IX. 153 138	Artificial mound with traces of walls.
el Qazâz, Kh.	A.	III. 177 257	see Tirat el Qazâz, Kh.
el Qaziya, Tell	N.	VII. 187 182	see Miska, Tell.
el Qazza'i, Tell	J.	VII. 175 196	Mound.
Qeduma	G.	VIII. 123 127	see el Biyar, Kh.
Qeila, Kh.	He.	XII. 150 113	Ruined walls, foundations, cisterns rock-cut tombs, rock-cut presses to south-east.
Qeimûn, Tell	H.	IV. 161 230	Artificial mound, foundations of a square fort and a small chapel, sculptured capitals.
el Qeisaraniya	Jm.	X. 170 122	Traces of ruins, rock-cut tombs.
Qeisariya, Kh.	N.	VI. 157 165	Remains of square building, foundations, cisterns cut in the rock, oil press.
Qeisharun, Kh.	T.	III. 189 241	Ruins of square enclosure, foundations of walls to north, heaps of stones, buried vault, cisterns, tombs.
Qesuma, Kh.	TK.	IV. 147 201	Traces of ruins.
Qeiyâfa, Kh.	He.	IX. 146 123	Ruined enclosure with square tower.
el Qeiyûma, Kh.	S.	III. 194 266	Remains of buildings, column, rock-cut cisterns, tombs, press.
Qilâ' er Rahîb	A.	III. 180 276	Fort, bell-shaped cistern, rock-cut caves and remains of vaults, column.
Qilqis, Kh.	He.	XII. 159 100	Walls, cisterns, wine press with mosaic, rock-cut tombs, columbarium.
el Qilt, Wadi	Jm.	X. 187 190 to 138 139	Aqueducts, cave with Greek inscriptions: see also Deir Mar Jiryis and Tahûnat el Qilt.
Qimas, Kh.	G.	XI. 117 116	Scattered stones, cisterns, ruined pool.
Qira	N.	VI. 166 170	Caves and tombs.
Qira wa Qâmûn	H.	IV. 160 225	Mound with ruined buildings, caves, tombs, cisterns.
Qisâriya	H.	IV. 140 212	see Caesarea.
el Qishâni	G.	XI. 097 104	Traces of wall, well, surface pottery and marble fragments, tombs.
el Qitâf, Tell	Bn.	V. 203 205	Two artificial mounds (including small mound 100 m. to north-east).
Qit'ât es Sitt, Tell	S.	I. 205 294	Dry stone enclosures on natural hill.

Name of Site	Sub-District	Map Reference	Description
el Qubeiba	Jm.	IX. 163 139	Ruined Crusaders' church.
el Qubeiba	He.	XII. 136 109	Caves, rock-cuttings, presses, inscription on rock ledge by side of road (Roman).
el Qubâr, Tell	N.	VII. 199 196	Artificial mound.
Qubâr Bani Israil	Jm.	X. 175 139	Prehistoric dry stone structures.
Qubâr el Walsaida	Ba.	XI. 101 083	Iron Age surface pottery over extensive area.
Qudâdi, Tell	Ja.	VI. 129 168	see esb Shûna.
Qula	Re.	VI. 146 160	Remains of medieval buildings in village.
Quleidiya, Kh.	He.	IX. 146 123	Remains of rectangular buildings, foundations, cisterns.
Qulu' Shiriya	S.	III. 190 267	Traces of tower built on natural rock.
Qumiya, Kh. (Geva')	Ba.	V. 187 219	Ruins of rectangular building, foundations, caves, rock-cut cisterns, architectural fragments and bossed stones.
Qummal, Kh.	T.	V. 194 230	Traces of settlement.
el Qumqum, Kh.	TK.	VI. 160 187	Heaps of stones.
Qumrân, Kh.	Jm.	X. 194 128	Remains of buildings, city wall, plastered tank, boundary wall, graves.
el Quneitira, Kh.	T.	III. 199 246	Ruined houses, foundations, heaps of stones, caves.
el Quneitira, Tell	Ba.	XII. 128 105	Artificial mound, surface pottery.
el Qûqa, Kh.	He.	XII. 143 111	Foundations, ruined walls, caves, cisterns, heaps of masonry.
el Qûr, Kh.	T.	III. 200 254	Ruined walls, scattered stones, doorposts, column shafts, cornice stones.
el Qureina, Kh. (Bir Nâzir, Kh., ez Za'tar, Kh.)	RA.	IX. 161 145	Rock-cut press and ancient road, cisterns, ruined walls, heaps of masonry.
Qureish, Kh.	N.	VI. 147 172	Foundations, rock-cut pool, cisterns, caves.
Qurma, Kh.	He.	XII. 148 116	Ruined buildings, fallen masonry, press, column shafts, rock-cut tombs, wells, ancient road, caves.
Qusabiya	H.	IV. 157 215	Traces of ruins.
el Qûsatîn, Kh.	He.	XII. 146 105	Foundations of buildings, cisterns, walls, surface pottery.
Quseiqis, Kh.	A.	III. 175 274	Foundations, heaps of stones, wine-press, cisterns cut in the rock.
el Quseir, Kh.	A.	III. 174 276	Ruins of fort, cisterns, sarcophagi.
el Quseir, Kh. (el Muntar)	N.	VI. 154 174	Ruined walls, rock-cut cistern.
el Quseir, Kh.	Jm.	IX. 165 124	Remains of buildings, cisterns, enclosure wall, ruins of aqueduct, rock-cut tombs.
Quseir, Kh.	Jm.	XIII. 180 109	Traces of ruins, rock-cut tombs.
Quahuqulliya, Kh.	He.	XII. 140 109	Foundations.
Qûsîn es Sahl (Sahl Qûsîn)	N.	VI. 166 186	Remains of watch-tower in enclosure, cistern, press; see also el Baubariya, Kh.
Qusqas	H.	IV. 164 236	Heaps of stones, rock-cut tombs.
Qusra	N.	VII. 181 166	Foundations, heaps of stones.
Qusûr, Kh.	Jm.	IX. 164 129	Foundations.
Qusûr el Muhâfaza	Ba.	XV. 135 071	Remains of flintstone tower, foundations of houses.
Quteit, Rujm	He.	XII. 141 091	Foundations, heaps of stones.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
el Qutn, Kh.	He.	XII. 145 115	<i>see</i> Umm el Qutn, Kh.
Qutshân, Kh.	Ba.	XI. 098 091	Traces of foundations, mosaics, cisterns, surface pottery and flints.
(Sha'arta, Kh.)			
Qutteina, Kh.	H.	IV. 153 226	Ruined walls of foundations, masonry well to south east.
er Rahadiya, Kh.	T.	III. 195 252	Rock-cut presses, cisterns, tombs, fallen masonry.
er Rabâ'i	G.	VIII. 124 131	Foundations, rubble cistern, remains of rubble reservoirs, surface pottery.
Rabbi Kahna	T.	III. 202 242	Rock-cut tomb.
Rabbis, Kh.	S.	III. 193 268	Foundations of walls, heaps of rough stones, surface pottery.
Rabla, Kh.	Jm.	IX. 153 129	Square fort with tower, to west olive press and rock-cut cisterns, to south rock-cut wine press.
Râbin, Kh.	J.	VII. 186 200	Rough ground covering ruins of buildings. Cisterns, caves, surface pottery.
er Rabiya, Kh.	He.	XII. 153 093	Foundations, fallen masonry, rough columns, cisterns.
Rabûd, Kh.	He.	XII. 151 093	Ruined walls, foundations of buildings, cisterns, tomb-cave.
Rachel's Tomb	Jm.	IX. 169 125	Domed chamber, section of stone aqueduct in vicinity.
er Radgha, Tell (er Ridgha, Tell)	N.	V. 200 201	Artificial mound, traces of stone walls, remains of basalt presses; to west Roman cemetery, masonry doorway and foundations, masonry near spring; to north small artificial mound.
Rafah, Kh.	G.	XIV. 078 079	Brick foundations, architectural fragments, ancient cemetery, column shafts and capitals.
Rafah, Tell	G.	XI. 076 082	Artificial mound, brick wall, surface sherds.
Râfât	N.	VI. 154 165	Foundations of building with mosaic and stone pavements, tombs, cisterns.
Râfât	Re.	IX. 146 131	Traces of ruins, cisterns, wine presses, pillar shafts, maqam.
Râfât	Jm.	IX. 168 142	Rock-cut tombs, traces of ruins.
Râfât, Kh.	He.	XII. 156 085	Ruined mosque with ancient materials, ruined buildings, wells, foundations, rock-cut tombs.
Rafeidiya, Kh.	Jm.	IX. 160 137	Foundations of buildings and tower, rock cuttings, cisterns, press, caves.
Rafi', Kh.	He.	XII. 143 115	Cisterns, heaps of stones.
er Râfid, Kh.	RA.	VII. 177 162	Remains of tower, rock-cut tombs, cisterns, ancient road.
Rafidiya	N.	VII. 172 181	Remains of church with three apses, medieval buildings in village, cross vaulted chamber (Badd Mas'ud el As'ad), press, grotto.
er Raghabini, Kh.	Jm.	X. 177 129	Square foundations, cisterns, hewn stones.
Rakhasun, Kh.	A.	III. 185 267	Extensive ruins of buildings, walls, cisterns, tombs, wine and oil-presses.

Name of Site	Sub-District	Map Reference	Description
er Ram	Jm.	X. 172 140	Remains of ancient buildings, walls, cisterns, quarries.
er Ram, Kh. (Khan er Ram)	Jm.	X. 171 140	Ruins of khan with vaults and rock-cisterns.
er Rama (el 'Anâqîr, Kh.)	A.	III. 185 200	Architectural fragments in village; to south and south west remains of buildings, foundations, oil-press, column fragments, bases, capitals, door posts, tombs.
er Rama Kh.	J.	VI. 166 196	Foundations of buildings, cisterns.
Ramallah	RA.	IX. 169 164	Remains of Crusader building (el Burj) with arched doorway; drafted masonry and column base at el Jami'.
Ramat el 'Amla	He.	XII. 159 107	see ed Duhdah, Kh.
Ramat Gan	Ja.	VI. 133 166	Tombs, remains of tessellated pressing floor.
Ramat el Khalîl (Beit Khalîl er Rahmân, el Khalîl)	He.	XII. 160 107	Rectangular masonry enclosure with remains of church, well, foundations, architectural fragments.
er Ramla	Re.	IX. 138 148	Medieval and Turkish buildings in town and vicinity: inscriptions, reservoir, cisterns, architectural fragments.
Rantis	Re.	IX. 152 159	Foundations of church with apse, cisterns, mosaic pavements, rock-cut tombs; to south-west ancient road.
Rantiya	Ja.	VI. 143 161	Vaults in village (el Baubariya).
Raq's, Kh.	He.	XII. 161 097	Walls, foundations, cisterns, caves.
er Raqadiya, Kh.	Re.	IX. 140 138	Traces of foundations, scattered masonry.
Raqibat el Wazza	Ba.	XI. 096 090	Mosaic pavement, rubble cistern, surface pottery.
Raqubis, Kh.	RA.	IX. 154 140	Ruined walls, fallen dressed stones, cave, rock-cut tombs, olive-press.
er Ras	TK.	VI. 154 194	see Shuweika.
er Ras	TK.	VI. 156 176	see 'Azzûn.
er Ras	TK.	VI. 156 184	Ruins.
er Ras	N.	VI. 160 172	Traces of ruined watch-tower.
er Ras	G.	XI. 113 109	see Sumsum.
er Ras, Kh.	N.	VII. 177 174	Foundations of walls, heaps of fallen masonry, rock-cut cisterns.
er Ras, Kh.	Re.	IX. 143 155	Rubble foundations, surface pottery.
er Ras, Kh. ('Irma, Kh.)	Jm.	IX. 154 129	Fallen masonry and surface pottery on knoll.
er Ras, Kh.	RA.	IX. 159 144	Ruined church with column shafts, capitals, bases, marble chancel and fragments, dressed stones, millstone, cisterns.
er Ras, Kh.	RA.	IX. 169 154	Ruins of watch-tower with fallen stones.
er Ras, Kh.	Ba.	XII. 138 082	Remains of buildings with stone pavement, columns, caves, cisterns, cut stones.
er Ras, Kh.	He.	XII. 146 107	Foundation, heaps of stones, caves, cisterns, columbarium.
er Ras, Tell	N.	VII. 176 179	Traces of rectangular building and fosse.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Ras 'Abbād, Kh. (‘Abbād, Kh.)	A.	III. 180 266	Remains of buildings with door-posts, lintels, heaps of stones, columns, rock-cut tombs, rock-cuttings.
Ras Abu 'Eisha, Kh.	Jm.	IX. 145 129	Ruined walls, column fragments, cisterns, caves.
Ras Abu Haltam	He.	XII. 141 107	Foundations of wall, cisterns.
Ras Abu Humeid	Re.	IX. 139 146	Hill with surface pottery.
Ras Abu Lûqa	TK.	VI. 161 187	Rock-cut tombs on hillside.
Ras Abu Murra	Re.	IX. 147 135	Remains of watch-tower and enclosure.
Ras el Ahmar	S.	III. 194 271	Rock-cuttings, traces of wine press with tessellated floor.
Ras el Alâwi, Kh.	Jm.	IX. 167 134	Cistern, tombs.
Ras el Bayâdir	Jm.	X. 175 138	Traces of ruins.
Ras ed Dar	N.	VII. 174 169	Ruins of square building.
Ras ed Deir	RA.	X. 181 153	see el Manatir.
Ras ed Deir, Kh. (Deir el Fiyya, Kh.)	RA.	VII. 176 161	Ruins of a monastery and chapel, walls, column fragment, cistern, ancient roads on south and west.
Ras ed Dhahr	A.	III. 178 258	see el Kanâyis, Kh.
Ras ed Diyâr, Kh.	N.	VII. 186 178	Foundations of ruined fort, cisterns, rock-cut tombs.
Ras el 'Ein	H.	II. 186 240	Small artificial mound, caves, tombs.
Ras el 'Ein	H.	IV. 146 216	see Miyamas.
Ras el 'Ein	Re.	VI. 144 168	Medieval castle on artificial mound.
Ras el 'Ein	N.	VII. 175 181	see Nablus.
Ras el Jumjuma	He.	XII. 161 111	Cairn of stones.
Ras Kalbân	A.	III. 171 263	Foundations, rock-cuttings, scattered stones.
Ras Kur	TK.	VI. 160 189	Traces of walls, accumulated debris, rock-cut cisterns and tombs on natural mound.
Ras el Ma	H.	IV. 146 216	see Miyamas.
Ras Muhammad	RA.	IX. 165 144	Foundations, columns used as door posts.
Ras en Nâqûra	A.	II. 160 278	Ruins of squared building with towers in corners, cistern, rock-cuttings, tomb.
Ras es Sûq, Kh. (et Tuleil, Kh.)	A.	III. 182 263	Foundations, press, heaps of stones on hill.
Ras et Tahûna	RA.	X. 170 146	Remains of tower.
Ras el Tawîl, Kh.	Jm.	X. 173 138	Heaps of stones, rock-cut wine-press, cisterns, caves.
Ras et Tira, Kh.	N.	VI. 151 174	Ruined walls, cisterns, rock-cut tombs.
Ras et Turûna	RA.	X. 170 156	see Tarafein, Kh.
Ras Wad el Biyâd, Magharat	He.	XII. 140 113	Cave with steps to masonry well.
Ras Wad Jurâba	Ba.	XV. 155 055	Square and circular rough stone buildings, surface pottery, graves, cairns.
Ras ez Zeitûn, Kh.	A.	III. 172 254	Remains of walls, tower(?), heap of earth and stones, rock-cuttings.
er Raseisa	H.	IV. 151 210	Ruined walls.
er Rasm	G.	VIII. 123 122	Traces of rubble foundations, surface pottery, rubble cistern, tesserae.
er Rasm	G.	XI. 089 092	Surface pottery, rubble tesserae and marble chips.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
er Rasm	G.	XI. 097 098	Foundations of Byzantine settlement, scattered building stones, columns, capitals, surface pottery.
er Rasm	G.	XI. 103 101	Surface pottery, rubble, tesserae and marble chips on rising ground.
er Rasm	G.	XI. 109 117	Foundations, Roman tomb, remains of reservoirs, cisterns.
er Rasm	G.	XI. 111 112	Traces of foundations, surface pottery.
er Rasm	G.	VIII. 119 122	<i>see</i> el Biyâr, Kh.
er Rasm, Kh.	He.	IX. 139 121	Foundations, scattered masonry, architectural fragments, surface pottery and tesserae.
er Rasm, Kh. (el Khirba)	G.	XI. 093 093	Foundations, cisterns, surface pottery, rubble and tesserae.
er Rasm, Kh.	G.	XI. 109 109	Remains of masonry, rubble foundations, surface pottery, cisterns.
er Rasm, Kh. (el Hajar, Kh.)	G.	XI. 109 113	Foundations, traces of masonry, remains of rubble reservoirs, surface pottery.
er Rasm, Tell	Ba.	XI. 108 093	<i>see</i> Rasm el Gharbi.
Rasm 'Abd el Hamid	He.	XII. 140 109	<i>see</i> Deir Sa'd.
Rasm 'Amir	He.	XII. 135 103	Traces of ruins.
Rasm el A'raj	He.	XII. 144 116	Ruined building with corner tower.
Rasm Bir Jubârat	Ba.	XII. 133 101	Foundations of block-house.
Rasm Dihna	He.	XII. 144 105	Ruined building and foundations, cisterns.
Rasm el Farsh	G.	VIII. 119 121	Vaulted tombs, rubble foundations and cisterns.
Rasm el Gharbi (Tell er Rasm)	Ba.	XI. 108 093	Two small mounds with rubble cisterns and surface pottery.
Rasm Ghatash, Kh. (Rasm Sandahanna)	He.	XII. 141 111	Traces of ruined buildings.
Rasm el Hamâm, Kh.	He.	XII. 146 106	<i>see</i> el Hamâm, Kh.
Rasm Hatta	G.	XII. 125 113	Traces of foundations, well, capital and fluted column in village.
Rasm Isma'îl	He.	XII. 144 115	<i>see</i> er Rusûm, Kh.
Rasm Jibrin	He.	XII. 139 104	Rock-cut wine press, cisterns, well, scattered stones.
Rasm el Kabîr, Kh.	He.	XII. 145 115	Foundations of two-roomed buildings, fallen walls and stones.
Rasm el Miqsar	Ba/G.	XII 136 092	Traces of buildings, caves.
Rasm Qa'qir	He.	XII. 146 104	Caves cut in the rock, columbarium.
Rasm Sandahanna	He.	XII. 141 111	<i>see</i> Rasm Ghatash, Kh.
Rasm esh Sha'f	G.	VIII. 121 123	Foundations, rubble cisterns, surface pottery.
Rasm Târ Tâni	He.	XII. 132 103	Caves, small stones, fragments of pottery.
Rasm Umm el Jamâjim	He.	XII. 145 108	Ruins of several buildings, foundations, doors, caves, presses with uprights. To south isolated buildings, rock-cut cisterns.
Rasm Umm esh Shabâyah	He.	XII. 141 111	<i>see</i> Hamda, Kh.
Rasm el Wâwi	He.	XII. 146 112	Foundations, cistern.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
er Rawāzin, Kh.	He.	XII. 145 113	Ruined walls, foundations, fallen masonry, cisterns, caves.
Rāya', Kh.	He.	XII. 142 102	Ruined walls, caves, cisterns, door-posts, tombs.
er Ra'yān, Tell	Bn.	V. 199 205	Artificial mound, surface pottery.
Rehovot-Nes Ziona Road	Re.	IX. 132 146	Flint flakes on surface.
er Reina	Nt.	V. 180 237	Roman reservoir and built conduit, rock-cut chamber and shaft tombs.
er Ribba, Kh.	He.	XII. 148 118	Ruined buildings, carved lintels, columns, remains of olive press, ancient road, caves, cisterns.
er Ridān, Tell	G.	XI. 082 088	Artificial mound, brick work and surface pottery, ancient tombs in vicinity.
er Ridgha, Tell	N.	V. 200 201	see er Radgha, Tell.
er Rih, Tell	G.	VIII. 124 131	Foundations, rubble cisterns, surface pottery.
er Rihāniya, Kh.	Bn.	V. 187 215	Foundations rock-cut cemetery, broken sarcophagi, caves.
er Rihya	He.	XII. 157 097	Foundations, caves and cisterns.
er Risa, Kh.	N.	VII. 185 171	Cisterns, caves, door posts.
er Rish, Tell	H.	IV. 165 234	Artificial mound.
Rishpon	Ja.	VI. 134 178	Rock-cut tombs, quarries, caves.
(el Muntar, Kh.)			
er Riyāh, Tell	G.	XI. 096 105	see Abu el Hawa, Tell.
er Rubei'a, Kh.	He.	XIII. 166 112	Walls, ancient road.
Rūbīn, Kh.	RA.	IX. 164 147	Ruins of building with door-posts, cisterns.
Rudeiha, Kh.	Ba.	XV. 152 051	Ruined buildings.
(Umm et Tin, Kh.)			
Rūdīn, Kh.	RA.	X. 180 153	Caves, walls, scattered stones.
Ruheiba, Kh.	Ba.	XIV. 109 049	Ruined Byzantine town, rubble reservoirs, cemeteries, well.
Rūjān, Kh.	N.	VII. 179 172	Ruins.
er Rujm, Kh.	H.	II. 163 247	Foundations of rectangular buildings, traces of surrounding wall.
er Rujām	Jm.	IX. 150 130	Small mound, foundations, scattered stones.
er Rujām, Kh.	RA.	IX. 156 145	Foundations, fallen walls.
(Ibn 'Awwād, Kh.)			
er Rūma, Kh.	Nt.	III. 178 244	Ruins of buildings, fallen masonry, cisterns, sarcophagi, fragments of columns, capital.
er Rumeidi	He.	XII. 159 104	Remains of mosque (Maqām el Arba'in) with vaulted rooms and enclosing wall; rectangular building with ruined vaults (Deir el Arba'in); pool; built tomb with Arabic inscription; press.
Rumeila, Kh.	Jm.	IX. 148 129	Artificial mound partly excavated. Ruined buildings, monastery, rock-cut tombs, cisterns.
(Beith Shemesh, 'Ein Shams)			
Rumeilta, Kh.	G.	VIII. 126 122	Low mound with rubble foundations, masonry well, cisterns, fragments of marble, columns, surface pottery.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Rumiya, Kh.	He.	XII. 135 106	<i>see</i> Haud er Rumiya, Kh.
er Rummāna, Kh.	Jm.	IX. 160 139	Fallen walls, foundations, rock-cut cisterns.
er Rummāna, Kh.	He.	XII. 138 105	Scattered ruins, foundations, cisterns, caves.
er Ruqeish, Tell	G.	XI. 086 091	<i>see</i> Bir er Ruqeish.
Ruqtīya, Kh.	H.	IV. 152 236	Heaps of stones, surface pottery. To east remains of pool and rock-cut tombs. Inscription and carved decoration.
Rua el Limlik	TK.	VI. 161 191	Cisterns, rock-cut tombs, presses, wine floors.
er Ruscim, Kh.	G.	XI. 107 097	Cisterns, heaps of stones, surface pottery.
Ruseisa, Kh.	H.	IV. 147 217	Artificial mound with remains of buildings, rock-cut wine-press and tombs, reservoir, column shafts, mosaic and tile fragments.
er Rush et Tahta, Kh.	He.	XII. 144 097	Ruined walls, enclosures, caves.
er Rushaniya, Kh.	RA.	IX. 159 156	Remains of two towers of dressed masonry, rock-cut cisterns.
Rushmiya, Kh.	H.	II. 150 244	Ruins of a rectangular building with tower, tombs cut in the rock, cisterns.
Rushrash	N.	VI. 169 189	Foundations, cisterns, caves, surface pottery.
er Rusūm, Kh.	G.	XI. 111 097	Heaps of stones, rubble cisterns, surface pottery.
er Rusūm, Kh.	He.	XII. 138 104	Heaps of stones, caves, cisterns.
er Rusūm, Kh. (Raam Isma'il)	He.	XII. 144 115	Ruins of rectangular buildings, cisterns, cave.
Rusūm el Butayir	Ba.	XV. 133 073	<i>see</i> Umm Sarbut.
Ruweihina, Kh.	S.	I. 203 294	Remains of walls, quarries, cupmarks in rock, surface pottery.
Ruweisāt, Kh.	A.	III. 175 269	Foundations, cut stones, cisterns, tomb.
er Ruweisāt, Kh. (Kurūm el Humeid, Kh.)	A.	III. 179 273	Foundations, heaps of stones, oil press with uprights, rock-cut cisterns, pool.
er Ruweisāt, Kh.	Jm.	IX. 165 127	Caves, cisterns, tombs, rock-cut presses.
er Ruweisī, Kh. Tell	A.	III. 181 272	Artificial mound with traces of foundations, scattered stones, fragments of pottery.
er Ruweisūn, Kh.	N.	VII. 171 171	Ruined mosque with Byzantine columns and capitals, vaulted cisterns.
Ruweisūn, Kh.	Re.	IX. 148 145	Ruined walls and foundations, cisterns.
er Ruzz, Kh.	He.	XII. 142 106	Traces of settlement, cisterns.
er Ruzzāza, Kh.	TK.	VI. 149 177	Foundations, heaps of stones, rock-cut cisterns.
es Saba', Kh.	Ba.	XI. 130 072	Traces of foundations and surface pottery.
es Saba', Tell	Ba.	XV. 135 072	Artificial mound with traces of walls; in the valley ruins of dam.
Sabalān	S.	III. 182 268	Rock-cut tombs.
Sabāna, Kh.	T.	III. 195 250	Heaps of stones, foundations, cisterns, terraces.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
es Sa'baniya, Kh. Sabastiya	A. N.	III. 184 264 VI. 169 187	Foundations, heaps of stones (unhewn). Ruins of town, churches and ancient tombs within an area bounded on the south by the railway track, on the west and north by the 300 metre con- tour, on the east by the Burqa-Naqûra track. Rock-cut and built tombs in the vicinity outside that area.
Sabâta, Kh.	J.	VII. 175 191	Heaps of stones.
Sabba	He.	XIII. 184 080	see Masada.
Sabbârin	H.	IV. 153 220	Foundations, well.
Sabbûba, Kh.	N.	VII. 184 167	Foundations of buildings.
Sab'ein, Kh.	J.	V. 181 205	Ruin.
Sabha, Kh.	Jm.	X. 172 128	Cisterns, masonry tomb.
Sabi', Kh.	He.	XII. 148 119	Foundations of square building, cis- terns, heaps of stones.
Sabil Abu Nabbût	Ja.	VI. 127 162	see Jaffa.
Sabil esh Sheikh Kabakba	G.	XI. 113 119	see Abu Fatân, Kh.
Sabir, Kh. Wadi	He.	XII. 139 117	Heaps of stones, foundations.
Sâbiya, Kh.	TK.	VI. 141 177	Foundations, remains of reservoir with tessellated pavement, scattered mason- ry, cisterns.
Sabta	He.	XII. 158 105	Ruins, rock-cut tombs.
es Sa'd, Kh.	T.	III. 190 249	Two hillocks with heaps of unhewn stones, cisterns, door-posts, caves, rock- cut tombs and presses.
ha-Sade	Ba.	V. 195 215	see Birkat el Fakht.
es Sa'di, Kh.	Ba.	XIV. 112 048	Ruined Byzantine town, caves, wells, rubbish heaps, rock-cut troughs.
es Safa, Kh.	He.	XII. 155 110	Foundations, caves, cisterns, heaps of stones.
Safa, Kh.	He.	XII. 159 117	Foundations, rock-cut cisterns, base and shaft of column, marble colonette.
es Safa, Tell	S.	III. 205 270	Heaps of stones, tombs, rock-cuttings, presses.
Safad	S.	III. 197 263	Remains of Crusaders castle and moats; medieval buildings and inscriptions in the town including 'Ein en Naib, Jami' el Ahmar, Khan el Ahmar, Ma- gharat Banât Ya'qûb, esh Sheikh Ni'ma, Zawayat Banât Hamid.
Saffûriya	Nt.	V. 176 240	Artificial mound beneath village, ruined church, castle, Roman theatre and wall. Remains of Byzantine buildings, tombs, sarcophagi, cisterns, aqueduct, walls, mosaics.
es Safi, Tell	He.	IX. 136 134	Artificial mound, traces of Crusaders' castle, walls, tombs, rock-cuttings, cave.
Safiriya, Kh.	J.	V. 181 201	see esh Sheikh Safiriyân, Kh.
es Sâfiya Kh.	He.	IX. 137 124	Foundations, tomb-caves.
Sâfiya, Kh.	He.	XII. 143 114	Cisterns, heaps of stones.

Name of Site	Sub-District	Map Reference	Description
es Safra, Kh.	Re.	IX. 147 136	Ruined walls of buildings, column bases, rock-cut cisterns, oil-press stones.
es Safrīya	Ja.	IX. 136 156	Foundations, square stones, capitals, shafts of columns.
Safsaf	S.	III. 192 268	Ornamented stones built into the doorway of the mosque, broken column, rock-cut graves.
es Safsāfa, Kh.	Nt.	V. 187 228	Foundations of walls, traces of mosaics, oil press, scattered cut stones.
Safta 'Adi, Kh.	H.	II. 166 247	Foundations of walls, heaps of stones, tombs cut in the rock, to north-east built well.
es Saghira, Kh.	He.	IX. 138 124	Foundations of houses, caves, cisterns.
es Saghira, Kh.	He.	IX. 145 125	Ruined walls, rectangular buildings, to south and south-east rock-cut caves.
es Saharij, Kh.	H.	IV. 146 211	Extensive site with scattered masonry, surface pottery and marble fragments, mosaic floors, fragments of sarcophagi, tombs.
es Saharij, Kh. (Bir es Saharij)	G.	VIII. 124 124	Rubble cisterns, surface pottery, tesserae on rising ground.
Sāhiba, Kh.	Jm.	XIII. 172 111	Ruined wall.
Sahl Qûsîn	N.	VI. 165 186	see Qûsîn es Sahl.
es Sabla, Kh.	A.	III. 183 262	Heaps of stones, cisterns, traces of ancient terracing.
es Sahlât, Kh.	RA.	X. 174 159	see el Bâtin, Kh.
Sa'ira, Kh.	Jm.	IX. 153 127	Foundations.
Sajûr	A.	III. 182 261	Rock-cut tombs, foundations, cisterns, column shafts and ancient building material in village.
Sakhnin	A.	III. 178 252	Built tomb with sarcophagi (Maqâm es Siddiq). Inscribed lintel in house of Sa'da el Qassûm.
es Sakhra, Kh.	G.	XI. 168 110	Traces of ruins, foundations.
Sakhrat en Nasâra	G.	VIII. 121 126	Ancient tombs, surface pottery.
es Sâkût, Kh. Tell	N.	VII. 202 197	Foundations, heaps of stones and surface pottery over extensive area. Foundations at spring, ancient cemetery to north.
Sal'a	N.	VI. 167 186	Rock-cut tombs with niches, caves.
Salamiya, Kh.	RA.	IX. 170 148	Rough masonry foundations, rock-cut tombs and caves.
Salantah, Kh.	He.	XII. 146 082	Foundations, flint heaps.
Salfit	N.	VI. 167 165	Rock-cut tombs in valley south of village.
Salha	S.	III. 193 276	Cisterns, pool, mosaic floor, rock-cut tombs, oil presses.
Sâlih, Kh.	Jm.	X. 171 127	Foundations of large building, door cill, cisterns.
Sâliha, Wadi	S.	III. 194 275	Caves with prehistoric worked flints.
Sâlim	N.	VII. 182 179	Foundations, cisterns, ruined tank, rock-cut tombs.
es Sallâma, Kh.	A.	III. 188 254	Foundations, tombs, rock-cuttings, caves, aqueduct.

Name of Site	Sub-District	Map Reference	Description
es Sallāqa, Tell	Re.	IX. 130 147	<i>see</i> el Khirba.
es Sallōja, Kh.	G.	VIII. 128 133	Rubble foundations, ruined cisterns and reservoirs, rough mosaics, surface pottery.
Salma, Kh.	He.	XII. 164 095	Foundations, heaps of stones.
Sam'a	He.	XII. 147 093	<i>see</i> Khallat Sam'a, Kh.
Samah, Kh.	A.	II. 169 275	Modern building on ancient foundations, rock-cut tombs, cisterns.
es Samak, Tell	H.	II. 146 248	Artificial mound, foundations of buildings, mosaic pavements, ancient landing places and rock-cuttings. Rock-cut cemetery to east. Foundations of chapel with mosaic floor beside main road.
Samāra, Kh.	J.	IV. 163 203	Walls and foundations of buildings, caves, rock-cut pool.
es Samarāt, Tell	Jm.	X. 192 141	Artificial mound, coloured tessellated pavement.
Sāmi, Kh.	G.	XI. 115 117	Ruined pool and foundations near the Maqām (en Nabi Sāmi), surface pottery, marble fragments.
es Samīra, Kh.	Jm.	X. 187 125	Mound with foundations of wall and buildings, terrace walls, pool.
Sāmiya, Kh.	RA.	X. 182 155	Ruined buildings at spring and on bank of Wadi el Mahāmi, caves.
Samkiya, Kh.	RA.	X. 176 150	Rough stone walls and foundations.
Sammu'lya	S.	III. 192 263	Foundations of walls. Ruined building with column and base, tombs cut in the rock, caves, lintels, capital, cut stones.
Sammūniya, Kh.	Nt.	V. 170 234	Artificial mound, traces of building with columns and pedestals, ancient rock-cuttings, rock-cut graves and sarcophagi in valley to north.
Sammūniya, Kh.	Jm.	IX. 156 129	<i>see</i> et Tantūra, Kh.
es Sammūra, Kh.	S.	III. 191 262	Foundations, heaps of stones.
Samra	T.	V. 208 237	Ancient site with foundation and stone heaps north and east of village. Roman cemetery to south and east.
Samra, Kh.	H.	IV. 152 210	Heaps of stones on apparently artificial mound.
es Samra, Kh.	N.	VI. 157 171	Foundations, caves, cisterns, traces of an ancient road.
Samra, Kh.	He.	IX. 137 196	Foundations, caves, well.
es Samra, Kh.	Jm.	X. 196 147	Foundations, quarries, caves.
es Samu'	He.	XII. 156 090	Remains of tower and synagogue, ruined buildings and foundations, many re-used lintels and carved fragments in village, tombs, caves.
Samwil, Kh.	Jm.	IX. 168 136	<i>see</i> el Khirba.
es Sanāhira, Kh.	He.	XII. 145 113	Ruined walls and foundations of dressed stone, cisterns. Press with stone stanchions, caves, area paved with white tesserae.

Name of Site	Sub-District	Map Reference	Description
es Sanam, Tell (en Nugeid, Tell)	G.	XI. 092 097	Artificial mound, surface pottery and marble.
Sanâsin, Kh.	Jm.	IX. 157 122	Foundations.
Sandahanna	G.	VIII. 119 126	Remains of walls, surface rubble and pottery, press, roller stone.
Sandahanna, Kh.	He.	XII. 141 111	Remains of church with apse, foundations.
Sandahanna, Tell	He.	XII. 140 111	Artificial mound, foundations, rock-hewn painted tombs, columbaria, shaft tombs, rock-hewn caves.
es Saniffa, Kh.	S.	III. 192 275	Heaps of stones, rock-cuttings, circular pressing floor and vat.
Sanjaq, Tell	S.	III. 203 263	Heaps of stones, enclosure of rough blocks, pool, surface pottery.
Sanniriya	N.	VI. 155 171	Traces of fort in village, mosque with vaulted burial chamber.
Sânûr	J.	VII. 173 196	Village wall with towers, tombs cut in the rock, inscriptions, rock-cuttings, caves, cisterns.
Sanût, Kh.	He.	XII. 163 102	Foundations, rock-cut cisterns.
es Saqâti, Tell	He.	XV. 141 080	Mound with traces of foundations, ruined well.
Sar'a	Jm.	IX. 149 131	Caves, tombs, rock-cut cisterns, wine-press, altar near track to 'Artuf.
Sâra, Kh.	T.	V. 192 231	Ruined walls, cisterns, presses, fragments of basalt column, rock-cut tomb.
Sâra, Kh.	N.	VII. 179 162	Foundations, cisterns, weight stone of press.
es Sar'a, Kh. Wadi	RA.	IX. 169 149	see 'Amûda, Kh.
es Sarafand	H.	IV. 144 223	Tombs in and near the village.
Sarafand el 'Amâr	Re.	IX. 136 152	Tombs, cisterns, sarcophagus.
Sarafand el Kharâb	Re.	IX. 132 149	Pool, vaulted building (el Baubariya).
Sarar, Kh.	He.	XII. 132 103	see Rasm Tûr Tâni.
es Sarâsir, Kh.	He.	XII. 157 104	Remains of building with niches, foundations, plastered cisterns, wine presses, rock-cut tombs and caves, cave with columns and capitals, spring with rock-cut channels.
es Sarâsira, Kh.	He.	IX. 151 123	Mosaic pavement, rock-cut steps, columns, lintel, press piers.
(es Sarâsira, Kh. Wadi, ed Dar, Kh.)			
es Sârim, Tell	Bn.	V. 197 207	Double mound, surface pottery.
Sârin, Kh.	N.	VII. 176 179	see el Qasr.
es Sarîra, Tell	H.	IV. 138 204	see esh Sheikh Zîraq, Tell.
Sarisa, Kh.	N.	VII. 172 172	Scattered stones, cisterns, tombs cut in the rock.
Sarona, Kh.	T.	V. 193 235	Vault over a spring, ruins of buildings, and reused ancient materials, columns, capitals, lintels and door-posts with carved ornament, mosaic pavement, traces of cemetery.
es Sarri, Kh.	He.	XII. 149 097	Ruined walls, caves, cisterns, rock-cut wine-press and tombs.

Name of Site	Sub-District	Map Reference	Description
es Sarris, Tell	H.	IV. 143 219	Remains of circular wall, surface stones.
Sarrisa, Kh. (Umm Sarrisa)	Re.	IX. 144 136	Ruined walls over extensive site, cisterns cut in the rock, vaulted caves.
Sartaba, Kh.	A.	III. 196 265	Ruined walls overgrown, cisterns, olive-press, tombs cut in the rock.
Sarub el Fauqa, Kh.	A.	III. 177 276	Ruined walls, shaft of column, cisterns, tombs.
Sa'sa'	S.	III. 187 271	Remains of walls, and vaults in village, rock-cut tombs, presses and cisterns, architectural fragments.
Sa'sa', Kh.	H.	II. 163 242	Foundations, rock-cut tombs, cisterns and caves.
es Satih, Kh. (es Satta, Kh.)	He.	IX. 141 122	Traces of walls, scattered stones, tomb, cave, cistern.
es Satti, Kh.	RA.	X. 172 154	see Shatti, Kh.
es Sauma'a, Kh.	Jm.	X. 172 136	Enclosure of large stones, remains of rectangular structures, cisterns, vaulted room, worked flints.
Sa'wa, Kh.	Ba.	XV. 149 076	Fallen walls and stones.
es Sa'wa, Tell	Ba.	XV. 149 076	Mound with remains of tower and cistern.
Sawabta, Kh.	G.	XI. 118 105	see el Marashân, Kh.
es Sawâfir el Gharbiya	G.	VIII. 122 123	Fragments of marble, columns at Maqâm esh Sheikh el Bâz. Foundations, ancient stones.
es Sawâfir esh Shamâliya	G.	VIII. 123 125	Fragments of marble, columns and capitals at well.
es Sawâfir esh Sharqiya	G.	VIII. 122 122	Column shafts and fragments at well.
es Sawâmîr, Kh.	H.	IV. 146 226	Foundations, heaps of dressed stones, caves, tombs, well.
es Sawâqi, Kh.	G.	XI. 101 103	Foundations, ruined pool, tombs, cisterns, surface pottery, marble fragments, well, column fragments, mosaic floor.
es Sawârîf, Kh.	G.	VIII. 109 122	see Dureibât es Sawârîf.
es Sawarika, Kh.	Ba.	XII. 120 103	Low mound with traces of ruins, scattered stones, surface pottery.
Sawawîn, Kh.	H.	IV. 149 216	see el Khirba.
es Sâwiya, Kh. (Barqîf Kh.)	N.	VII. 175 166	Ruined walls, foundations, rock-cut tombs.
es Sâyigh, Rujm	N.	VII. 196 169	Ruined tower.
Sde Nahum	Bn.	V. 195 215	see Birkat el Fakht.
Seilum, Kh.	N.	VII. 178 162	Artificial mound, ruins of churches with mosaics, two ruined mosques, rock-tombs, cave, rock-pool, ancient road, presses.
es Seiyâd, Kh.	N.	VII. 175 187	Traces of ruins.
es Seiyâda, Kh.	T.	V. 199 237	Ruined houses, foundations, heaps of stones.
es Seiyâh, Kh. (Dhahrat Seiyâh)	Re.	VIII. 125 140	Surface pottery and rubble, tesserae.
es Seiyâra, Kh.	S.	III. 208 267	Remains of basalt buildings.

Name of Site	Sub-District	Map Reference	Description
es Sfaï', Rujûm	Ba.	160 030	Ruins of buildings and walls along summit of ridge, flints.
Sha'ab	A.	III. 173 255	Cisterns, tombs, well cut in the rock, sculptured stones reused in village mosque.
Sha'arta, Kh.	Ba.	XI. 098 091	see Qutshân, Kh.
Sha'b el Fallâh, Kh.	He.	XII. 143 114	see el Fallâh, Kh.
Shabâna	H.	IV. 166 240	Ruined walls, uprights of oil press, round stone basin.
Shabtîn, Kh.	Re.	IX. 154 153	Scattered masonry, rock-cut cisterns and tombs, caves, rock-cut press.
Shaddûd, Tell	Nt.	V. 172 229	Artificial mound, surface pottery, rock-cuttings to north-east, well to south-east.
esh Shâdarwân, Kh.	He.	XII. 145 101	see el Mahami, Kh.
Shafa 'Amr	H.	II. 166 245	Two ruined forts (es Sarâya and el Burj), cisterns, caverns, tombs.
Sha'fat el Mughr (Sha'fat Umm ez Zamliya)	G.	XI. 113 100	Roman cemetery with rock-cut tombs.
esh Shaghrab, Kh.	Jm.	X. 172 123	Traces of foundations, cisterns.
esh Shâh, Kh.	He.	IX. 140 125	Remains of settlement, cisterns, caves cut in the rock, ancient terraces, columbarium.
Sha'fra, Kh.	Ja.	VI. 140 164	Rock-cut pool, surface pottery, masonry, well, rubble cistern.
esh Shajara	T.	V. 188 240	Buried foundations of church, columns, bases, pedestals and carved stone fragments, rock-cut tombs, inscribed stone at house of M. Darwish.
esh Shajara, Kh.	N.	VI. 167 167	Ruined buildings, tower with windows; to west rock-cut cisterns.
esh Shajara, Kh.	He.	IX. 140 125	see esh Shâh, Kh.
Shajarat en Nitla	Jm.	X. 196 140	see en Nitla, Tulûl.
Shajarat es Sa'âda	J.	V. 176 209	Foundations and traces of walls, rock-cut tombs, wine-presses, cistern.
esh Shakhta	Jm.	IX. 156 126	see esh Sheikh Ibrahim, Kh.
esh Shalandi, Kh.	Ba.	XII. 136 090	Small ruin, cisterns, caves, Roman milestone.
Shalkha, Kh.	G./He.	XII. 133 113	see Umm Kalkha, Kh.
esh Shallâl, Kh.	N.	VI. 164 166	Foundations, rock-cut tombs.
Shallâla, Kh.	H.	IV. 152 237	Remains of building, aqueduct, caves, tombs, quarry.
Shallâlat Umm el 'Umdân (Qa' Wadi es Sana', Darajat Wadi es Sana')	He.	IX. 153 124	Foundations, ruined walls, column shafts and pedestals, wine presses, rock-cut steps, Roman milestones.
Sham', Kh.	S.	III. 191 264	Funerary monument (es Sarîr), ruined buildings, doorposts, columns, wine and olive-presses cut in the rock, tombs, cisterns, caves.
esh Shamdîn, Tell	Bn.	V. 194 211	Artificial mound, foundations, scattered stones.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
esh Shamdin, Tell	Bn.	V. 203 224	Artificial mound, stones, foundations and pottery.
esh Shamsaniyat, Kh.	He.	XII. 136 113	Foundations.
esh Shamsawi, Kh.	T.	V. 199 232	Ruins of houses, foundations, cisterns.
(esh Sheikh esh Shamsawi, Kh., Shamsin, Kh.)			
Shamsin, Kh.	TK.	IV. 157 203	Traces of ruins, cisterns, heaps of stones.
Shanna, Kh.	A.	III. 179 277	Walls, foundations, standing column and upright stones, cisterns, reservoirs, rock-cut tombs.
esh Shaqq, Kh.	N.	VII. 197 195	Traces of ruins.
Sha'ra, Kh.	T.	V. 192 235	Accumulated debris with foundations and scattered masonry, cisterns, column shaft.
esh Sharaf, Kh.	TK.	VI. 138 197	Rock-cut tombs, quarries, sarcophagus, cistern.
esh Sharaf, Kh. (Ashraf, Kh.)	G.	XI. 106 114	Ancient remains, surface pottery.
esh Sharabba, Kh.	N.	VII. 179 174	see Shurrab, Kh.
Sha'ratta, Kh.	G.	XI. 118 106	Remains of rubble buildings, cisterns, scattered glass and pottery.
esh Sharawi, Kh.	He.	XII. 148 109	Foundations, caves, cisterns, columbaria.
esh Sharif'a, Kh.	He.	IX. 146 125	Foundations, cisterns, caves.
esh Sharif'a, Tell	S.	I. 309 290	Artificial mound with surface pottery.
esh Sharif'a, Tell	Ba.	XI. 119 089	Artificial mound, surface pottery.
esh Sharqi, Kh.	Jm.	IX. 162 128	Ruined walls, foundations, caves, cisterns. Watch-tower to east.
Sharta, Kh.	H.	II. 162 246	Foundations of wall, heaps of stones, rock-cut tombs, cisterns, caves.
Shatta	Bn.	V. 190 217	Foundations, columns, rock-cut pits, buried columns, old cemetery 2 kms. to north.
Shatti, Kh.	RA.	X. 172 154	Walls, foundations, rock-cut tombs.
esh Shauf, Tell	Bn.	V. 193 211	Artificial mound with traces of foundations.
esh Shauf, Tell (North)	Bn.	V. 203 223	see ez Zanbaqiya el Gharbi, Tell.
esh Shaumar, Wadi	RA.	X. 171 148	Megalithic flint-walls, rock-cut tombs on north slope.
Shaumariya, Kh.	A.	II. 169 272	Traces of walls, lintels, cisterns.
Shaumariya, Kh.	H.	IV. 142 216	Rock-cuttings, tomb, Caesarea high level aqueduct in tunnel, low level aqueduct to west.
esh Sheikh 'Abdallah	Ba.	XII. 132 107	see el Habur, Kh.
esh Sheikh Abu el 'Einein	RA.	IX. 164 148	Remains of massive stone building and walls.
esh Sh. Abu Rabiya	He.	XII. 140 117	Small artificial mound.
esh Sh. Ahmad el 'Areini, Tell (el 'Areini, Tell)	G.	XII. 130 113	Artificial mound, Maqam with inscriptions.
esh Sheikh 'Ajlin	G.	XI. 094 101	Well with marble base of column and sarcophagus, Arabic inscription at Maqam.

Name of Site	Sub-District	Map Reference	Description
esh Sheikh 'Ali	Re.	IX. 146 156	see 'Ali Mālikina, Kh.
esh Sheikh 'Ali Jidfr, Kh.	Re.	IX. 146 137	see Jadira, Kh.
esh Sheikh 'Amād ed Din	N.	VII. 175 182	Building with dome and fragments of mosaic flooring.
esh Sheikh 'Awwad	G.	VIII. 109 122	Reservoir and rubble foundations, architectural fragments near the shrine, surface pottery, vaulted tomb, fragments of ornamented sarcophagus.
esh Sheikh Banft, Kh.	S.	III. 199 266	Heaps of stones, tombs.
esh Sheikh Barqān	J.	V. 188 212	see Fuqeiqi'a, Kh.
esh Sheikh Barrāq, Kh.	He.	XII. 143 112	Remains of few buildings. Doorposts, rock-cut caves. Cave at Muqatta'at esh Sheikh Barrāq.
esh Sheikh Bassūm, Kh.	T.	V. 196 238	see Bassūm, Kh.
esh Sheikh Bureik	H.	IV. 145 231	see Māliha, Kh.
esh Sheikh Bureik, Kh. (including Mght. Jahannam, Magharat es Sih)	H.	IV. 162 234	Artificial mound, foundations, architectural fragments, pool, caves, tombs, sarcophagus.
esh Sheikh Dawūd	Re.	IX. 137 127	Foundations, hewn stones, lintels, walls, cave.
esh Sheikh Dawūd, Tell	Bn.	V. 203 208	Artificial mound, surface pottery.
esh Sheikh Dhiyāb, Tell	N.	VII. 191 161	Artificial mound, rubble foundations, traces of stairway, aqueduct.
esh Sheikh Fātūr	Bn.	V. 199 200	Well with ancient materials, reused.
esh Sheikh Ghānim, Kh.	N.	VII. 176 179	see Jebel et Tur.
esh Sheikh Ghāzi, Kh.	He.	IX. 151 121	Shrine with conical dome, ruined town with streets, remains of buildings, caves, cisterns, press, rock-cuttings.
esh Sheikh Handhal	He.	XII. 142 096	Subterranean chamber, column fragments, chancel post.
esh Sheikh Hasan, Tell	Bn.	V. 188 215	see Tel Yosef.
esh Sheikh Humūd, Tell	Bn.	V. 192 212	see Humūd, Tell.
esh Sheikh Ibrāhīm, Kh.	Jm.	IX. 152 131	Remains of ancient building, rock-cut caves and cisterns, rock-cuttings, oil press.
esh Sheikh Ibrāhīm, Kh.	Jm.	IX. 156 126	Foundations, rough stone walls, rock-cut tombs.
esh Sheikh Ibrāhīm, Kh.	Jm.	X. 194 150	Foundations, heaps of stones, cistern, ruined Maqām with mihrab.
esh Sheikh Isa	TK.	VI. 163 190	Ruined domed shrine.
esh Sheikh Isa	RA.	IX. 164 150	Foundations, heaps of stones.
esh Sheikh Is-hāq, Kh.	H.	IV. 162 232	Ruined masonry, drafted and carved stones, columns.
esh Sheikh Khālid, Kh.	Re.	IX. 141 137	Cisterns, caves, remains of wall.

Name of Site	Sub-District	Map Reference	Description
esh Sheikh Madhi	H.	IV. 146 226	<i>see es Sawāmīr, Kh.</i>
esh Sheikh Madh- kur, Kh.	He.	XII. 150 117	Domed Maqām with inscriptions, heaps of stones, caves, well, remains of press.
esh Sheikh Mahmud, Kh.	He.	XII. 140 114	Caves and cisterns cut in in the rock, cut stones and marble colonettes at shrine.
esh Sheikh Mansūr el 'Aqqāb, Kh.	H.	IV. 144 217	Foundations of walls, cisterns, rock-cut tanks.
esh Sheikh el Mughāzi	Ba.	XI. 091 092	<i>see Idmīta, Kh.</i>
esh Sheikh Muham- mad, Kh.	Nt.	V. 189 234	Artificial mound, traces of masonry, dry stone enclosures, surface pottery.
esh Sheikh Muham- mad el Kabakba	G.	XI. 113 119	<i>see Abu Fatān, Kh.</i>
esh Sheikh Muham- mad el Qabu, Tell	Bn.	V. 201 206	Ruins of a small mosque.
esh Sheikh Musa, Kh.	Re.	IX. 144 139	Foundations, well, marble capital.
esh Sheikh Nabhan	Ba.	XI. 095 093	Ruins of Maqām on foundations of church, architectural fragments, Arabic inscriptions.
esh Sheikh Nakhur	Ba.	XI. 095 098	<i>see el 'Adini, Kh.</i>
esh Sheikh Nasrallah Kh.	N.	VII. 181 179	Foundations, cisterns, tombs, tanks.
esh Sheikh Qasim, Tell	Bn.	V. 204 222	<i>see Māsa, Tell.</i>
esh Sheikh Ribab	Bn.	V. 197 206	Small artificial mound with ruined ma- sonry to west, Roman milestones to south.
esh Sheikh er Rumi	S.	III. 193 256	<i>see en Nuweiriya, Kh.</i>
esh Sheikh Sa'd, Kh.	He.	IX. 141 123	Ruined fort, foundations, cisterns.
esh Sheikh Safriyān, Kh.	J.	V. 181 201	Foundations, heaps of stones, rock-cut tombs.
esh Sheikh Sa'id	G.	XI. 107 113	<i>see Hirbīya.</i>
esh Sheikh Sālih, Tulūl	Bn.	V. 200 217	<i>see Zab'a, Kh.</i>
esh Sheikh Sha'lā	N.	VI. 170 186	Remains of ancient building east of well, Greek inscribed lintel, rough stone enclosure.
esh Sheikh esh Shamsāwi, Kh.	T.	V. 199 232	<i>see esh Shamsāwi, Kh.</i>
esh Sheikh es Simād, Tell	Bn.	V. 199 209	Two artificial mounds, surface pottery.
esh Sheikh Suleimān, Kh.	Re.	IX. 146 143	<i>see Kufrata, Kh.</i>
esh Sheikh Tamīm	He.	XII. 139 113	Carved marble panel with Arabic in- scription in Maqām.
esh Sheikh Yahya	H.	IV. 147 232	<i>see el Mazār.</i>
esh Sheikh Yusuf, Tell	S.	I. 208 287	Artificial mound, traces of bridge or dam.
esh Sheikh Zirāq, Tell (el Akhdar, Tell; es Sarira, Tell)	H.	IV. 138 204	Foundations and accumulated debris, marble, pottery and mosaic fragments, masonry pool with buttresses.

Name of Site	Sub-District	Map Reference	Description
Shekhunat Geffen	Ja.	VI. 133 167	Bronze Age cemetery.
esh Shi', Kh.	H.	IV. 147 224	Foundations, rock-cut tombs, cistern, tank.
Shi'b Abu Rijām	He.	XII. 157 094	see el Muntar, Kh.
Shi'b el Butm	He.	XII. 163 090	Remains of megalithic structures.
Shi'b es Siyāj	Jm.	IX. 168 141	Walls, foundations, press, scattered stones, cave.
esh Shiba, Kh.	A.	III. 189 259	see Abu esh Shiba, Kh.
Shibirqa, Kh.	He.	XII. 146 110	Ruins of rectangular buildings, grooved stones, cave with columbarium, cisterns, rock-cut, tombs.
Shifaiya, Kh.	A.	III. 171 268	Traces of early buildings.
Shifāt, Kh.	Nt.	III. 176 249	Traces of ruined buildings and walls, cisterns, caves with stairs, rock-cuttings, reservoir.
Shihada, Kh.	H.	IV. 147 236	Ruined walls and foundations, remains of an ancient road, caves, tombs, rock-cuttings.
Shiqmons	N.	VI. 159 173	Cisterns.
	H.	II. 147 247	Enclosure wall, rock-cuttings to east and south, rock-cut tombs, to south tanks, wine press paved with mosaics.
Shu'b Nasr. Kh.	RA.	X. 177 150	Heaps of stones, ruined cisterns.
Shu'b eth Thaur, Rujm	He.	XII. 143 115	Foundations, cisterns.
esh Shubeika, Kh.	A.	II. 165 269	Foundations of houses, ruined vaults, lintels, rock-cuttings, rock-cut tombs.
Shufnūn, Kh.	A.	III. 187 263	Foundations, rock-cut shaft, two reservoirs to east, cave.
Shukr, Kh.	S.	III. 207 262	Foundations, enclosures, basalt stone heaps.
esh Shūna (Qudādī, Tell)	Ja.	VI. 129 168	Remains of Iron Age tower, ramp, foundations and surface pottery to south and east.
esh Shūna, Kh.	S.	III. 196 257	Vestiges of ruined hamlet, basaltic building.
esh Shūna, Kh.	H.	IV. 145 216	Remains of Roman theatre in modern building, aqueducts, mosaic pavement, ruined dams, remains of marble sarcophagi and columns, inscribed fragments.
esh Shūna, Kh.	N.	VII. 176 166	Ruined wall, heaps of weathered stones surface pottery.
Shūnat el Masāni'	N.	VII. 194 175	Foundations of tower, heap of stones.
Shūnat Tamra	Nt.	V. 188 227	Ruined tower.
esh Shuqaf, Kh.	N.	VI. 163 165	Foundations.
esh Shuqaf, Tell	Ba.	V. 195 203	Small artificial mound.
esh Shuqaf, Tell	G.	XI. 102 112	Small artificial mound with surface pottery.
esh Shuqaf, Tell (Abu er Raff')	Ba.	XII. 123 107	Artificial mound, cistern, surface pottery.

Name of Site	Sub-District	Map Reference	Description
esh Shuqaf, Tulûl	G.	VIII. 121 126	Remain of rubble reservoir and masonry construction, perhaps a pottery; many surface sherds.
Shuqaqiya, Kh.	He.	XII. 138 107	<i>see</i> Shuqqâq, Kh.
Shuqba, Magharat	Re	IX. 154 154	Cave with prehistoric remains.
esh Shuqfa, Kh.	S.	III. 151 271	Traces of foundations, small pool, heaps of stones.
esh Shuqqâq, Kh.	He.	XII. 135 102	<i>see</i> Umm Suweilim, Kh.
Shuqqâq, Kh.	He.	XII. 138 107	Foundations of squared stones, wine vats cut in the rock, heaps of stones, cisterns.
Shûra, Kh.	S.	III. 204 204	Foundations of walls, dressed stones, reservoir, sarcophagi, shafts of columns.
esh Shureim, Kh.	N.	VI. 170 187	Foundations, rock-cut cisterns and caves.
Shurrâb Kh.	N.	VII. 179 174	Traces of ruins.
Shuteiwi el 'Uscibi, Kh.	Ba.	XI. 119 095	Scattered stones, cisterns.
Shuweika, Kh.	N.	VII. 186 179	Traces of ruins, well.
Shuweika (er Ras)	TK.	VI. 154 194	Artificial mound, foundations of walls, on north side rock-cuttings, caves, cisterns.
Shuweika, Kh.	He.	IX. 148 121	Ruined walls of houses, carved stones, caves, cisterns, rock-cut wine and oil presses.
Shuweika, Kh.	He.	XII. 151 090	Ruined buildings, foundations, caves, rock-cut cisterns, wells.
Si', Kh.	RA.	X. 181 158	Ruined buildings of squared masonry, walls, cisterns, rock-cut pool, caves, ancient road from north-west to south, rough stone structure, tomb with mural paintings partly rock-cut partly built.
es Siba	Bu.	V. 201 209	Roman milestones.
Sibtari, Kh.	Ja.	IX. 138 155	Artificial mound, column shafts, surface pottery, reservoirs to east and west.
es Sih, Kh.	A.	III. 178 257	<i>see</i> Bât es Sih, Kh.
es Sih, Kh.	A.	III. 178 273	Ruined buildings, drafted masonry, cisterns, tombs, columns, doorposts, press.
es Sih, Magharat	H.	IV. 162 234	<i>see</i> esh Sheikh Bureik, Kh.
Sihan, Tell	G.	XI. 106 095	Cisterns, surface pottery and marble fragments, ancient rubbish mound to east.
Si'ir	He.	XII. 164 110	Rock-cut tombs.
es Sikka, Kh.	He.	XII. 144 100	Remains of foundations, cisterns, well, rock-cut caves and underground chambers.
Silwad	RA.	X. 175 155	Rock-cut tombs south and west of village, cisterns. To south press and fragment of tessellated floor.
Silwan	Jm.	X. 174 131	Rock-cut tombs.
Simbis, Kh.	G.	XI. 119 112	Remains of rubble walls, ruined cisterns, surface pottery.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
es Simiya	He.	XII. 153 092	Ruins of town with remains of buildings, cisterns, carved lintels, columns, door jambs and drafted masonry. To south-east rock-cut tombs with columns.
es Simiya, Kh.	He.	XII. 146 104	Foundations of buildings with doorposts and columns, cisterns, rock-cuttings, cave.
es Sineina, Kh.	S.	III. 204 263	Scattered heaps of basalt, dolmens.
Sinji	RA.	VII. 175 160	Traces of squared masonry building, tombs cut in the rock, fragments of columns and column bases, arches over spring.
es Siq, Wadi	Ba.	150 1000	Rough stone fort.
Sir	J.	VII. 180 196	Foundations, cisterns cut in the rock, heaps of stones.
Sir, Kh.	N.	VI. 156 178	Rock-cut tombs, terraces, well.
Sir el Ghanam	Jm.	X. 172 124	see es Siyar el Ghanam, Kh.
es Sira	Nt.	III. 189 243	Circular dry stone enclosure.
es Sira, Kh.	Nt.	V. 186 225	Extensive ruins, heaps of stones, sarcophagus.
Sirat el Ballā'i	He.	XII. 160 108	Foundations, cave, cisterns cut in the rock, rough pillars, staircase.
es Sirb, Kh.	N.	VII. 183 186	Remains of Roman camp and tomb.
Sirin	Bn.	V. 197 229	Mosaic pavement, vaulted spring with fragment of cornice, Greek inscription in house of Zeid esh Shihāda.
Sirīs	J.	VII. 178 192	Cisterns, caves, foundations in village. Mosque with inscribed lintel.
Sirisiya, Kh.	N.	VI. 151 163	Remains of buildings, circuit wall and houses with door-posts and column fragments, rock-cut caves, ancient roads and tombs to east and west.
es Sirr, Kh. (Qasr es Sirr)	Ba.	XV. 149 054	Ruined buildings and foundations, remains of well, terrace walls, surface pottery. To north masonry cistern and tower with arches (Qasr es Sirr).
es Sitt Leila, Kh.	H.	IV. 150 215	Artificial mound with remains of walls, cisterns, press stone, stone troughs, tombs cut in the rock.
es Sitt Nafisa	Ja.	IX. 132 156	Rock-cut tombs.
Siya, Kh.	RA.	IX. 166 156	Ruins of small town, remains of buildings, streets, columns with Maltese crosses and bases, rock-cut reservoir, cisterns, mosaic fragments, presses.
es Siyar el Ghanam, Kh.	Jm.	X. 172 124	Remains of monastery with ruined walls, vaulted cisterns, mosaic floor, tombs.
Solomon's Pools	Jm.	IX. 166 122	see el Burak.
St. Euthymius	Jm.	X. 182 133	see Khan el Ahmar, Kh.
Sāba	Jm.	IX. 162 132	Remains of Crusaders' castle, vaults, walls, glacis, rock-scarp, tombs.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Sâba, Kh.	He.	XII. 149 106	Ruined walls and foundations of dressed stones, rock-cut caves.
es Subât, Tell (el Khiyâr, Tell)	H.	II. 153 247	Artificial mound with foundations, surface pottery, built well with channel to north.
Subeih, Kh. Tell	TK.	VI. 147 190	Low artificial mound with foundations of two reservoirs, surface stones and pottery.
Subeita	Ba.	110 030	see Isbeita.
Su'eida, Kh.	Jm.	IX. 162 129	Ruined building, vaults, foundations, Greek inscribed lintel, column base, column fragment, el Habs, well, press, rock-cut tomb.
Sufari, Tell	N.	VII. 173 182	Artificial mound, scattered stones, to north tomb with moulded doorway.
es Sufeira, Kh.	N.	VII. 193 184	Traces of ruins.
Sufi el Khuraibât	N.	VII. 190 193	Ruined walls.
Sûfin, Kh.	TK.	VI. 148 178	Heaps of stones, rock-cut cisterns, reservoirs, caves, fragments of mosaic pavement, Rock-cut tombs to north.
Sûfiya, Kh.	He.	IX. 142 121	Cisterns, caves, heaps of stones.
es Sufrâni, Tell	Bn.	V. 199 204	Small artificial mound.
Sufsâfa, Kh.	H.	IV. 147 212	Mound with foundations, surface pottery and stones, architectural fragments at farmhouse by spring.
es Sugheiyar, Kh.	Jm.	IX. 159 132	Ruined walls.
Suhmâta	A.	III. 178 268	Foundations of church with mosaic pavement and inscription, rock-cut cisterns. Remains of building, pool, tombs.
es Sukhûl, Magharat	H.	IV. 148 230	Cave with prehistoric remains.
es Sukkar, Kh.	Jm.	IX. 155 131	see el Mitras, Kh.
Sukreir, Kh.	G.	VIII. 121 136	Ruins of khan, vaults, cistern, masonry well, pool.
Sukriya, Kh.	Ba.	XII. 129 108	Remains of khan, foundations, surface pottery and stones, decorated pedestal, column bases, Arabic inscription.
Sûlam	Nt.	V. 182 224	Artificial mound north east of village, foundations, rock-cut tombs to north.
es Suleimân, Kh.	H.	II. 164 242	see Jibiyatha, Kh.
es Suleimâniya, Kh.	H.	IV. 148 223	Walls, foundations, rock-cut tombs, presses, cisterns.
es Sultân, Tell (Abu Sultân, Tell)	Re.	VIII. 126 147	Artificial mound, surface pottery.
es Sultân, Tell	Jm.	X. 192 142	Artificial mound partly excavated, tombs in vicinity, masonry pool ('Ein es Sultân).
es Sûmara, Kh.	N.	VII. 176 168	Traces of settlement, two wells on terraced slope.
es Sûmara, Kh.	He.	XII. 144 092	Walls, caves, tombs, cisterns.
es Sumeili, Kh.	Ba.	XII. 120 108	see es Sawarika, Kh.
es Sumeiriya, Tell	A.	II. 159 263	Artificial mound, ruins of dressed masonry, mosaic pavements, tombs, shafts capitals.

Name of Site	Sub-District	Map Reference	Description
Sumeit, Kh.	N.	VII. 184 187	Ruined walls, qubba.
es Summāna, Kh.	N.	VI. 151 166	Heaps of stones.
Summāqa, Kh.	H.	IV. 154 231	Ruined buildings, one with moulded door jambs, slotted columns, tanks, cisterns, tombs, architectural remains.
Summeil	G.	XII. 131 119	Remains of medieval castle, column shafts, rubble masonry pool.
Summeil, Kh.	Re.	IX. 130 139	Well, ruined cistern, foundations, tombs, caves, rock-cuttings, (Mughaiyir Summeil).
es Sumra, Kh.	N.	VII. 197 187	Ruined walls.
Sumsum (er Ras)	G.	XI. 113 109	Artificial mound, rubble foundations, surface pottery, ancient well.
es Sūq, Kh.	Jm.	X. 175 127	see Deir es Sūq.
Sūq el Khan, Kh.	T.	V. 189 236	Caravanserail and fort.
Sūq Māzin, Kh.	Ba.	XI. 088 086	see Dureibāt esh Sheikh Hammūda.
Suqeifa, Kh.	He.	XII. 138 109	Heaps of stones, foundations, caves.
Suqūr, Kh.	S.	I. 204 292	see el Mabrum, Tell.
es Sūra, Kh.	He.	XII. 142 117	Ruined walls, cisterns, carved lintel, caves, remains of an olive press, Roman milestones.
Suratein, Kh.	N.	VII. 171 180	Watch-tower.
es Sureik, Kh.	Jm.	IX. 145 132	Foundations of ruined buildings, rock-cut wine-press, cisterns, rock-cut shaft with niches, tombs to south, subterranean tunnel, caves.
Surūh el Fauqa, Kh.	A.	III. 178 276	Ruined buildings, arches, walls, cisterns, upright stones, rock-cut tombs, foundations, including tomb with graffito (el Jabara).
es Surūj, Tell	J.	IV. 169 210	Ruined walls, foundations, rock-cut tombs and cisterns, quarries.
Sūsiya, Kh.	N.	VI. 158 165	Traces of ruins.
Sūsiya, Kh.	He.	XII. 160 090	Ruins of extensive settlement, foundations of building with portico, apse, doorways, moulded pilasters, cisterns, caves, lintels, ancient road.
es Suwadiya, Kh.	Re.	IX. 151 139	Rock-cut presses and tombs.
es Suweid Tell	N.	VII. 196 168	Ruins of small fort.
es Suweida, Kh.	N.	VII. 199 189	Tombs, sarcophagus, watch-tower.
es Suweif, Kh.	He.	XII. 159 063	Foundations of watch-tower, cisterns, rock-cuttings.
Rujm Suweijira, Kh.	A.	II. 165 272	Ashlar walls and traces of tower, column fragments, traces of mosaic pavement, cisterns, rock-cut tombs, caves.
es Suweika, Kh.	RA.	X. 170 144	Ruins of buildings and streets, columns and door jambs, cisterns, caves, oil press, scattered mosaic fragments, ancient road.
Suweilim, Kh.	He.	XII. 135 102	see Umm Suweilim, Kh.
es Suweis, Kh. (es Suweiti, Kh.)	He.	XII. 145 102	Foundations of church with font, caves, wells.
Suweiwā	Ba.	XIV. 100 074	Field with worked flints.

Name of Site	Sub-District	Map Reference	Description
Suwwāna, Kh.	A.	III. 176 274	Ruins of town, fallen buildings, arched and rock-cut cisterns, column fragments, tombs.
Suwwānāt	Re.	IX. 152 141	Flint quarries and implements.
es Suy-yāgh, Kh.	Jm.	IX. 150 128	Foundations of building, press stone.
Ta'abiya, Kh.	G.	VIII. 123 127	<i>see</i> el Biyār, Kh.
Tabakhāna, Kh. (Majādil, Tell)	He.	XII. 134 092	Foundations of buildings, rock-cut wine-press, cisterns, caves.
Tabaliyā, Kh.	Jm.	IX. 170 127	Ruined building with courtyard and traces of vaulted rooms, cisterns.
Tabaq el Hanna, Kh.	A.	II. 166 275	Heaps of ancient stones, quarries, wine-presses, caves.
et Tabāqa (et Harasha Tell)	G.	XL 085 091	Artificial mound with brick foundations, surface pottery.
et Tabayiq, Kh.	A.	II. 160 276	Foundations of walls, cave, cisterns.
et Tabbāna, Kh.	Jm.	IX. 155 122	Walls and foundations of building with rectangular rooms.
et Tābgha (Birkat 'Ali edh Dhahr)	T.	III. 202 253	Remains of Byzantine church and atrium with mosaic pavements and architectural fragments; to north-east remains of chapel partly rock-cut with mosaic floor, cave, cistern; to east and south-east pool, aqueducts, ruined tower, (Birkat 'Ali edh Dhahr), remains of walls and press.
et Tābgha- Rosh Pinna Road	S.	III. 201 258-60	Heaps of stones and megalithic constructions on both sides of the road at kilometre 193 and between kilometres 195 and 195.5
et Tabla, Kh.	A.	III. 171 274	<i>see</i> el Abawāt, Kh.
Tabor, Mt.	Nt.	V. 187 232	<i>see</i> Jebel et Tur.
Tabsur	TK.	VI. 139 178	<i>see</i> 'Azzun, Kh.
Tab'un	H.	IV. 163 236	Traces of early settlement, tombs, cisterns, rock-cuttings.
et Tabun, Magharat	H.	IV. 147 231	Cave with remains of Stone Age occupation.
ed Tadwira	H.	IV. 141 215	Loose masonry, architectural fragments and surface pottery on low mound, and to the north. Water conduit and reservoir, rubble vault.
Taffūh	He.	XII. 155 105	Rock-quarries, caves, ancient road.
Tafsa, Kh.	N.	VI. 166 175	Ruined village, drafted masonry, barrel vaults, ruined mosque, press, rock-cut cisterns.
et Tahūna, Kh.	A.	III. 188 260	Heaps of stones, foundations, shafts and bases of columns, ruined aqueduct, mill.
et Tahūna, Kh. (Deir et Tahūna)	Jm.	IX. 148 131	Ruins of building with dressed masonry and carved stones; to north foundations of building.
Tahūnat el Hawa	Jm.	X. 191 142	Fortress.
Tahūnat el Mafjar	Jm.	X. 193 144	Reservoir and ruined mill connected with an aqueduct.
Tahūnat el Qābū	T.	III. 198 251	Ruined mills.

Name of Site	Sub-District	Map Reference	Description
Tahûnat el Qadriya	N.	VII. 196 172	Rock-cut channel.
Tahûnat el Qilt	Jm.	X. 186 138	Aqueduct, rock-cut tunnel, remains of bridge.
Tahûnat es Sukkar, Tell	Bn.	V. 198 208	Artificial mound, surface pottery, remains of mill.
et anûna, Wadi	Jm.	IX. 169 120-121	Dam, aqueduct.
et Taiyâh, Kh.	TK.	VI. 154 190	Foundations, heaps of stones, rock-cut cisterns, press weight.
et Taiyiba	Bn.	V. 192 223	Traces of Crusaders' castle and ancient materials in village; tombs and sarcophagi to east, built spring.
et Taiyiba	TK.	VI. 151 186	Foundations, rock-cuttings and rock-cut tombs.
et Taiyiba	RA.	X. 178 151	Remains of church, Crusaders' castle in the village (el Baubariya), foundations of buildings, mosaics, rock-cut tombs, presses, cisterns.
et Taiyiba, Kh.	H.	II. 169 243	Ruins of village with foundations, fragments of columns and bases, rock-cut tombs, cisterns.
et Taiyiba, Kh.	J.	IV. 167 213	Ruined village.
et Taiyiba, Kh.	He.	XII. 153 107	Remains of buildings and vaults, rock-cut tombs to south.
Taiyibat el Ism, Kh.	He.	XII. 144 107	Foundations, remains of masonry, caves, tombs cut in the rock.
Tal'at el Ballâna	A.	II. 162 264	Remains of aqueduct, ruined walls of ancient village, surface stones and pottery.
Talha, Kh.	S.	I. 204 293	see Tel Hay.
Talhûm	T.	III. 204 254	Ruins of a synagogue, tombs; remains of buildings, presses and walls in vicinity.
Tallât en Nusûra	S.	III. 201 266	Basalt foundations, surface flints, lines of stones (el Muntara).
Tallûza	N.	VII. 178 186	Foundations and remains of buildings, columbarium, tombs, cisterns, Maqâm Harûn, Jami' el Arba'in.
Tamra	A.	II. 169 251	Foundations of ancient buildings in village, cisterns, tombs, caves cut in the rock.
Tamra	Nt.	V. 188 227	Remains of houses, fragments of mosaic floors. Foundations and columns of two churches, rectangular basin at spring, tombs, column shafts, decorated lintels.
Tana el Fauqa, Kh.	N.	VII. 185 176	Foundations, caves, cisterns, rock-cut tombs.
Tann Ibrinn, Kh.	He.	XII. 163 112	see Tin Brin, Kh.
Tannâr, Kh.	Ba.	XII. 123 107	Heaps of stones, surface pottery, cisterns, ruined reservoir.
Tannîn, Kh.	J.	V. 182 202	Traces of settlement.
Tannûra, Kh.	N.	VI. 155 171	Walls, cisterns, cave.
Tannûriya, Kh.	S.	III. 186 268	Foundations, heaps of stones, cistern.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
et Tantûr, Kh.	A.	II. 164 258	Small mound with wall foundations and surface pottery.
Tantûra (including el Burj and Jazīrat esh Shaddādīn)	H.	IV. 143 224	Artificial mound; remains of temple, harbour and other buildings, Crusader buildings on promontory (el Burj): rock-cut tombs, masonry wells, columns: building with arches on Jazīrat esh Shaddādīn, architectural fragments.
et Tantûra, Kh. (Sammûniya, Kh.)	Jm.	IX. 156 129	Foundations of square building, cisterns, tombs.
Tantûra, Kh.	RA.	X. 176 150	Remains of watch-tower, surface pottery.
et Tāqa, Kh.	Bn.	V. 201 224	Foundations of buildings.
Tarafein, Kh.	RA.	X. 170 156	Extensive ruins of buildings, ruined walls, foundations, drafted masonry, door-posts and cills.
et Tarāmi, Kh.	A.	III. 178 272	Foundations of walls, heaps of stones, cisterns, tomb cut in the rock, oil press with uprights, caves.
et Tarātīr, Kh.	G.	IX. 131 125	Surface pottery and rubble foundations, ancient well to south.
Tarbanā, Kh.	Nt.	V. 174 226	Low artificial accumulation with surface pottery.
Tarbīkha	A.	III. 177 276	Olive-press, cistern, tombs with covers cut in the rock.
et Tarīm, Kh.	J.	IV. 168 208	Traces of ruins.
Tarrāma, Kh.	He.	XII. 153 098	Remains of fort on artificial knoll, pool, rock-cut caves, columbaria.
Tarshiha	A.	III. 175 268	Village on ancient site, rock-cut tombs, cisterns, flight of steps leading to spring.
et Tārūd, Rujm	Jm.	IX. 165 129	Cairn, rock-cut cave.
Tātā, Kh.	H.	IV. 149 220	Foundations and scattered masonry, door posts, press stones, part of column, cisterns, rock-cut tombs.
et Tatarama	A.	III. 178 272	<i>see</i> et Tarāmi, Kh.
Tatrit, Kh.	Ba.	XII. 143 084	Walls, foundations, door-posts, heaps of stones, cisterns, octagonal well-head.
Taur Ikhbeina	G.	XI. 094 096	Surface pottery.
Taur Umm Rashīd	Ba.	XI. 094 094	Rubble cisterns and foundations, surface pottery.
Tawāhīn Farradiya	S.	III. 190 250	Ruined mills, aqueducts.
Tawāhīn es Sukkar	Bn.	V. 197 206	Artificial tumuli, masonry mill lead.
Tawāhīn es Sukkar	Jm.	X. 192 142	Mound with surface pottery, ruined mills with walls, vaults, aqueduct, millstones. To west vaulted room with Arabic inscription and blason.
Tawwās, Kh.	He.	XII. 150 114	Ruined walls of buildings, foundations of church with apse, cisterns, well-head, rock-cut presses, ancient road to south.

Name of Site	Sub-District	Map Reference	Description
Tayâsir	N.	VII. 188 194	Rock-cut tombs at el Qasr with masonry superstructure, other rock-cut tombs and mound with ruined buildings, cisterns, north of village foundations of buildings, presses and cisterns; to south milestones at Khallat Qâsim; ancient roads.
Tazâ, Kh.	Jm.	IX. 161 126	Traces of ruins, vault at 'Ein el Qâbû.
Teida	G.	XL 098 106	Traces of settlement consisting of wall foundations and surface pottery in dunes.
et Teira, Kh.	RA.	X. 180 149	see Qaswal, Kh.
Teitaba	S.	III. 195 268	Remains of ancient tomb and dolmens north of village; small mound to the east.
Tel Hay (Talha, Kh.)	S.	I. 204 293	Foundations of walls, rock-cut tombs.
Tel Yosef	Bn.	V. 188 215	Artificial mound, foundations of buildings in heavy masonry, surface pottery.
et Tell	A.	II. 164 268	see en Nahr.
et Tell	TK.	VI. 161 191	Mound, rock-cut tombs and caves.
et Tell	N.	VI. 163 166	Hill with traces of walls, encircling wall and cup-marks. Cave. Rough square tower to north. Pottery.
et Tell, Kh.	RA.	X. 175 147	Artificial mound, remains of city walls and buildings, heaps of stones, cisterns, tombs.
et Tell, Kh.	RA.	X. 175 159	Walls and vaults of ruined buildings, ruined mosque with niche, columns, capitals and bases, rock-cut cisterns, presses, steps, pool.
et Tell, Kh.	Ba./He	XII. 137 091	Caves, cisterns, traces of buildings.
Tha'la, Kh.	N.	VII. 194 182	Traces of ruins.
Tharîda, Kh.	RA.	VI. 156 162	Foundations of village. Remains of oil press, carved door-jamba, lintel.
(Balâta, Kh.)			
eth Thaum, Tufûl	Bn.	V. 197 205	Twin mounds, surface pottery.
eth Theiga	Ba.	130 030	Block house.
Tiberias	T.	III. 201 241	City walls, traces of Roman town and ancient remains, comprising an area bounded on the east by the sea; on the south by Wadi Quseib; on the south-west and west by a line drawn parallel to the shore, at a distance from it of 600 metres. to a point west of Qasr Bint el Malik, and from there northwards to the Power Station; on the north by a line drawn from the Power Station to the lake, including the ruin known as Sitt Sakina; Roman tombs outside that area to the north.
Tibirya, Kh.	A.	II. 169 272	Heaps of stones, cisterns, remains of masonry.
Tibna, Kh.	Jm.	IX. 144 128	Ruined walls, column fragments, caves, wine-presses, cisterns.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Tibna, Kh.	RA.	IX. 160 157	Fallen walls, foundations and vaults on mound, tombs cut in the rock.
Ti'innik	J.	V. 171 214	Artificial mound, rock-cut tombs and caves, rock-cuttings, cupmarks, presses.
Tilfit	J.	V. 182 201	Masonry.
Tilliya, Kh.	Jm.	IX. 170 136	Ruins of camp in dry rubble masonry, cistern, Roman road in valley to south.
Tin Brin, Kh. (Tann Ibrinn, Kh.)	He.	XII. 163 112	Ruined buildings, remains of square fort to north, drafted masonry, rock-cut cisterns.
et Tira Kh.	A.	II. 166 251	Ruined walls, cisterns, rock-cut tombs, Roman milestones 1 kilometre to south-east.
et Tira Kh.	Nt.	V. 181 234	Cisterns, scattered stones, tombs, caves, rock-cut wine-presses.
et Tira Kh.	Re	IX. 145 158	Foundations, columns, well, press with reservoir, rock-cut tombs, caves.
et Tira Kh.	RA.	IX. 168 147	Remains of church with mosaic pavement, column bases, piers in cave, foundations, rock-cut cisterns.
Tirat el Khāriba	Bn.	V. 193 226	Ruined settlement, caves, tombs, cisterns, rock-cuttings.
Tirat el Qazāz, Kh. (el Qazāz, Kh.)	A.	III. 177 257	Ruined building with apse, cisterns, rock-cut press.
et Trāni, Tell	Jm.	X. 189 150	Artificial mound with foundations of rectangular and other buildings.
Tāba, Kh.	S.	III. 207 263	Foundations of cut stones, column shaft, sarcophagi.
Tābās	N.	VII. 185 192	Village on ancient site. Foundations, tombs, cisterns and presses, caves and rock-cuttings.
et Tubeiqa, Kh.	He.	XII. 159 111	Site of town with ruined walls and houses, cisterns, tomb caves.
Tubrus	J.	IV. 165 201	see Jami' Tubrus.
et Tufāniya, Kh.	A.	III. 174 262	Ruined tower and houses, dressed stone doors and windows, rock-cut pool, sarcophagi, old track.
Tufeil	S.	III. 208 273	Artificial mound beneath village.
et Tufeil, Kh.	A.	III. 182 263	see Ras es Sûq, Kh.
Tulkarm	TK.	VI. 153 191	Foundations, rock-cut masonry and tombs, cisterns, sarcophagi, presses, vaulted Roman tombs in properties of Amin Salih and Mustafa Habayib.
Tāmīs, Tell	Bn.	V. 196 213	Artificial mounds, foundations, columns, mosaic floors, Roman milestones.
Tuneifisa, Kh.	He.	IX. 139 120	Traces of foundations, caves, cisterns (one with winding staircase).
et Tuqû', Kh.	Jm.	XIII. 170 116	Ruined buildings, remains of church with octagonal font, columns and bases, caves, rock-cut tombs.
Tur es Safa, Magharat	He.	XII. 154 110	Cave.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Tur'an	Nt.	III. 185 242	Some ancient masonry, caves, rock-cut cisterns and tombs, built well to north.
Turmus 'Aiya	RA.	VII. 177 160	Cisterns, inscriptions and architectural fragments built into modern walls, rock-cut tombs, sarcophagi and remains of built monuments, remains of press with tessellated floors.
et Tuwaiyil, Kh.	N.	VII. 187 168	Foundations, heaps of stones, cistern.
et Tuwaiyil, Tell	Ba.	XIV. 109 068	Surface pottery and rubble.
et Tawāni, Kh.	He.	XIII. 165 091	Enclosure walls, foundations, well, rock-cut tombs, lintel, caves.
et Tawāni, Tell	He.	XII. 165 091	Traces of foundations and cut stones on summit of natural hill, cistern cut in the rock.
et Tuyūr, Tell	G.	XII. 125 118	Low artificial mound with surface pottery.
'Uba, Kh.	S.	III. 194 276	Foundations, caves, tombs, reservoir.
'Ud, Kh. (Zammāra, Kh.)	Ba.	XI. 106 089	Traces of settlement with rubble cisterns, surface pottery and rubbish mounds.
el 'Uda, Kh.	A.	III. 171 274	see el Abawāt, Kh.
el 'Uddeisa, Kh.	He.	XII. 163 106	Dry stone circuit wall and rock-scarp within ruined walls. Rock-cut cisterns and caves.
'Udhfur, Kh.	N.	VII. 183 186	Foundations, heaps of stones, rock-cut cisterns, tombs. South of Khallat esh Shu'b tomb caves and cisterns.
el 'Ujūl, Tell	Nt.	V. 185 226	Hill top with heaps of rough stones and surface pottery.
el 'Ujūl, Tell (el 'Ajjūl, Tell)	G.	XI. 093 098	Artificial mound partly excavated, cemeteries in the plain and dunes.
'Ukbur, Kh.	Jm.	IX. 146 128	Fallen buildings, streets, door-posts; lintels, mill-stones; rock-cut cisterns; caves.
el Ukheidir, Tell	G.	VIII. 118 137	see Murra, Tell.
'Ulam	T.	V. 197 230	Ruined walls, old masonry and carved stones reused, column, grind stones; cisterns south and south-west of village.
el 'Umari, Kh.	Ba.	XII. 130 085	Traces of foundations, cisterns.
el 'Umdān	He.	XII. 143 109	see Umm el 'Amad, Kh.
Umm el 'Adas	He.	IX. 145 120	see el 'Adas, Kh.
Umm 'Adra, Kh.	Ba.	XI. 109 089	Traces of ruined buildings, rubble cisterns, surface pottery.
Umm 'Ajwa (el Qādi, Kh.)	Ba.	XIV. 097 073	Cisterns, column fragments, surface pottery and rubble.
Umm el 'Alaq Kh.	T.	V. 192 239	see Kafr Sabt.
Umm el 'Alaq Kh.	H.	IV. 145 217	Remains of tower, ruined walls, column shaft and base.
Umm 'Ali, Kh.	S.	III. 201 278	Scattered stones.
Umm el 'Amad	H.	IV. 166 237	see Waldbeim.
Umm el 'Amad	Jm.	XIII. 176 114	Ruined walls, pillar shafts, tank.

Name of Site	Sub-District	Map Reference	Description
Umm el 'Amad, Kh.	T.	III. 189 247	Remains of a synagogue with columns and bases, carved lintel and decorated stones; building partly built of ancient stones; vaults, foundations, reservoir, broken sarcophagus to south; rock-cut tombs and cisterns, traces of presses, ancient road.
Umm el 'Amad, Kh. (el 'Umdân)	He.	XII. 143 109	Roman milestones.
Umm el 'Amad, Kh.	He.	XII. 154 094	Ruined walls, caves, cisterns, rock-cut wine press.
Umm el 'Amad, Kh. (el Ghanâyim, Kh.)	He.	XII. 163 095	Ruined Byzantine church with standing columns and lintels, remains of monastery, caves, rock-cut wine-press, tower, rock-cut cisterns, columbaria.
Umm 'Amir	Ba.	XI. 090 095	see Dhahrat Umm 'Amir.
Umm 'Amûd, Kh.	He.	XII. 135 118	Traces of foundations, scattered stones.
Umm el 'Amûd, Magharat	N.	VII. 190 180	Cave, tombs.
Umm el 'Asâfir, Kh.	Jm.	X. 171 125	Traces of walls, rock-cut caves, columbaria.
Umm el Asfa, Kh.	He.	XIII. 165 094	Traces of small settlement.
Umm el 'Ausaj	Re.	IX. 142 130	see 'Asfûra, Kh.
Umm el Autâd, Kh. (Bir el Autâd)	He.	IX. 141 129	Foundations, old stones at well, surface pottery.
Umm el Autâd, Kh.	Jm.	X. 187 122	Ruined settlement.
Umm 'Azba, Kh.	Jm.	X. 194 149	Caves with traces of prehistoric settlement.
Umm Bâbein	He.	XII. 142 114	see Umm Haqqein, Kh.
Umm Baghla, Kh.	He.	XII. 141 093	Foundations, caves, cisterns.
Umm el Banâya, Kh.	G.	VIII. 125 132	Remains of rubble buildings and cisterns, surface pottery, tombs.
Umm el Basal, Kh.	H.	IV. 153 211	Ruined walls, worked stones, cisterns.
Umm el Basal, Kh.	He.	XII. 140 114	Ruined walls, caves, cisterns, tomb.
Umm el Basal, Kh.	He.	XII. 148 119	Ruined walls of buildings, cisterns, cylindrical stone of press; to south rock-cut cave.
Umm el Bikâr, Kh.	Ba.	XII. 126 105	Scattered stones, ruined cisterns.
Umm el Bureid, Kh.	Re/N.	VI. 149 166	Foundations, ruined walls on hilltop, door post, reservoir.
Umm Burj, Kh.	He.	XII. 147 116	Ruined walls, caves, cisterns, columbarium, cupmarks in the rock.
Umm Buteih, Kh.	Ba.	XII. 120 100	Remains of rubble buildings and cisterns, well, marble column-shaft fragments.
Umm Buteina, Kh.	Ba.	XV. 138 076	Traces of ruined settlement.
Umm el Butm, Kh.	J.	V. 178 203	Ruined buildings and Maqâm, heaps of stones, rock-cut caves and cisterns, rough stone structure to north, rock-cut tomb to east.
Umm ed Dajâj, Kh.	He.	IX. 151 122	see Umm el Jâj, Kh.
Umm ed Dakâkin	He.	XII. 163 098	Rock-cut tomb with rock piers.

Name of Site	Sub-District	Map Reference	Description
Umm ed Dakâkin, Kh. J.	J.	V. 172 203	Traces of settlement, rock cut tomb, scattered stones, well in valley.
Umm Dar, Kh. (el Muntar)	J.	IV. 163 207	Square tower.
Umm ed Daraj	He.	XII. 149 091	Quarry.
Umm ed Daraj, Kh.	H.	IV. 153 229	Foundations and scattered masonry. Column shafts, cisterns, presses.
Umm ed Daraj, Kh.	Re.	IX. 147 132	Foundations, enclosures, caves.
Umm ed Daraj, Kh. (ez Zubeiya, Kh.)	He.	XII. 141 117	Rock-cut cisterns, foundations.
Umm ed Deinina, Kh.	He.	XII. 143 087	Heaps of stones, enclosure wall, foundations, caves. Cistern, column fragments.
Umm edh Dhiyâb, Kh.	He.	IX. 150 123	Foundations, heaps of cut stones, rock-cut cisterns.
Umm el Fulûs	TK.	VI. 141 190	Rock-cut cisterns, surface pottery, rubble foundations, mosaic pavement, scattered stones.
Umm el Ghanam, Kh.	Nt.	V. 187 231	Fallen column-shafts and masonry, caves, artificial mound in the plain.
Umm el Ghânima, Kh.	N.	VI. 167 185	Ruined walls, foundations, columns, cisterns.
Umm el Ghawâdi, Kh.	Nt.	V. 180 228	Foundations of buildings, sarcophagus north of site.
Umm el Haffa, Kh.	J.	V. 171 205	see el Muhaffar, Tell.
Umm el Hajar	G.	XI. 085 091	Traces of rubble foundations, surface pottery, tesserae and marble chips.
Umm Hajar, Kh. (Dhahrat Humsa)	N.	VII. 197 178	Watch-tower.
Umm Halasa, Kh.	He.	XIII. 166 099	Traces of ruins, two wells.
Umm Hallâl	N.	VII. 192 170	Watch-tower.
Umm Hamâta, Wadi	Ba.	130 020	Ruined buildings, terrace and boundary walls, rock-cut cistern.
Umm el Hammâm, Magharât	Jm.	X. 187 129	Pool, small cave.
Umm Haqqein, Kh.	He.	XII. 142 114	A cave, cistern, heaps of stones.
Umm Hâratein, Kh.	Re.	IX. 146 139	Ruined walls, drafted stones, olive-press.
Umm Hâratein, Kh.	He.	XII. 137 100	Foundations, fallen stones, caves, cisterns.
Umm el Hasan, Kh.	N.	VII. 194 185	Heaps of stones, rock-cut tomb.
Umm Hujeir, Kh.	Bn.	V. 200 228	Foundations of buildings, rubble stones.
Umm el Humâm, Kh.	S.	III. 200 273	Tomb, two reservoirs.
Umm el Husr, Kh.	N.	VII. 196 188	Heaps of stones, rock-cut tomb.
Umm Huweita, Rujm	He.	XII. 162 086	Ruined watch-tower.
Umm el Ibgâ, Kh.	N.	VI. 150 164	Ruined walls, vaulted chambers with recesses, tombs, wine-press, rock-cut cisterns.
Umm el Ibgâ, Kh.	N.	VII. 194 191	Foundations, tombs, cisterns.
Umm Itsân, Wadi	Ba.	XV. 145 059	Enclosures and terrace walls, ruined cistern.
Umm el Jâj, Kh.	He.	IX. 151 122	Walls, cisterns, rock-cut tombs, caves.
Umm Jarrâr, Kh.	Ba.	XI. 097 092	Rubble cisterns, buried mosaic pavement, surface pottery.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Umm el Jimâl, Kh.	H.	IV. 151 223	<i>see</i> Bat Shelomo.
Umm el Jimâl, Kh.	Jm.	X. 177 130	Traces of ruins, foundations, rock-cut cisterns, caves and tombs.
Umm Jîna, Kh.	Jm.	IX. 146 125	Foundations, heaps of stones, cisterns, to south rock-cut tombs.
Umm Jubeil, Kh.	Nt.	V. 186 237	Foundations of an old wall, terraces, rock-cut tombs, cisterns, fragments of columns.
Umm el Jurein, Kh.	N.	VII. 192 183	Ruined cistern, foundations.
Umm el Kadish, Kh. (el Akâdîsh Kh.)	H.	IV. 154 216	Ruined walls, cisterns.
Umm el Kalkh	S.	III. 204 257	Dolmen field.
Umm Kalkha, Kh.	Re.	IX. 137 136	Foundations, rock-cut tombs, caves, cisterns.
Umm Kalkha, Kh.	G./He.	XII. 133 113	Foundations, surface pottery.
Umm Kashram, Kh.	He.	XII. 136 107	Foundations, well, caves, rock-cisterns.
Umm Khâlid	TK.	VI. 138 193	Remains of vaulted building with corner tower, well, granaries, reservoir, surface pottery to west and north of village, cisterns; prehistoric worked flint in road cutting to north-west.
Umm el Khanazir, Kh.	He.	XII. 148 112	<i>see</i> el Khanazir, Kh.
Umm el Kharrûba, Rujûm	He.	XII. 159 082	Foundations of two watch-towers.
Umm el Kharrûba, Wadi	Ba.	130 040	Tower of rough limestone blocks.
Umm el Kubaish, Kh.	N.	VII. 191 185	<i>see</i> 'Urqân el Hamâm.
Umm el Labad, Kh.	Re.	VI. 148 162	Ruined buildings and walls, cisterns.
Umm Lâqis, Kh.	G.	XII. 120 109	Foundations and surface pottery on partly artificial mound, cisterns.
Umm el Lauz, Kh.	He.	XII. 146 118	Foundations, column fragments, carved lintel, cisterns, caves.
Umm el Madâbigh	S.	III. 202 262	Wine press and vat cut in the rock.
Umm Mâlik, Kh.	He.	XII. 142 113	Foundations, cisterns, caves with niches.
Umm el Meis	He.	XII. 161 116	Foundations of walls, oil press, heaps of stones.
Umm el Meis, Kh.	He.	XII. 143 103	Traces of settlement with caves, rock-cut cisterns.
Umm Mu'arrif, Kh.	Ba.	XII. 130 105	Remains of heavy stone foundations.
Umm el Muddeida	G.	XI. 079 084	Two artificial mounds, rubble stones, marble fragments, tesserae, surface pottery.
Umm el Mughr	He.	IX. 142 125	Foundations, enclosures, scattered stones, cisterns, caves, rock-cuttings.
Umm en Naml, Kh.	J.	V. 177 204	Heaps of stones, artificial caves and cisterns.
Umm en Naqûs, Magharat	Jm.	XIII. 173 116	Cave with prehistoric remains.
Umm en Natsha, Kh.	Jm.	X. 171 120	<i>see</i> en Natsh, Kh.
Umm Nukheila	Ba.	XI. 103 090	Rubble cisterns, surface pottery.
Umm el Qal'a, Kh.	Jm.	IX. 161 124	Ruined walls, foundations, scattered masonry.

Name of Site	Sub-District	Map Reference	Description
Umm Qal'a, Magharat Jm.		XIII. 173 117	Cave with prehistoric remains.
Umm el Qalâ'id, Kh.	J.	IV. 168 223	Remains of small settlement, foundations of walls, column fragment.
Umm Qallûm, Kh.	G.	XI. 111 107	Ruined room with remains of oil press, rubble foundations, surface pottery.
Umm el Qanâtir	T.	V. 204 235	Piers of ruined bridge in river bed.
Umm el Qaryatein,	He.	XII. 161 085	Foundations of buildings and enclosing wall, caves, cisterns.
Kh. (Mu'ei'id, Kh.)			
Umm el Qâsim, Kh.	N.	VII. 184 184	Traces of ruins.
Umm Qatafa,	Jm.	XIII. 173 118	Cave with prehistoric remains.
Magharat			
Umm el Qatan, Kh.	N.	VII. 195 184	Foundations, heaps of stones.
Umm Qeisama, Kh.	N.	VII. 193 183	see Muqeisima, Kh.
Umm Qeisuma, Kh.	Ba.	XIV. 114 051	Ruins of Byzantine settlement, well, foundations of large building, cisterns, column fragments.
Umm el Qutn, Kh.	He.	XII. 145 115	Foundations, mosaic floor, cisterns, heaps of stones, rock-cut caves.
Umm er Ramâmin,	Ba.	XII. 137 087	Ruined buildings on extensive site, moulded and carved stones. Column, press, cisterns.
Kh. (Umm er Ramali, Kh.)			
Umm Râziq, Kh.	He.	XII. 142 115	see el Huseinât, Kh.
Umm er Rihân, Kh.	J.	IV. 164 210	Traces of ruins, ruined watch-tower.
Umm Rijl, Kh.	Ba.	XI. 103 088	Surface pottery and stones, rubble cisterns.
Umm er Riyâh, Kh.	G.	VIII. 116 126	see el Wâwiyât, Kh.
Umm er Rujmân	N.	VII. 189 176	Heaps of stones.
Umm er Rujmân, Kh.	Re.	IX. 153 144	A large square enclosure.
Umm er Rujûm, Kh.	G.	XI. 119 104	see el Hammâm, Kh.
Umm Rukba, Kh.	He.	XIII. 165 096	Remains of buildings, lintel.
Umm er Rûs esh	He.	IX. 152 122	Remains of church with mosaic pavement, ruined buildings, walls, column, bases, door posts, cisterns, caves.
Shamaliya, Kh.			
Umm Sâbuna, Kh.	Bn.	V. 201 221	Foundations of buildings, heaps of rubble, surface pottery.
Umm Safâh	RA.	IX. 166 157	Ancient masonry in Jami' en-Nabi Hanân and foundations to west, medieval surface pottery.
Umm Sarbut	Ba.	XV. 133 073	Rubble cisterns, cave cut in the rock, tunnel.
Umm Sarriisa	Re.	IX. 144 136	see Sarriisa, Kh.
Umm es Sayar	He.	XII. 151 091	Caves, ruined enclosure, cistern.
Umm esh Shaibak,	N.	VII. 194 187	see Musheibish, Kh.
Kh.			
Umm esh Sharâshih	Bn.	V. 201 215	see Bawâti, Kh.
Umm esh Sharit, Kh.	RA.	IX. 170 144	see 'Ein Umm esh Sharâ'it, Kh.
Umm esh Shaumar,	He.	XII. 136 117	Foundations, oil press, cisterns cut in the rock, stone trough.
Kh.			
Umm esh Shaumar,	H.	IV. 153 234	Rock-cut tombs, remains of rubble houses, surface pottery.
Kh.			
Umm esh Shuqaf,	G.	VIII. 114 121	see edh Dhirâ', Kh.
Kh.			

Name of Site	Sub-District	Map Reference	Description
Umm esh Shuqaf, Kh.	G.	VIII. 115 121	<i>see</i> el Mahjar, Kh.
Umm esh Shuqaf, Kh.	Jm.	IX. 164 124	Traces of foundations, wine-presses, rock-cut cisterns, surface pottery, rock-cut tombs and wells to east.
Umm esh Shuqaf, Kh.	He.	XII. 142 099	Mound with foundations, cisterns, caves, rock-cuttings.
Umm Sira, Kh.	He.	XII. 147 084	Ruins of settlement with foundations, extensive ruins, remains of buildings, column drums, cisterns and cistern heads, carved stone fragments, caves.
Umm es Sumeiqât	Re.	IX. 147 145	Foundations, rock-cut cisterns, cave, surface pottery.
Umm Sâr, Kh.	TK.	VI. 143 190	Low hill with remains of encircling wall and buildings, traces of vaults, column shafts, cisterns, reservoir near well.
Umm es Sâr, Kh.	Re.	IX. 149 143	Foundations of a church and other buildings, cisterns and presses cut in the rock.
Umm es Su'ûd, Kh. (Zab'a)	Bn.	V. 196 219	Rough stone enclosures and traces of walls.
Umm es Suweid, Kh.	He.	XII. 147 117	Foundations and walls of buildings, door posts, streets, cisterns, press with tessellated floor, ancient road, caves.
Umm es Suweida, Kh.	He.	XII. 136 108	<i>see</i> ed Duweir, Kh.
Umm Suwwâna, Kh.	Ba.	XV. 144 078	Foundations and heaps of flints, cisterns.
Umm es Suweilim, Kh.	He.	XII. 135 102	Foundations, caves, cisterns, well.
Umm Tâbân, Kh.	G.	XI. 111 106	Remains of rubble buildings and cisterns over extensive area, well and reservoir, marble column fragment, to east cemetery with painted tomb.
Umm Tal'a, Kh.	Jm.	X. 175 123	Ruined watch-tower, cistern
Umm et Tal'a, Kh.	He.	XII. 136 110	Foundations, cisterns, caves.
Umm et Tawâmin, Magharat	Jm.	IX. 152 126	Large cave, rock-cut pool.
Umm et Tawâqi, Kh.	Re.	VI. 149 163	Ruined masonry buildings, foundations, rock-cuttings.
Umm et Tawas	H.	IV. 147 224	<i>see</i> esh Shi', Kh.
Umm et Tawûs, Kh.	H.	IV. 146 223	Stone enclosure, rock-cut tomb, quarries, surface pottery.
Umm et Tin, Kh.	Ba.	XV. 152 051	<i>see</i> Rudeiha, Kh.
Umm et Tina, Kh.	Re./N.	VI. 148 165	Foundations, caves, cisterns, doorpost.
Umm Tôba, Kh.	Jm.	X. 172 126	Rock-cut cisterns, caves, columns, capitals.
Umm Tûnis, Kh.	He.	XII. 149 119	Remains of building with column fragments, vault below rock-cut cisterns, rock-cut tombs, caves, ancient road to west.
Umm 'Uleiyan	Ba.	XII. 132 092	Traces of a small ruin.
Umm el 'Umdân	Bn.	V. 200 210	Four Roman milestones.
Umm el 'Umdân, Kh.	A.	III. 175 259	Foundations of chapel with apse and of other buildings, rock-cut cistern.

Name of Site	Sub-District	Map Reference	Description
Umm el 'Umdân, Kh.	Jm.	IX. 151 126	Ruined walls of dressed stones, door-posts, press with uprights, rock-cut cistern, white mosaic pavement.
Umm el 'Umdân, Kh.	Re.	IX. 149 143	Ruined buildings, columns, door-posts, rock-cut caves and cisterns, well.
Umm el 'Umdân, Kh.	He.	XII. 147 118	Remains of several presses, cisterns, caves, ruined walls.
Umm el 'Uqûd, Kh.	Jm.	IX. 142 126	Foundations, cisterns, heaps of stones, caves.
Umm 'Usheish, Kh.	Ho.	XII. 144 113	see 'Usheish, Kh.
Umm el 'Ushûsh	G.	VIII. 120 135	Rubble foundations, reservoir.
Umm el Yamas	H.	IV. 146 216	see Miyamas.
Umm Zeid, Tell	J.	IV. 168 209	Traces of ruins.
Umm ez Zinât	H.	IV. 156 228	Foundations, rock-cut and carved tombs, caves, cistern, sarcophagus to east.
Umm Zubeila, Kh.	Jm.	IX. 143 127	see Beiyârat Bureij.
Umm ez Zuweitina, Magharat	He.	XIII. 172 109	Cave with traces of Stone Age occupation.
'Umrân, Kh.	Jm.	IX. 155 128	Heaps of stones, rock-cut press.
Umrashrash	Ba.	140 880	see Murashrash.
el 'Uneizliya, Kh.	Jm.	IX. 164 140	see Abu Mu'ammâr, Kh.
'Uqbur, Kh.	He.	IX. 143 120	Foundations, heaps of stones, cisterns, caves.
el 'Uqda, Kh. (Bir el Leimân)	Jm.	IX. 145 128	Ruined building over well, fallen walls of buildings, cisterns, rock-cut wine-press.
el 'Uqeiba, Kh.	S.	III. 198 260	Foundations, scattered hewn stones, wine-presses, enclosure.
el 'Uqûd, Kh.	N.	VII. 178 181	Ruined khan with remains of barrel vaults, traces of buildings, cistern, rock-cuttings.
'Urâd, Tell	He.	XV. 162 077	Artificial mound with traces of encircling wall, surface pottery, cisterns and caves.
el 'Ureima, Kh.	T.	III. 201 253	Artificial mound on natural hill, remains of walls and foundations, conduit cut in rock.
'Uris, Kh.	TK.	VI. 151 176	Ruined watch tower, cisterns, caves.
el 'Urma, Kh.	N.	VII. 180 173	Fortified hill top with tower at south end, caves and cisterns cut in rock scarp, drafted stones, surface pottery.
el 'Urqân, Kh.	He.	IX. 145 122	Foundations of building, architectural fragments.
'Urqân el Hamâm	N.	VII. 191 185	Walls, heaps of stones.
'Urqân el Khala	He.	XII. 140 115	Scattered masonry, caves, rock-cut cisterns, tombs.
'Urqân en Nimr	N.	VII. 201 177	Ruined fold, ancient caves.
el 'Useifriya, Kh. (Wabeidi, Kh.)	Ba.	XI. 103 091	Ruins of town with foundations of buildings, cisterns, marble capitals and fragments, well.
'Useila, Kh.	He.	XII. 143 088	Heaps of stones, foundations, caves, ancient road, olive press.
'Usheish, Kh.	He.	XII. 144 113	Traces of ruins, caves.
el 'Ushsha, Kh.	S.	III. 206 255	Heaps of stones, remains of reservoirs.

Name of Site	Sub-District	Map Reference	Description
'Uskur, Kh.	N.	VI. 163 177	Ruined buildings, vaults, cisterns; to west pool (Birket el 'Uskur).
el 'Uyûn, Kh.	N.	VI. 158 174	see Kafr Qari', Kh.
'Uyûn Khudeira	H.	IV. 143 226	Rock-cut shaft tombs.
el 'Uzeir	N.	VII. 177 174	see en Nabi 'Uzeir.
el 'Uzeirât	N.	VII. 177 174	Domed tomb, Samaritan inscription.
el 'Uzeiz, Kh.	He.	XII. 158 093	Ruins of town with traces of houses, streets, a building with columns, architectural fragments, presses.
el Wâd, Magharat	H.	IV. 147 231	Cave with prehistoric remains, rock-cuttings.
Wâd es Sarâsira, Kh.	He.	IX. 151 123	see es Sarâsira, Kh.
Waheidi, Kh.	Ba.	XI. 103 091	see el 'Useifriya, Kh.
el Wahshiya, Kh.	Ba.	XII. 124 106	Foundations, scattered stones, surface pottery.
Waldheim	H.	IV. 166 237	Rock-cut tombs and caves.
Waqiya, Kh. Tell	A.	II. 167 269	Remains of square rough stone building, rock-cut cisterns.
Waqqâs, Kh. (el Qadah)	S.	III. 203 269	Artificial mound, remains of buildings and walls, cut stones, cisterns, press.
el Wa'r, Tell	H.	IV. 160 232	Natural mound with traces of ancient building, caves, rock-cuttings, scattered pottery and stones.
Wa'r Mûsa	S.	III. 194 263	Ruined dolmens and cairns.
Wa'rat el Kabbâra (Deir Ghazzâla)	J.	V. 184 212	Dry-stone monument, megalithic tomb.
Wâsil, Kh.	TK.	VI. 159 195	Remains of building with coursed rough stone masonry, cisterns, cave, surface pottery.
el Watwat, Magharat	Re.	IX. 147 156	Cave with prehistoric remains.
el Wâwiya, Kh.	He.	XII. 146 116	Foundations of buildings, remains of press, cisterns, rock-cut caves with columbaria.
el Wâwiyât, Kh. (Umm er Riyâh, Kh.)	G.	VIII. 116 126	Rubble foundations and cisterns, surface pottery, heaps of stones.
el Wâwiyât, Tell	S.	I. 206 291	Small artificial mound with scattered stones.
el Waziya, Kh.	A.	II. 169 259	Ruined walls and vaults, cisterns, wine and olive presses, rock-cut tombs, caves, column base and capital.
el Weibida, Kh.	He.	XII. 140 100	Foundations, heaps of well-cut stones, caves, cisterns.
el Wibda, Kh.	He.	XII. 164 097	Walls, foundations.
el Wuheidi, Kh.	G.	XI. 098 094	Masonry well, ruined cisterns, heaps of pottery.
el Wureidât, Kh. (el Hamâm, Kh. Wadi)	T.	III. 196 248	Foundations, remains of a building with columns and dressed masonry, architectural fragments.
Ya'bad	J.	IV. 166 206	Foundations, rock-cut tombs, and cisterns. Jami' el Arba'in. Architectural fragments in village.
el Yahudiya	Ja.	IX. 140 160	Foundations, rubble vaults, tombs, sarcophagi, architectural fragments.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
el Yahudiya, Kh.	Jm.	IX. 163 196	Remains of fort, drafted masonry, rock-cut caves and tombs, column bases, cisterns, press.
Yājūr	H.	II. 156 241	Foundations, tombs with sarcophagi, glass, and pottery.
Yalū	Re.	IX. 152 139	Remains of building with vaults below (el Habs), artificial mound (Tell el Kauka), masonry well.
Yamma, Kh.	TK.	VI. 153 197	Ruined walls and cisterns beneath the village, rock scarp and traces of surrounding wall to north-west and west, ancient materials reused.
el Yāmūn	J.	V. 172 210	Village on ancient site, columns, capitals and bases at door of mosque, rock-cut tombs, architectural fragments, cisterns.
Ya'nūn, Kh.	A.	III. 171 255	Foundations of walls on partly artificial mound, tombs, well.
Yānūh	A.	III. 174 265	Foundations, olive press, cisterns, ancient material in village.
Yānūn, Kh.	N.	VII. 184 174	Ruined buildings of weathered masonry, rock-cut cisterns, lintels.
Yāqūq	T.	III. 195 254	Rock-cut tombs, cisterns, column fragments in village.
Yarda, Kh.	Re.	IX. 143 140	Foundations, tomb, column base, wine-press, surface pottery.
Yarda, Kh.	He.	XII. 143 111	Traces of buildings, well, columbarium, cave with flight of steps cut in the rock.
el Yarmūk, Kh.	He.	IX. 148 124	Fallen walls and foundations, artificial mound, cisterns, caves.
Yarza, Kh.	N.	VII. 191 191	Ruined walls, foundations, carved fragments, caves, tombs, cisterns.
Yasid	N.	VII. 176 189	Ruined mosque with inscription, minaret, vaulted building (Dar Abu Dhāhīr), vaults, cisterns, inscription at 'Umari mosque in village, rock-cut tombs.
Yāsin, Kh.	G.	VIII. 117 127	Ruined rubble cisterns, surface pottery.
Yāsūf	N.	VII. 173 168	Rock-cut tombs, Roman road, column shafts in village.
Yatta	He.	XII. 158 095	Village on ancient site, foundations, tombs, rock-cut presses, some architectural fragments.
Yaubak, Kh.	TK.	VI. 152 180	Foundations, cisterns.
Yāzūr	Ja.	IX. 132 159	Ruins of medieval castle (el Baubariya), walls, vaults, remains of church incorporated in mosque, tombs.
Yibna	Re.	VIII. 126 142	Artificial mound beneath village, Crusaders' church converted to mosque (el Kanisa), Maqām Abu Hureira, foundations, architectural fragments, bridge, ancient tombs to east.
Yirka	A.	III. 170 262	Village on ancient site, columns, architectural fragments, foundations, cisterns; pool to east.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Yirka, Kh.	A.	III. 170 261	Ruins of village, fallen masonry walls, cisterns.
Yubla	Bn.	V. 194 220	Foundations and heaps of stones in the village.
Yûnis, Tell	Re.	VIII. 125 156	Artificial mound, surface pottery, tiles, mosaic fragments and rubble.
ez Za'aq, Kh.	Ba.	XII. 137 090	Ruined walls, caves, cisterns.
Zab'a	Bn.	V. 196 219	see Umm es Su'ûd, Kh.
Zab'a, Kh.	Bn.	V. 200 217	Two artificial mounds (Tulûl esh Sheikh Sâlih); scattered ruins along stream to east.
(el 'Ish-sha, Kh., Tulûl esh Sheikh Sâlih)			
ez Zabâbida	J.	VII. 181 199	Vaulted building (el Baubariya), masonry foundations and coarse mosaics in village. Mosaic pavement in Latin Convent.
Zabbûd, Kh.	Jm.	IX. 158 135	Remains of crude buildings and watch-tower.
ez Zabîb, Kh.	S.	I. 202 291	Foundations of walls, heaps of stones.
Zabid, Kh.	J.	V. 174 214	Foundations, rock-cut cisterns, column fragments, voussoir, tesserae, heaps of stones.
Zâbud, Kh.	A.	III. 189 264	Ruined walls, cisterns, oil and wine presses, cave.
Za'farân, Kh.	Ba.	XI. 092 092	Rubble foundations and surface pottery.
ez Za'farân, Kh.	He.	XIII. 167 110	Foundations.
ez Zaghaniya, Kh.	Re.	IX. 144 150	Surface pottery, rock-cut and built cisterns.
Zahlûq	S.	III. 205 261	see Ghazâla, Kh.
ez Zahra, Tulûl	Bn.	V. 193 213	Two artificial mounds.
ez Zahrân, Kh.	TK.	VI. 158 191	Ruined walls in rough stone enclosure, cisterns, rock-cuttings; rock-cut tombs across valley.
Zakanda, Kh.	Jm.	XII. 164 119	Ruined walls, rock-cut tombs.
(Fâghûr, Kh.)			
Zakariya, Kh.	Re.	IX. 148 148	Remains of vaulted and other buildings, foundations, press, rock-cut cisterns, Maqâm.
Zakariya, Kh. Tell	He.	IX. 144 123	Artificial mound, cave with stairs.
ez Zakûr, Kh.	N.	VI. 149 172	Ruined walls, foundations, cisterns, rock-cuttings.
Zalafa	J.	IV. 168 217	Traces of ancient settlement in village, foundations, well.
Zammâra, Kh.	Ba.	XI. 106 089	see 'Ud, Kh.
ez Zanbaqiya	Bn.	V. 203 223	Artificial mound, foundations, door-posts, surface pottery.
el Gharbi, Tell			
ez Zanbaqiya	Bn.	V. 203 223	Artificial mound on natural hill, rough pavement on summit, surface pottery.
esh Sharqi, Tell			
Zanû', Kh.	He.	IX. 150 125	Extensive site with remains of buildings, cisterns, caves, column fragments, carved lintel, press, rock-cuttings; ancient roads to Kh. 'Alyâ and Beit Nattif.
Zânûta, Kh.	He.	XII. 149 086	Ruins of small town, tower, drafted masonry, building with pilasters; inscribed stones, cisterns.

Name of Site	Sub-District	Map Reference	Description
Za'qûqa, Kh.	He.	XII. 147 112	Foundations, part of an ancient building, built to a modern house, rock-cut caves, wine-press.
Zari', Kh.	Ba.	XI. 118 093	Scattered stones, cisterns.
ez Zarnûq	G.	VIII. 118 133	see Dhahrat et Tâta.
ez Za'tar, Kh.	Jm.	IX. 156 133	Fallen walls, rock-cut cisterns, caves, millstone.
ez Za'tar, Kh.	RA.	IX. 161 145	see el Qureina, Kh.
Za'tara, Kh.	J.	V. 179 204	Foundations.
Za'tut, Kh.	He.	XIII. 167 097	Walls, heaps of stones.
Zâwiya	J.	VII. 172 198	Rock-cut tombs.
Zâwiya	N.	IX. 154 167	Ancient foundations in the village.
ez Zâwiya, Kh.	A.	III. 177 271	Ruins of houses, doorposts, olive-press, cisterns, rock-cut tombs.
Zeifasfiya, Kh.	Re.	IX. 145 156	Foundations of apsidal building, cisterns, press, rock-cut tombs, vaulted cave, reservoir with tessellated floor.
ez Zeit, Kh.	RA.	IX. 160 143	Traces of ruins, walls, press caves and cisterns.
Zeitâ	TK.	VI. 155 199	Columns and carved stones at mosque and at Maqâm esh Sheikh Suleimân: rock-cut tombs and wine press east of village.
Zeitâ	G.	XI. 104 102	Remains of rubble cisterns and foundations.
Zeitâ	G.	XI. 100 108	Foundations, rubble cisterns, two vaulted chambers.
Zeitâ	G.	XI. 111 109	Rubble foundations, cisterns, well, surface pottery.
Zeitâ, Kh.	G.	XI. 108 106	Ruined reservoirs and surface pottery.
Zeitâ, Kh.	He.	XII. 134 115	Artificial mound, foundations, scattered stones and surface pottery.
Zeitâ, Kh.	He.	XII. 139 103	Ruined walls, caves, cisterns, rock-cut tombs.
ez Zeitâwiya, Kh.	Ba.	XI. 096 092	Traces of foundations, surface pottery.
Zeitûn er Râma, Kh.	A.	III. 188 259	Ruined walls, door-posts, rock-cut chamber and shaft with niches.
Zeitûna, Kh.	H.	IV. 143 218	Small artificial mound, rubble masonry, surface pottery.
ez Zib	A.	II. 160 171	Artificial mound, traces of foundations and floors, cisterns; rock-cut tombs on shore to south (el Buqbaq) and on ridge to south east (er Ras).
Zibda	J.	IV. 162 206	Foundations, cisterns, tombs.
ez Zibda, Kh.	H.	II. 159 249	Low mound with traces of ruined building.
Zibda, Kh.	Re.	IX. 150 151	Ruined buildings and walls, rock-cut cisterns, press with uprights; to west column shafts (ed Deir).
ez Zibdiya, Tell	A.	II. 166 274	Heaps of rough hewn stones, cisterns, uprights of press.
Zif, Kh.	He.	XII. 163 095	Extensive ruins, ruined walls, foundations, cistern, caves, vaulted building.

<i>Name of Site</i>	<i>Sub-District</i>	<i>Map Reference</i>	<i>Description</i>
Zif, Tell	He.	XII 163 098	Mound partly artificial, foundations and scattered masonry, quarry, tombs cut in the rock.
Zikhron Ya'aqov	H.	IV. 146 220	Foundations of early settlement in the village and to east, rock-cut cisterns and tombs.
Zikrîn, Kh.	He.	XII. 137 119	Foundations, caves, cisterns, tombs cut in the rock, heaps of stones.
Zir'in	J.	V. 161 218	Remains of medieval vaulted building and chapel, foundations, cisterns, wine presses, caves.
ez Zubâla, Kh.	Ba.	XII. 126 091	Remains of walls, cisterns, press, architectural fragments, well, caves.
ez Zubeiya, Kh. Zubûba	He. J.	XII. 141 117 V. 171 217	see Umm ed Daraj, Kh. Ruins of early settlement beneath village, rock-cut cisterns, well, caves.
Zuheiliqa, Kh.	Ba.	XI. 115 094	Rubble cisterns and surface pottery over extensive area, well.
Zuq el Fauqâni (Zuq el Haj)	S.	I. 206 294	Foundations of walls, olive press.
Zuq et Tahtâni	S.	I. 206 291	Artificial mound, foundations, dry stone enclosures, surface pottery.
ez Zuqqûma, Tell	N.	VII. 196 196	Artificial mound.
ez Zuttiya, Magharat	T.	III. 198 252	Cave with prehistoric remains.
Zuweinita, Kh.	A.	III. 171 269	Heaps of stones, cisterns.
ez Zuweira, Rujm	Ba.	XVI. 173 071	Ruins of square fort with corner towers.
ez Zuweira et Tahta, Rujm	Ba.	XVI. 183 062	Ruined watch-tower.
Zuweirita, Kh.	Ba.	XV. 148 051	Ruined rectangular building, cistern.

GOVERNMENT OF PALESTINE.

Telegram: "ANTIQUE"
Telephone: JERUSALEM 543.

ALL COMMUNICATIONS SHOULD BE
ADDRESSED TO THE DIRECTOR

In reply please quote

ATQ/689.

DEPARTMENT OF ANTIQUITIES

P. O. B. 586
JERUSALEM.

14th July, 1938.

The Engineer in Charge,
Public Works Department,
Nablus.

Subject :- Protection of
Historical Sites.

Thank you for your letter No.1/14/3
of 7th July, 1938, and enclosed plan:

I attach a list of historical sites
in the immediate vicinity of roads under construction
or to be constructed.

I should be grateful if you would
warn your foreman against taking away stones
from these sites or disturbing them in any
other way.

(Signed) R. W. HAMILTON

A/Director.

Copy to: District Officer, Nablus.
District Officer, Tulkarem.
District Officer, Jenin.